

Hydrogeological Assessment, Strohvest Subdivision, Township of Wellesley, Ontario

FINAL REPORT

June 2024

Prepared for:

Strohvest Ontario Inc. 6770 86 Line Elmira, ON N3B 2Z2

Prepared by:

Stantec Consulting Ltd. 100-300 Hagey Boulevard Waterloo, ON N2L 0A4

First Submission: January 2022

File No. 161413217

Sign-off Sheet

This document entitled Hydrogeological Assessment, Strohvest Subdivision, Township of Wellesley, Ontario was prepared by Stantec Consulting Ltd. ("Stantec") for the account of Ron Stroh (the "Client"). Any reliance on this document by any third party is strictly prohibited. The material in it reflects Stantec's professional judgment in light of the scope, schedule and other limitations stated in the document and in the contract between Stantec and the Client. The opinions in the document are based on conditions and information existing at the time the document was published and do not take into account any subsequent changes. In preparing the document, Stantec did not verify information supplied to it by others. Any use which a third party makes of this document is the responsibility of such third party. Such third party agrees that Stantec shall not be responsible for costs or damages of any kind, if any, suffered by it or any other third party as a result of decisions made or actions taken based on this document.

Prepared by	
,	(signature)
Grant Whitehead, MES, P.G Senior Hydrogeologist	eo. (Limited)
Reviewed by	(signature)
Roger Freymond, P.Eng. Senior Hydrogeologist	

pk w:\active\161413217\05_report_deliv\deliverable\ver.2_second_submission\rpt_161413217_strohlands_hydrogeology_20240628_second.submission_final.docx



Table of Contents

1.0	INTROD	UCTION	1.1
2.0	PHYSIC	AL SETTING	2.1
2.1	PHYSIO	GRAPHY, SURFACE WATER FEATURES, AND TOPOGRAPHY	2.1
2.2	REGION	AL GEOLOGY AND HYDROGEOLOGY	2.1
2.3	SOURCI	E WATER PROTECTION	2.3
	2.3.1	Ontario Clean Water Act	
	2.3.2	Region of Waterloo Official Plan	2.5
3.0	METHO	DOLOGY	3.1
3.1		DLE DRILLING	
3.2	MONITO	RING WELL INSTALLATION AND DEVELOPMENT	3.2
3.3	GROUN	DWATER LEVEL MONITORING	3.2
3.4	HYDRAU	JLIC RESPONSE TESTING	3.3
3.5	GROUN	DWATER SAMPLING AND QUALITY TESTING	3.3
	3.5.1	Onsite Monitoring Wells	
	3.5.2	Offsite Private Wells	
3.6	TEST PI	T EXCAVATIONS	3.5
4.0	LOCAL GEOLOGY AND HYDROGEOLOGY		
4.1		GY AND HYDROSTRATIGRAPHY	
4.2		GEOLOGY	
	4.2.1	Groundwater Levels	
	4.2.2	Groundwater Flow	
	4.2.3 4.2.4	Infiltration Potential	
		Groundwater Quality	
5.0		S ASSESSMENT AND MITIGATION MEASURES	
5.1		BALANCE AND INFILTRATION	
5.2		DWATER DEWATERING	
	5.2.1	Construction Dewatering	
- 0	5.2.2	Permanent Dewatering	
5.3		E WATER PROTECTION	
5.4			
5.5		ONTAINMENT AND RESPONSE	
6.0	CONCL	JSIONS	6.1
7.0	REFERE	NCES	7.1



LIST OF APPENDICES

APPENDIX A: DEVELOPMENT PLANS

APPENDIX B: FIGURES

Figure 1: Location Plan
Figure 2: Physiography
Figure 3: Topography
Figure 4: Surficial Geology

Figure 5: Source Water Protection

Figure 6: Regional Wellhead Protection Sensitivity Areas

Figure 7: Hydrographs - Monitoring Wells

Figure 8: Hydrographs MW01-21, MW02-21, and MW03-21 Hydrographs MW04-21, MW05-21, and MW06-21

Figure 10: Cross-Section A-A'
Figure 11: Cross-Section B-B'
Figure 12: Groundwater Flow
Figure 13: Piper Diagram

APPENDIX C: TABLES

Table 1: Monitoring Well Construction Details

Table 2: Groundwater Level Data - Monitoring Wells

Table 3: Infiltration Estimates

Table 4: Groundwater Quality Results - Onsite Monitoring Wells Table 5: Groundwater Quality Results - Offsite Private Wells

APPENDIX D: REGIONAL GROUNDWATER MAPPING

APPENDIX E: SOURCE WATER PROTECTION PLAN MAPPING

APPENDIX F: REGION OF WATERLOO SOURCE WATER PROTECTION

LAND USE CATEGORIES

APPENDIX G: BOREHOLE LOGS

APPENDIX H: HYDRAULIC CONDUCTIVITY TESTING SOLUTIONS

APPENDIX I: LABORATORY CERTIFICATES OF ANALYSIS

APPENDIX J: TEST PIT PHOTOGRAPHS



Abbreviations

AMSL above mean sea level

AO Aesthetic Objective

ASTM American Society for Testing and Materials

BGS below ground surface

Client Ron Stroh

EASR Environmental Activity and Sector Registry

GRCA Grand River Conservation Authority

GUDI Groundwater under the direct influence of surface water

HDPE High density polyethylene

HVA Highly Vulnerable Area

IPZ Intake Protection Zone

LERSPC Lake Erie Region Source Protection Committee

m meters

m³ cubic meters

m/s meters per second

m³/year cubic meters per year

MECP Ministry of the Environment, Conservation and Parks

MOH Medical Officer of Health

ODWQS Ontario Drinking Water Quality Standards

OG Operational Guideline



i

OGS Ontario Geological Survey

PVC Polyvinyl chloride

PTTW Permit to Take Water

SGRA Significant Groundwater Recharge Area

SPP Source Protection Plan

Stantec Stantec Consulting Ltd.

Subject Lands Plan 1148, Part Lot 80, Registered Plan 58R-3548, Part 1, Township

of Wellesley, Regional Municipality of Waterloo

WHPA Well Head Protection Area



Introduction June 2024

1.0 INTRODUCTION

Strohvest Ontario Inc. (Applicant) retained Stantec Consulting Ltd. (Stantec) to complete a hydrogeological assessment of a land parcel located to the north of Gerber Road in the Village of Wellesley. The Lands Owned by the Applicant (Applicant Lands) cover an area of 16.4 hectares (ha); however, the portion of these lands currently being proposed for development at this time (Phase 1) cover an area of 10.2 ha and are legally described as Plan 1148, Part Lot 80, Registered Plan 58R-3548, Part 1, Township of Wellesley, Regional Municipality of Waterloo (Subject Lands) (Figure 1). The Subject Lands are bounded to the south by Gerber Road, to the west and north by active agricultural lands, and to the east by existing low-rise residential development. The Subject Lands will be developed with full municipal servicing.

This hydrogeological assessment has been prepared to support Zoning By-law Amendment and Draft Plan of Subdivision applications, with proposed development for the Subject Lands to consist of up to 169 residential units comprised of 57 single-detached units, 34 semi-detached units, 54 townhouse units, and either an additional 12 townhouse units or up to 24 apartment units on one block (Appendix A). A stormwater management block is currently planned for the south end of the Subject Lands fronting Gerber Road.

The hydrogeological work performed for the Subject Lands follows the *Conservation Authority Guidelines* for *Development Applications - Hydrogeological Assessment Submissions* (2013), as well as drawing upon Stantec's experience with the completing of hydrogeological assessments in support of land development projects throughout the Regional Municipality of Waterloo. Specifically, the objectives of the hydrogeological assessment are to:

- Characterize the geological and hydrogeological conditions at the Subject Lands, including identifying hydrostratigraphic / aquifer units, seasonal positioning of the groundwater table, groundwater flow regimes, groundwater recharge and/or discharge zones / features, and the hydraulic conductivity of the subsurface deposits.
- Identify local groundwater uses near the Subject Lands (i.e., municipal and private water well uses)
 and evaluate the potential for quantity and/or quality interference to these existing groundwater uses
 because of the proposed site development.
- 3. Assess whether proposed buildings and associated servicing infrastructure on the Subject Lands will intercept the groundwater table, evaluative the potential need for temporary construction dewatering and/or installation of a permanent drainage system (for long-term dewatering), and identify what mitigation measures could be employed at the site to minimize any potential disturbances to the groundwater flow system and, subsequently, groundwater availability to local water supply wells and surface water features.



Introduction June 2024

- 4. Conduct a pre- and post-development water budget assessment to evaluate potential changes on local groundwater recharge.
- 5. Evaluate whether proposed land use activities conform to Source Water Protection requirements as stipulated in the Clean Water Act, S.O. 2006, Chapter 22.

The report is arranged into seven sections, including this introduction (Section 1.0). Section 2.0 presents the physical setting of the Applicant Lands at a regional scale, with Section 3.0 outlining the methods utilized to evaluate existing hydrogeological conditions within these lands. Section 4.0 presents the results of the hydrogeological field investigation and Section 5.0 provides an assessment of potential hydrogeological constraints associated with the proposed Site development and recommended mitigation measures to address these constraints. Report conclusions and references are listed in Sections 6.0 and 7.0, respectively.

Appendix A provides a copy of the Draft Plan of Subdivision, with all figures and tables referenced in this report being presented in Appendices B and C, respectively. Appendices D to J include Regional Groundwater Mapping, Source Water Protection Plan Mapping, Region of Waterloo Source Water Protection Land Use Categories, Borehole Logs, Hydraulic Conductivity Analytical Solutions, Laboratory Certificates of Analysis, and Test Pit Photographs, respectively.



Physical Setting June 2024

2.0 PHYSICAL SETTING

2.1 PHYSIOGRAPHY, SURFACE WATER FEATURES, AND TOPOGRAPHY

The Applicant Lands are situated within the physiographic region referred by Chapman and Putnam (1984) as the Stratford Till Plain, with these lands sitting upon undrumlinized till plains composed predominantly of silty clay. Spillways lie immediately to the south of the Site (Figure 2).

The Applicant Lands are located within the Bamberg Creek-Nith River subwatershed. As shown in Figure 2, the closest surface water features to the Applicant Lands include Wellesley Pond and Firella Creek, which lie approximately 250 m to the northeast of the site, and a tributary positioned approximately 180 m to the southwest of the site. These previously mentioned watercourses flow into the Nith River, which generally flows southward and eventually discharges to the Grand River near Paris. Two wetlands exist to the northwest of the Applicant Lands: Firella Creek Swamp (660 m from site) and the Wellesley West Wetland Complex (830 m from site).

In the region containing the Applicant Lands, a topographic high point of 368 m AMSL exists near the T-intersection of Queens Bush Road and Hutchison Road, with the lands sloping to the east, south and west towards Wellesley Pond, Firella Creek, the Nith River, and the tributaries associated with these watercourses from this point (Figure 3). In the Applicant Lands (Figure 1), a surface water drainage divide is shown to run in a southwest to northeast direction in the northern portion of the property. The lands slope from an elevation of 363.5 m AMSL at the divide to 360.2 m AMSL near MW03-21, with this area of the property draining overland to the north towards Queens Bush Road. To the south of the divide, the lands slope from an elevation of 363.5 m AMSL to 353.5 m AMSL along Gerber Road, with most of the Applicant Lands (including the full area of the Subject Lands) draining overland to the south to an existing culvert that crosses the road and ultimately discharges to the Nith River. Some external flows also enter the Applicant Lands through the existing agricultural fields located to the west of the property.

2.2 REGIONAL GEOLOGY AND HYDROGEOLOGY

The Applicant Lands are located immediately to the north of the Waterloo Hills (Figure 2), also commonly known as the Waterloo Moraine, a kame moraine formed between ice lobes extending from the Lake Ontario-Erie, Huron, and Georgian bay areas (Karrow 1993). Numerous advances and retreats of the ice lobes during the Wisconsinan glaciation resulted in a complex deposit of ice-contact and glacial outwash sands and gravels separated by silt- and clay-rich tills. The conceptual hydrogeologic model for the Waterloo Moraine comprises four main aquifers and aquitards after Terraqua Investigations Ltd. (1995), which was broken down further into 19 hydrostratigraphic units after Bajc and Shirota (2007). The model generally does not include more recent deposits shown on surficial geology mapping such as modern alluvial deposits (Figure 4, unit 19), which are found in wetlands and creek / river valleys.



Physical Setting June 2024

The hydrostratigraphic units expected to be encountered in the subsurface where the Applicant Lands occur are described below. The units are described from ground surface downward, with Bajc and Shirota (2007) unit names shown in parentheses.

Outwash Deposits (AFA2): Referred to as the Grand River glaciofluvial deposits and equivalent aquifers that consist of well bedded sands and gravels restricted to the valleys of the Conestogo, Grand, and Nith rivers (Figure 4, Unit 7).

Aquitard 1 (ATB1): Surficial and spatially discontinuous glacial till units found predominantly along the flanks of the Waterloo Moraine. Along the western flank of the moraine Aquitard 1 corresponds to the Mornington Till (silty clay till; Figure 4, Unit 5d), Stratford Till (sandy silt till; Figure 4, Unit 5b), and Tavistock Till (clayey silt till); whereas along the eastern flank of the Moraine this unit corresponds to the Upper Maryhill (clay till) and Port Stanley Tills (sandy to silty till) (Bajc and Shirota, 2007). Aquitard 1 is characterized by low permeability and forms a relatively impermeable barrier that effectively limits the downward movement of groundwater to the deeper aquifer systems.

Aquifer 1 (AFB1/ATB2/AFB2): This hydrostratigraphic unit represents the main water supply aquifer in the core areas of the Waterloo Moraine. Depending on the depositional environment, the composition of Aquifer 1 varies from a layered silt and fine sand to coarse sand and gravel. Throughout the core areas of the moraine, Aquifer 1 corresponds to a thick, laterally extensive sand and/or gravel aquifer overlying Aquitard 2 and is often exposed at surface. In some areas, Aquifer 1 is interpreted to be bisected by the Middle Maryhill Till (ATB2), which effectively separates Aquifer 1 into two units: AFB1 and AFB2. Where Aquifer 1 is overlain by Aquitard 1, the aquifer behaves as a confined to semi-confined aquifer system. Where Aquitard 1 is absent and the sediments of Aquifer 1 are exposed at ground surface, these deposits represent an important source of groundwater recharge to this aquifer system.

Aquitard 2 (ATB3): Aquitard 2 corresponds to the Lower Maryhill Till, an overconsolidated, stony, clayey silt till, that represents one of the primary regional hydrostratigraphic units (Bajc and Shirota, 2007). Along the flanks of the Waterloo Moraine, the Lower Maryhill Till is often found to be discontinuous.

Aquifer 2/3 (AFB3/AFD1): Associated with reworked layers of gravel, sand and silt associated with the Catfish Creek Till (Aquifer 2) and Pre-Catfish Creek sand and gravel (Aquifer 3), with these aquifers being separated by the Catfish Creek Till (stony, silty to sandy till) (Aquitard 3, ATC1/ATC2). These units are discontinuous through the Waterloo Moraine. The municipal production wells of the Wellesley Wellfield (i.e., WY1, WY5 and WY6; Figure 5) are partially screened within these aquifer units (LERSPC, 2021a).

Bedrock: Bedrock in this region is comprised of limestone, dolostone, and sandstone corresponding to the Bois Blanc Formation (Armstrong and Dodge 2007). According to available MECP water well records, bedrock is encountered between 295 m AMSL and 307 m AMSL. Municipal production wells in Wellesley are screened partially within this unit (LERSPC, 2021a).



Physical Setting June 2024

The regional study completed by the Grand River Conservation Authority (2001) indicates that groundwater flow through the overburden deposits of the unconfined aquifer (i.e., using static water levels in wells constructed less than 25 m deep) is generally from northwest to southeast and moves towards the Nith River, which is identified as a potential groundwater discharge feature (Figure ST-7, Appendix D).

Mapping created using the Grand River Information Network (GRIN) (GRCA, 2021) indicates that annual groundwater recharge rates across the Applicant Lands range between 100 to 200 mm/year, for an average of 139 mm/year (Figure D-1, Appendix D), in those areas where silty to sand till is mapped as occurring at ground surface (Figure 4). However, in the southern portion of the Applicant Lands where silty to clayey till is exposed at ground surface (Figure 4), annual recharge rates are identified as being lower with values ranging from 50 to 100 mm/year, for an average of 52 mm/year (Figure D-1, Appendix D).

2.3 SOURCE WATER PROTECTION

2.3.1 Ontario Clean Water Act

As established under the Ontario *Clean Water Act*, 2006, S.O., 2006, c. 22, source protection areas and associated land use restrictions exist for all municipal drinking water sources located throughout the Lake Erie Source Protection Area.

The Ontario Ministry of the Environment (now the MECP) introduced the *Clean Water Act* as a means of ensuring the protection of drinking water sources in the Province. The *Clean Water Act* requires that a detailed Assessment Report be prepared for each municipal drinking water system, with this Assessment Report incorporating numerous components as outlined in the document "Technical Rules: Assessment Report, *Clean Water Act* (2006), November 16, 2009". This legislation provides a basic framework for communities to follow in developing an approach to protecting their municipal water supplies, with the key components of this approach being as follows:

- Identification and assessment of risks to the quality and quantity of municipal drinking water sources and determine which risks are significant and require immediate action, which risks need monitoring to ensure they do not become significant, or which pose low to negligible risk. This information is presented in a detailed Assessment Report, with the content of this report consisting of (i) the defining of Well Head Protection Areas (WHPA) for groundwater drinking water sources and Intake Protection Zones (IPZ) for surface water drinking water sources, (ii) completion of a vulnerability assessment for each WHPA and IPZ, and (iii) identification of drinking water issues and threats.
- Preparation of a Source Protection Plan (SPP) that addresses identified drinking water threats, particularly significant threats.
- Carry out the SPP through existing land use planning and regulatory requirements.
- Perform ongoing monitoring and reporting to measure the effectiveness of the actions taken to protect drinking water sources and ensure that they are protected in the future.



Physical Setting June 2024

Within the Lake Erie Source Protection Area and specifically the Grand River Source Protection Area, the MECP has designated the following types of vulnerable areas that apply to drinking water sources:

Wellhead Protection Area (WHPA): an area delineated on the ground surface that represents the capture zone for the underlying aquifer in which a given municipal well draws its water. The zone represents the total amount of time it would take for groundwater to flow through the aquifer system and reach the intake of a given municipal well. The zones are defined as follows:

- WHPA-A: 100 m radius around the municipal well.
- WHPA-B: Horizontal time-of-travel to the municipal well is two years or less.
- WHPA-C: Horizontal time-of-travel to the municipal well is equal to or less than five years and greater than two years.
- WHPA-D: Horizontal time-of-travel to the municipal well is equal to or less than 25 years and greater than five years.
- WHPA-E: Area where groundwater is under the direct influence of surface water (GUDI), where
 horizontal time-of-travel of this groundwater from the surface water body to the municipal well is two
 hours or less.

The water supply for the Village of Wellesley is obtained from production wells of the Wellesley Wellfield, which are located approximately 250 m to the east of the Applicant Lands (Figure 5). These wells draw their groundwater supply from Aquifer 2 (AFB3) and Aquifer 3 (AFD1), and potentially from the Bedrock Aquifer (Paragon Engineering Limited 1991; LERSPC, 2021a; MECP, 2021a). Based on a review of the online MECP Source Water Protection Information Atlas (2021b) and as shown in Figure 5, most of the Applicant Lands are located in the WHPA-B of the Wellesley Wellfield, with the northern and southern extents of these lands occurring in WHPA-C and WHPA-D of the same wellfield. The vulnerability scoring for WHPA-B to WHPA-D that intercepts the Applicant Lands is 6 (Map A1, Appendix E).

Intake Protection Zone (IPZ): An IPZ is a zone established around a drinking / surface water intake in which a spill or leak may get to the intake too quickly for the operators of the municipal water treatment plant to shut the intake down until the pollutant passes by. These zones also include land adjacent to streams and storm sewers where surface water runoff can quickly reach the intake. Based on a review of the online MECP Source Water Protection Information Atlas (2021b) and as shown in Figure 5, the proposed Applicant Lands do not intercept any surface water system IPZs.

Significant Groundwater Recharge Area (SGRA): Groundwater recharge represents the proportion of precipitation and/or surface water run-off that infiltrates to the subsurface and reaches the groundwater table. Recharge areas are classified as "significant" when they supply more water to an aquifer used as a drinking water source than the surrounding area. The volume of water that infiltrates to the subsurface is largely influenced by site topography, the physical properties of the soil, and land cover characteristics. The LERSPC (2021a) defines a significant groundwater recharge area (SGRA) to be an area where the annual recharge rate is greater than the average plus 15% or more across the source protection region.



Physical Setting June 2024

As per the Assessment Report (LERSPC, 2021a), lands in the Grand River Source Protection Area (i.e., the Grand River Watershed) are deemed to be SGRA when the annual recharge rate is greater than 176 mm/year. Based on a review of the online MECP Source Water Protection Information Atlas (2021b) and as shown in Figure 5, the Applicant Lands are not designated as SGRA.

Highly Vulnerable Aquifer (HVA): Defined as subsurface, geologic formations that are sources of drinking water, which could be easily affected by the release of pollutants on the ground surface. The HVA is identified using variables that include depth to the aquifer, physical properties of the overlying soil and/or rock, and the aquifer composition. In general, an HVA will consist of granular aquifer materials (i.e., sands and gravels) that are exposed near the ground surface and where a relatively shallow water table is present. Based on a review of the online MECP Source Water Protection Information Atlas (2021b) and as shown in Figure 5, the Applicant Lands do not occur in an area designated as HVA.

Water Quantity Vulnerable Area: Water quantity vulnerable areas are determined through a tiered process of water budget analyses as set out in the Technical Rules under O. Reg. 287/07. WHPA-Q is defined as an area where an activity can occur and pose a threat to drinking water quantities. Any activity that takes water without returning it to the same source or an activity which reduces recharge may be a threat in WHPA-Q. Based on a review of the online MECP Source Water Protection Information Atlas (2021b) (Figure E-1, Appendix E), the Applicant Lands do not occur in an area designated as WHPA-Q.

2.3.2 Region of Waterloo Official Plan

In the Region of Waterloo, sensitivity rankings were developed for the municipal well fields, with these rankings being based on modeled time-of-travel capture zones and the vulnerability of the groundwater to contamination at each individual well head. A Sensitive Area 1 designation represented an area surrounding the well head that has the highest potential for groundwater contamination, whereas a Sensitivity Area 8 designation represents the lowest. As per the Region of Waterloo Official Plan (ROP) (2015), Wellhead Protection Sensitivity Areas (WPSA) are categorized under eight categories (WPSA 1 to WPSA 8). This range of classifications allows for varying degrees of management relative to the vulnerability of the underlying groundwater to contamination, the importance of the subject well to the capacity of the municipal drinking-water supply system, and the length of time groundwater in the WPSA will take to reach the municipal well.

As shown in Figure 6, the Applicant Lands occur in what appears to be the WPSA of the Wellesley Wellfield. The specific WPSA include:



Physical Setting June 2024

WPSA-4:

Where covering the Applicant Lands, this WPSA indicates that groundwater takes less than two years to flow to the intake of a given municipal production well. As per the ROP (2015) Schedule B, Category 'A' (Very High Risk) land uses are not permitted in this zone, whereas Category 'B' (High Risk), 'C' (Moderate Risk) and 'D' (i.e., underground parking garages, individual wastewater treatment systems, pipelines, sewers, stormwater management ponds (or other ponds), and plans of subdivision or vacant land condominiums) land uses may be permitted subject to further study in accordance with Policy 8.A.4¹. A copy of Schedule B from the ROP (2015) that lists the various land uses associated with each Category is provided in Appendix F.

WPSA-5:

Where covering the Applicant Lands, this WPSA indicates that groundwater takes between two to 10 years to flow to the intake of a given municipal production well. Category 'A' land uses are not permitted in this zone, nor are Category 'B' and 'C' land uses located outside of the Built-Up Area (note that the Applicant Lands do not fall within this area). However, Category 'B' and 'C' land uses already permitted by existing Area Municipal official plans may be permitted subject to further study in accordance with Policy 8.A.4. Category 'D' land uses and plans of subdivision or vacant land condominiums may also be permitted subject to further study in accordance with Policy 8.A.4.

¹ Policy 8.A.4 states that studies submitted in support of a development application must be completed in accordance with the Regional Implementation Guideline for Source Water Protection Studies to the satisfaction of the Region. Studies submitted by the owner/applicant will demonstrate that the proposed use will not negatively impact the quantity and/or quality of drinking-water resources in Source Protection Areas for the development application to receive approval.

Methodology June 2024

3.0 METHODOLOGY

Section 3.0 provides the methodology used to obtain the data required to complete the hydrogeological investigation. The key components of the investigation included:

- borehole drilling
- · installation and development of monitoring wells
- monitoring of groundwater levels
- performing hydraulic response (hydraulic conductivity) testing
- collection of groundwater samples from onsite monitoring wells and offsite private wells for quality testing
- test pit excavations.

The methodology for these tasks is described in Sections 3.1 to 3.6 below.

3.1 BOREHOLE DRILLING

From May 5 to 6, 2021, boreholes were advanced at eight locations across the Applicant Lands (Figure 1) using a CME track-mounted drilling rig equipped with hollow-stem augers operated by a licensed drilling subcontractor (Geo-Environmental Drilling Inc.). The depth of the boreholes extended to 5.2 m to 6.7 m below ground surface (BGS), with six of the eight boreholes being equipped with a single monitoring well (i.e., MW01-21 to MW06-21). Soil sampling occurred using a 0.6 m long stainless-steel split spoon sampler at 0.75 m (2.5 feet) intervals for the first 3.6 m (12 feet) of drilling depth, followed by sample collection occurring at approximately every 1.5 m (5 feet) to the termination depth of the borehole. Stantec personnel directed the drilling, soil sampling operations, and logging of the borehole stratigraphy. The borehole logs contain descriptions (where relevant and possible) of soil type, texture, colour, structure, consistency, plasticity, moisture content, and other visual and olfactory observations as per the procedures outlined in American Society for Testing and Materials (ASTM 2009) specification D2488-09a. Overall, the boreholes were strategically positioned throughout the Applicant Lands to confirm shallow soil conditions, seasonal groundwater depths, and the direction of horizontal groundwater flow. Further details on the borehole drilling and monitoring well installations are provided in the Geotechnical Investigation Report (Stantec, 2021). Copies of the borehole logs are provided in Appendix G.



Methodology June 2024

Between October 16 and 17, 2023, an additional borehole was advanced directly adjacent to MW05-21, with the purpose of this borehole to confirm the potential depth of Aquitard 1 (ATB1) and whether groundwater monitoring results obtained from the initial investigation were indicative of a perched groundwater system. Stantec retained a licensed drilling contractor (Aardvark Drilling Inc.) on behalf of the Applicant to drill the borehole. Aardvark Drilling Inc. drilled the borehole to a depth of approximately 25 m BGS (i.e., elevation of 337 m AMSL) using a CME 850 track-mounted drilling rig equipped with hollow-stem augers. Soil sampling and logging of the borehole occurred using the same previously mentioned techniques. A copy of the borehole log is provided in Appendix G

3.2 MONITORING WELL INSTALLATION AND DEVELOPMENT

Stantec observed the installation of monitoring wells in six of the eight initial boreholes advanced throughout the Applicant Lands (i.e., MW01-21 to MW06-21 between May 5 and 6, 2021) and the supplementary borehole drilled in October 2023 (i.e., MW105-23), with the wells being installed to allow for the measurement of groundwater levels / elevations, completion of in-situ hydraulic conductivity testing, and/or the collection of groundwater samples for quality analysis. The drilling contractor installed the monitoring wells adhering to the construction requirements as outlined under Ontario Regulation 903 (O. Reg. 903) (MECP, 1990). Installation details for each of the monitoring wells are summarized in Table 1. Each monitoring well is constructed of 50 mm inside diameter, Schedule 40 polyvinyl chloride (PVC) pipe, having a No. 10 slot screen (0.01-inch slot) measuring 3.0 m in length. Backfilling of the screened interval consisted of silica sand to a height of approximately 0.3 m above the top of screen, followed by granular bentonite to ground surface prevent a hydraulic connection from occurring between the screened formation and overlying soils. The completion of each monitoring well involved encasing the pipe stick-up within a lockable steel casing. Stantec Geomatics surveyed the ground surface and top-ofpipe elevations at each monitoring well location to a geodetic benchmark using Global Positioning System (GPS) having a spatial accuracy of ± 0.03 m and ± 0.02 m in the vertical and horizontal plane, respectively.

Following installation, Stantec developed each monitoring well to remove drilling fluids, solids, or other particulates that may have been introduced during drilling. Stantec purged each monitoring well using dedicated 16 mm inside diameter high density polyethylene (HDPE) tubing connected to a D-25 Waterra™ foot valve. Stantec purged ten standing column volumes from each monitoring well to clear out the drilling residues and any fine-grained sediments to establish a proper hydraulic connection with the native saturated material.

3.3 GROUNDWATER LEVEL MONITORING

Stantec manually measured water levels in the monitoring wells multiple times between June 2021 and June 2024 using a battery operated Heron™ water level meter. Equipped with an electrode connected to a graduated polyethylene tape, Stantec used the meter to measure the depth to water by slowly lowering the electrode into the well until the buzzer sounded. Stantec recorded the water level measurements in meters to the nearest 0.01 m. A summary of the manual water level measurements measured at the monitoring wells by Stantec throughout the investigation is provided in Table 2.



Methodology June 2024

The continuous recording of groundwater level fluctuations occurred in each onsite monitoring well from June 2021 to June 2024 using dataloggers (i.e., either Solinst® Levelogger 5® or vanEssen Instruments® TD-Diver®). Suspended into the water column at each monitoring well, the datalogger was programmed to record water levels at 60-minute intervals. Dataloggers are not vented to the atmosphere and, therefore, record total pressure (where total pressure is the sum of the atmospheric pressure and the height of water column). To obtain an accurate measurement of the groundwater level at each well, the water level data obtained from the dataloggers are corrected for atmospheric pressure using data obtained from a Solinst® Barologger 5® (Barologger), which was suspended in the air column within one of the onsite monitoring wells (i.e., MW01-21). Hydrographs showing groundwater level fluctuations in the monitoring wells over time are presented in Figures 7 to 9.

3.4 HYDRAULIC RESPONSE TESTING

To estimate the horizontal hydraulic conductivity of the deposits beneath the Applicant Lands, Stantec performed in-situ hydraulic response testing on MW01-21 to MW05-21 on May 31, 2021, and at MW105-23 on April 2, 2024. The testing performed for this investigation consisted of creating an instantaneous change in the monitoring well water level by removing a known volume of water from the well (i.e., rising head / bail test), followed by recording the time taken for the resulting water level to return to static conditions using a combination manual and continuous (i.e., Levelogger) measurements. The testing results were analyzed using the Bouwer and Rice (1976) / Bouwer (1989) solution provided in the software package AQTESOLV™ Pro Version 4.5 (Duffield, 2014) to calculate the horizontal hydraulic conductivity of the aquifer sediments within the immediate vicinity of the screened interval of each monitoring well. Table 1 provides a summary of the calculated horizontal hydraulic conductivities, with the analytical solutions for the data being presented in Appendix H.

Stantec also used the in-situ hydraulic response testing results obtained from the monitoring wells to provide preliminary estimates of infiltration rates for the overburden soils (i.e., at depths between 2.8 m and 6.2 m BGS). Since hydraulic conductivity in the horizontal direction is generally an order (potentially two orders for clay-based deposits) of magnitude higher than hydraulic conductivity in the vertical direction (Todd 1980; Freeze and Cherry 1979), the vertical hydraulic conductivities for overburden deposits surrounding the well screens were assumed to be one order of magnitude lower than in-situ measured horizontal hydraulic conductivities. The Credit Valley Conservation-Toronto and Region Conservation (CVC-TRCA) (2010) method for converting vertical hydraulic conductivity to an infiltration rate was then applied to these data, with the results being presented in Table 3.

3.5 GROUNDWATER SAMPLING AND QUALITY TESTING

3.5.1 Onsite Monitoring Wells

On May 27, 2021, April 13 and December 5, 2023, Stantec personnel collected groundwater samples from the onsite monitoring wells for analysis and comparison against the Ontario Drinking Water Quality Standards (ODWQS) (MECP, 2018).



Methodology June 2024

Groundwater collected from the monitoring wells involved using the same dedicated tubing to develop the monitoring wells (Section 3.2). Prior to collecting the sample, Stantec personnel measured in-situ field parameters of pH, temperature, and specific conductivity using a Hanna HI 98129 waterproof pH/conductivity/TDS tester. The meter was calibrated prior to use according to the manufacturer's specification with the appropriate clabration standards. Sampled groundwater was poured directly from the HDPE tubing into lab supplied sample bottles. All groundwater samples were packed into coolers with ice, which was added to maintain sample temperatures below 10°C during transit to the analytical laboratory. Samples were delivered to an accredited laboratory (i.e., Bureau Veritas Laboratories) for the analysis of general inorganic chemistry, nutrients, and metals. Samples collected for metals were filtered in the field using dedicated disposable 0.45 µm in-line filters and, subsequently, reported concentrations represent dissolved metals.

Chain of custody forms were completed and included with the samples at the time of the laboratory submission. The quality results for groundwater sampled from the onsite monitroing wells are summarized in Table 4. A copy of the laboratory Certificate of Analysis is presented in Appendix I.

3.5.2 Offsite Private Wells

The Village of Wellesley primarily receives their drinking water from the municipal system (i.e., Wellesley Wellfield); however, there are residential properties on the surrounding edges of the Village that obtain their potable water supply from private wells. Stantec personnel delivered letters to homes surrounding the Applicant Lands that were identified as potentially having a private well, inviting the residents to participate in a voluntary, pre-construction well water quality monitoring program. The letter detailed that the monitoring program would consist of the completion of a well survey questionnaire, collection of a water quality sample, and an inspection of the well head, with the well water quality results being provided to the resident. Four letters were delivered to properties near the Applicant Lands, with two homeowners responding to the letter expressing their interest in participating in the pre-construction monitoring program. The locations of the properties participating in the program (i.e., RW01 and RW02) are shown on Figure 1.

• Water samples were either collected from an outdoor tap attached to the house or garage, or from a kitchen faucet. Prior to collecting the water sample, the aerator, if present and easily accessible on the tap spout, was removed. Stantec personnel disinfected the tap spout with a dilute (10%) sterilene solution and allowed the water to run for a minimum of 10 minutes. While the water was running, Stantec personnel recorded quality parameters such as temperature, pH, specific conductivity, and turbidity using a Hanna pen® and the Hach 2100Q® turbidity meter. Once these parameter values stabilized, Stantec personnel proceeded to collect the water sample.



Methodology June 2024

Water samples were collected directly into labelled, laboratory supplied containers (as per MECP, 2009), and placed in coolers on ice for storage for transport and submission to Bureau Veritas Laboratories for analysis. Water samples collected from the private wells were analyzed for microbiological parameters (i.e., total coliform and *E.coli*), general inorganic chemistry, nutrients, and metals. The samples were not filtered in the field and, subsequently, metals results represent total concentrations (versus dissolved).

Chain of custody forms were completed and included with the samples at the time of the laboratory submission. The results of the groundwater quality testing are summarized in Table 5. A copy of the laboratory Certificate of Analysis is presented in Appendix I.

3.6 TEST PIT EXCAVATIONS

On May 2, 2024, the Applicant provided a rubber tire backhoe and proceeded to excavate five test pits (TP01-24 to TP05-24) throughout the Subject Lands under the observation of Stantec. The purpose of excavating the test pits was to confirm the positioning of the high groundwater table as suggested by water levels recorded in the onsite monitoring wells. Stantec strategically located the test pits near each monitoring well constructed in the Subject Lands (i.e., MW01-21, MW02-21, MW04-21, and MW05-21), with an additional test pit being excavated in the central-east portion of the property (i.e., TP03-24). The test pits were excavated to depths ranging from approximately 3.5 to 4.0 m BGS. Stantec classified the excavated soils using the ASTM guideline for visual-manual description and identification of soils (ASTM D2488-00), providing descriptions (where relevant and possible) of soil type, texture, colour, structure, moisture content, and other observations. Stantec also obtained soil grab samples from TP01-24 and TP04-24 and submitted these samples to Stantec's geotechnical laboratory for grain-size analysis, Atterberg limits, and moisture content testing.

Once excavated, Stantec instructed the Applicant to leave the test pits open for approximately 24 hours to observe / confirm the presence of potential groundwater seepage conditions in each test pit. After this period, the Applicant proceeded to backfill the test pits and return each location to its original ground surface elevation. Locations of the test pits are shown on Figure 1, with the ground surface elevation at each test pit being estimated based on the topographic contours provided on this figure (i.e., contours generated based on Stantec Geomatics survey results as previously mentioned in Section 3.2). Copies of the test pit logs and results of the geotechnical laboratory testing are provided in Appendix G.



Local Geology and Hydrogeology June 2024

4.0 LOCAL GEOLOGY AND HYDROGEOLOGY

4.1 GEOLOGY AND HYDROSTRATIGRAPHY

Figure 4 presents the surficial geology within and surrounding the Applicant Lands as mapped by the OGS (2010). Deposits of stone-poor, sandy silt to silty sand till, which is interpreted to represent the Stratford Till, covers most of the Applicant Lands with these deposits also covering the northern portion of the Subject Lands (Figure 4, Unit 5b). The remainder of the Subject Lands are covered with glaciolacustrine-derived deposits of silty clay till, which is interpreted to represent the Mornington Till (Figure 4, Unit 5d). Surrounding the Applicant Lands are glaciofluvial deposits of sand and gravel (AFA2), modern deposits of alluvium associated within the corridors of the Nith River and its associated tributaries, and ice-contact stratified deposits of gravel, sand, and silt that are potentially associated with Aquifer 1 (AFB1). Overall, the onsite drilling results completed as a part of this investigation support the OGS interpreted distribution of surficial soils that cover the Applicant Lands.

Figure 4 shows the locations of Cross Sections A-A' (Figure 10) and B-B' (Figure 11), which were constructed using the results of the onsite drilling investigation. A summary of these drilling results is shown on the borehole logs provided in Appendix G. The investigation results indicate that a 0.3 to 1.5 m thick mixture of fill and topsoil (sandy silt to silty sand) covers the Applicant Lands, with the fill being encountered mostly along the eastern and southern limits of these lands (e.g., MW01-21, MW04-21, MW06-21, and BH07-21). In general, these surficial deposits overlie a combination of sandy silt, silty clay, and clay tills (i.e., Aquitard 1; ATB1), which form a horizontally and vertically contiguous unit that extends up to the termination depth of the shallow boreholes (i.e., 4.7 m BGS to 6.7 m BGS; approximately 350 m AMSL) and confirmed reach a depth of at least 25 m BGS (337 m AMSL) based on the drilling results recorded at MW105-23. Local MECP water well records (Appendix G) suggest that the Aquitard 1 unit extends to a depth of up to 50 m BGS near the Applicant Lands. Layers and seams of sand, silt, and sand and gravel are also present in the glacial till at variable depths, with notable pockets of these deposits being encountered at MW03-21 and MW05-21 (Figure 11).

4.2 HYDROGEOLOGY

4.2.1 Groundwater Levels

Figures 7 to 9 and Table 2 present the continuous and manual water levels recorded in the monitoring wells between June 2021 and June 2024 (i.e., representing approximately three years of groundwater level monitoring data). Groundwater levels across the Applicant Lands were recorded at ground surface (at MW02-21) to 4.8 m BGS (at MW03-21) over the monitoring period, equating to elevations ranging from 353.1 m AMSL to 361.7 m AMSL. In the Subject Lands, groundwater levels ranged from at ground surface (at MW02-21) to 3.7 m BGS (at MW02-21), equating to elevations ranging from 353.1 m AMSL to 361.6 m AMSL.



Local Geology and Hydrogeology June 2024

As shown in Figure 7, the groundwater table demonstrated a similar pattern in fluctuations across the Applicant Lands. Traditionally, high groundwater elevations in southern Ontario occur in the spring, with groundwater elevations typically beginning their steady rise in the late fall. This groundwater table rise is attributed to a reduction in soil moisture losses to evapotranspiration that occurs over the late fall to spring together with a melting snowpack that occurs during the spring, which in turn provides a greater volume of water available to infiltrate and recharge the groundwater system. In contrast, during the summer months the groundwater table reaches its lowest elevation due to more water being drawn from the subsurface to meet an increased evapotranspiration demand. Overall, the difference between the high and low groundwater table positioning (i.e., total fluctuation) beneath the Applicant Lands in each of the 2021 and 2023 monitoring periods ranged from 1.4 to 2.9 m.

Stantec notes that a pronounced drop in the groundwater table occurred across the Applicant Lands during the notably dry year experienced in 2022. In 2022, a lower-than-average amount of precipitation that fell over the region where total precipitation (rainfall + snowfall) equaled 580 mm compared to the corresponding 30-year average (1991 to 2020) of 850 mm (as recorded at the Kitchener/Waterloo Climate Station). As such, the resulting deficit of soil moisture available in the subsurface to meet local evapotranspiration demands resulted in water being drawn up from deeper portions of the groundwater system to satisfy these demands and, consequently, caused the groundwater table to decline by up to 4.6 m throughout the property.

As previously mentioned, groundwater levels recorded at the monitoring wells located in the Subject Lands indicate that the groundwater table can be positioned just below ground surface to 0.5 m BGS, with these high groundwater conditions typically occurring in early to mid-fall (i.e., September / October) and continuing into the late spring (i.e., May) (Figures 7 to 9). Results of the onsite test pitting provides supporting evidence that the water levels observed in the monitoring wells are true as the test pit walls (excavated on May 2, 2024, and left open for approximately 24 hours) were beaded with water indicating the slow seepage of groundwater from the low permeable deposits (i.e., geometric mean hydraulic conductivity of 10-8 m/s; Table 1) of sandy silt, silt, silty clay, and clay till (i.e., Aquitard 1; ATB1), which comprise the subsurface of the Subject Lands (e.g., Photos 4, 8, and 18; Appendix J). In addition, varying degrees of soil sloughing off the test pits walls occurred while the excavations were open, pointing to soil saturation associated with a high groundwater table (e.g., Photos 2, 6, 12, and 19; Appendix J). Although relatively higher flowing seeps from saturated sand layers interbedded in the previously mentioned deposits of ATB1 resulted in the ponding of groundwater at the base of some test pits (e.g., TP03-24, Photos 10 to 12; TP04-24, Photos 13 and 14; TP05-24, Photo 18), the flow from these seeps slowed notably within the time that the pit remained open, indicating that these higher permeability deposits had largely drained out (i.e., after initial draining, recharge back into the sand layers was limited by the surrounding lower permeable silts and clays). The fact that flows from these sand layers slowed considerably suggests that these layers are also of limited extent in the subsurface of the Subject Lands.



Local Geology and Hydrogeology June 2024

Stantec notes that the soil moisture / groundwater observations made in the onsite monitoring wells and test pits are not the result of a perched groundwater condition in the shallow overburden. Results from the drilling of MW105-23 indicate that ATB1 forms a continuous groundwater unit (i.e., no evidence of unsaturated zone pockets) extending up to at least the termination depth of the borehole at 25 m BGS (Appendix G).

4.2.2 Groundwater Flow

Figure 12 presents groundwater elevation contours and the interpreted direction of horizontal flow through the groundwater system beneath the Applicant Lands using water level measurements collected from the onsite monitoring wells in June 2021. In general, groundwater contours generally mimic the prevailing topography of the Applicant Lands, with an interpreted localized groundwater divide occurring somewhere in the northern portion of these lands and potentially being in line with the surface water flow divide that separates Catchments 100 and 101. In the Subject Lands, groundwater flows in a southern direction towards Gerber Road, with this interpretation being in general agreement with regional groundwater flow patterns (Figure ST-7, Appendix D).

Available horizontal hydraulic conductivity estimates calculated from onsite hydraulic response testing completed at the monitoring wells in the shallow overburden deposits of the Subject Lands (i.e., MW01-21 to MW04-21) ranged from 7.3 x 10⁻⁶ m/s to 5.8 x 10⁻⁹ m/s (Table 1; Appendix H), for an estimated bulk (i.e., geometric mean) horizontal hydraulic conductivity of 7.8 x 10⁻⁸ m/s (Table 1).

The velocity at which groundwater horizontally flows through the subsurface is calculated through the application of Darcy's law, where:

$$\mathsf{V} = \frac{\mathsf{K} \; \nabla}{\theta}$$

where: v = velocity (m/s)

K =hydraulic conductivity (m/s) $\nabla =$ hydraulic gradient (m/m) $\theta =$ effective porosity (unitless)

As discussed in Section 4.1, the Subject Lands are covered by the deposits of Aquitard 1 (ATB1; sandy silt, silt, silty clay, and clay tills) that vertically extend to a confirmed depth of up to 25 m BGS (approximately 337 m AMSL) but potentially up to a depth of 50 m BGS based on local MECP water well records, with the groundwater table being positioned within this unit. Assuming an effective soil porosity of 0.20 for glacial till (Fetter, 1994), a calculated average horizontal hydraulic gradient of 0.02 m/m, and geometric mean hydraulic conductivity of 7.8 x 10⁻⁸ m/s (Table 1), the estimated velocity of groundwater flowing in a southward direction through Aquitard 1 (ATB1) beneath the Subject Lands is calculated to be approximately 0.26 m/year (i.e., one meter every 3.9 years).



Local Geology and Hydrogeology June 2024

4.2.3 Infiltration Potential

Estimated infiltration rates for the overburden deposits are provided in Table 3. Infiltration rates were calculated based on an established relationship between vertical hydraulic conductivity and infiltration rate presented in CVC-TRCA (2010), with vertical hydraulic conductivities being estimated based on in-situ hydraulic response testing completed at MW01-21 to MW05-21 (Section 3.4).

Vertical hydraulic conductivities for overburden deposits screened at depths between 2.8 m to 6.1 m beneath the Applicant Lands and tested via in-situ hydraulic response testing completed at the previously mentioned monitoring wells is assumed to be one order of magnitude lower than in-situ measured horizontal hydraulic conductivities at these locations (Todd, 1980; Freeze and Cherry, 1979). For the deposits of Aquitard 1 (ATB1), vertical hydraulic conductivities are estimated to range from 7.3 x 10⁻⁷ m/s to 5.4 x 10⁻¹⁰ m/s, equating to infiltration rates ranging from 6 mm/hour to 42 mm/hour (Table 3).

4.2.4 Groundwater Quality

Onsite Monitoring Wells

Groundwater samples were collected from the monitoring wells on May 27, 2021 (i.e., MW01-21, MW03-21, and MW05-21) and on April 13 and December 5, 2023 (i.e., MW01-21 to MW06-21), for the analysis of general inorganic chemistry, nutrients, and metals. The samples were compared to Ontario Drinking Water Quality Standards (ODWQS) for health and non-health related parameters (MECP, 2018). Groundwater sampled from across the Applicant Lands is identified as calcium-bicarbonate type water (Figure 13), which is typical of fresh shallow groundwater in southern Ontario. Overall, no analyzed parameters in the groundwater samples had concentrations detected above applicable ODWQS health related objectives (i.e., maximum acceptable concentrations) (Table 4), although some parameters did exceed their corresponding Aesthetic Objective (AO), Operational Guideline (OG), and/or Medical Officer of Health Reporting Limit (MOH) concentrations as outlined below.

- Aluminum exceeded the ODWQS OG (0.1 mg/L) at MW01-21 and MW04-21 in December 2023 with concentrations of 0.32 mg/L and 0.44 mg/L, respectively.
- Hardness exceeded the ODWQS OG (80 to 100 mg/L) at all sampling locations and events with concentrations ranging from 190 to 450 mg/L. Overall, the presence of elevated hardness is typical of groundwater in southern Ontario and not considered to be a concern.
- Iron exceeded the ODWQS AO (0.3 mg/L) with concentrations of 0.4 mg/L and 0.5 mg/L recorded at MW03-21 and MW04-21, respectively.
- Manganese exceeded the ODWQS AO (0.05 mg/L) at MW01-21 (0.052 to 0.054 mg/L), MW03-21 (0.065 mg/L), MW04-21 (0.053 to 0.085 mg/L), and at MW05-21 (0.076 mg/L). Overall, the presence of elevated manganese is typical of groundwater in southern Ontario and not considered to be a concern.



Local Geology and Hydrogeology June 2024

- Sodium exceeded the ODWQS MOH reporting limit (20 mg/L) with concentrations ranging from 33 mg/L to 93 mg/L at MW01-21, MW02-21, and MW04-21. If the groundwater is utilized as a potable drinking-water source, the local Medical Officer of Health should be notified when the sodium concentration exceeds 20 mg/L so that this information may be communicated to local physicians for their use with patients on sodium restricted diets.
- Total dissolved solids (TDS) exceeded the ODWQS AO (500 mg/L) with concentrations of 520 mg/L to 660 mg/L at MW01-21.
- Turbidity exceeded the ODWQS AO (5 mg/L) with concentrations of 1,800 mg/L at MW01-21, 2,100 to 3,500 mg/L at MW05-21, and 4,700 mg/L at MW03-21 in May 2021. This parameter is often elevated in groundwater samples collected from monitoring wells due to the presence of sediment in the samples from the sampling process.

Offsite Private Wells

Groundwater quality results for those samples collected from the offsite private wells (i.e., RW01 and RW02; Figure 1) indicate that the groundwater is calcium-sulfate type water (Figure 13), suggesting that these wells draw their water supply from a deeper confined aquifer system (e.g., Aquifer 2/3 and/or the Bedrock Aquifer – refer to Section 2.2). Overall, no analyzed parameters in the groundwater samples had concentrations detected above applicable ODWQS health related objectives (i.e., maximum acceptable concentrations) (Table 5), although some parameters did exceed their corresponding Aesthetic Objective (AO) and Operational Guideline (OG) concentrations as outlined below:

- Hardness exceeded the ODWQS OG (80 to 100 mg/L) with concentrations of 420 mg/L (RW01) and 580 mg/L (RW02). The presence of elevated hardness is typical of groundwater in southern Ontario and not considered to be a concern.
- Iron exceeded the ODWQS AO (0.3 mg/L) with concentrations of 0.4 mg/L (RW01) and 5.9 mg/L (RW02). Manganese was also detected in the well water sample collected from RW02 at a concentration of 0.08 mg/L, exceeding the corresponding ODWQS AO of 0.05 mg/L. Elevated concentrations of iron and manganese in well water are often indicative of groundwater that is drawn from an aquifer that is characterized by anaerobic (i.e., reducing) conditions, which is often characteristic of a confined aquifer system.
- Total dissolved solids (TDS) exceeded the ODWQS AO with concentrations of 530 mg/L (RW01) and 780 mg/L (RW02). The presence of elevated TDS is typical of groundwater drawn from confined bedrock aguifer systems in Ontario and not considered to be a concern.
- Turbidity exceeded the ODWQS OG (5 mg/L) with a concentration of 49 mg/L at RW02.



Effects Assessment and Mitigation Measures June 2024

5.0 EFFECTS ASSESSMENT AND MITIGATION MEASURES

5.1 WATER BALANCE AND INFILTRATION

Proposed development for the Applicant Lands will consist of future residential development and with this development will come the introduction of impervious surfaces (e.g., rooftops, concrete/asphalt roadways, parking lots, and walkways) and, subsequently, a corresponding reduction in the volume of water infiltrating to the subsurface.

As documented in Appendix F of Stantec's (2024) Functional Servicing Report, results of the water balance analyses indicate that the total volume of infiltration occurring across the Applicant Lands under the pre-development condition is approximately 33,660 m³/year, with this volume declining to 13,464 m³/year under an unmitigated post-development condition (i.e., infiltration deficit of 20,196 m³/year). To address this situation, the primary post-development infiltration augmentation measure proposed for the Applicant Lands will be to capture rooftop runoff and return this clean stormwater to the subsurface via a series of lot-level infiltration galleries designed to infiltrate and retain a 25 mm storm event, where possible.

A key constraint to the implementation of post-development infiltration augmentation measures is the positioning of a seasonally high groundwater table. As per CVC-TRCA (2010), the recommended vertical separation between the base of a given infiltration augmentation option and the high groundwater table is at least one meter; however, distances of less than one meter of separation in soils having higher infiltration potential may still be effective. Based on groundwater monitoring data presented in this report (i.e., from June 2021 to June 2024), groundwater levels are shown to fluctuate between just below existing grades to 4.8 m BGS throughout the Applicant Lands (Figures 8 and 9) with the subsurface deposits having estimated infiltration rates ranging from 6 mm/hour to 42 mm/hour (Table 3). Overall, the implementation of post-development infiltration augmentation measures across certain areas of the Applicant Lands may be challenging based on the high groundwater level and low soil permeability conditions mentioned above.

The utilization of the previously mentioned post-development low impact development (LID) infiltration augmentation option (i.e., lot-level infiltration galleries) throughout the Applicant Lands will be evaluated further during the detailed design stages of the development.



Effects Assessment and Mitigation Measures June 2024

5.2 GROUNDWATER DEWATERING

5.2.1 Construction Dewatering

With the construction of below ground structures (e.g., basements) and servicing infrastructure (e.g., sewer and watermain, SWM pond facilities) comes the potential of intercepting the groundwater table and, consequently, the need for short-term construction dewatering and/or the installation of permanent drainage systems (in the absence of waterproofing). Where required, dewatering will result in the lowering of the groundwater table to the base of a given excavation and/or underground structure. The effects of local dewatering in general cannot be mitigated, since dewatering deliberately seeks to create an effect (i.e., lowering of groundwater levels).

For dewatering occurring in the moderate to low permeability deposits associated with ATB1, the dewatering zone of influence (ZOI) (i.e., horizontal extent of groundwater level declines / drawdown caused by dewatering activities at a point source) is expected to remain within relatively short distances around excavations and/or subsurface structures, given that these deposits are characterized by horizontal hydraulic conductivities ranging from 7.3 x 10⁻⁶ m/s to 5.4 x 10⁻⁹ m/s (geometric mean of 8.0 x 10⁻⁸ m/s) (Table 1; Appendix H). At these hydraulic conductivities, low volumes of groundwater are expected to discharge into temporary construction excavations, with conventional pumping from filtered sumps being capable of removing these anticipated volumes from a given excavation area.

Under O. Reg. 64/16 and O. Reg. 63/16A, if construction dewatering volumes are projected to exceed 50,000 L/day, registration of an MECP Environmental Activity and Sector Registry (EASR) or Permit to Take Water (PTTW) will be required for dewatering to occur. A PTTW is required when groundwater volumes for construction dewatering are expected to exceed 400,000 L/day or when groundwater collected and discharged from a permanent drainage system exceeds 50,000 L/day. An EASR is required when construction dewatering volumes are projected to range from 50,000 L to 400,000 L/day.

Stantec notes that recent amendments made to EASR requirements by the MECP for construction dewatering include the following:

The ability to register multiple dewatering pits for a single project under the same EASR.

- Allowing construction dewatering of up to 400,000 L/day for each dewatering pit as long as the dewatering area of influence do not overlap.
- Stormwater will no longer be counted in the 400,000 L/day water taking limit, however, registrants will
 at a minimum be required to keep a record of precipitation events, or if determined by a Qualified
 Person, detailed monitoring/documentation.
- EASRs will apply to linear projects including transit and pipelines.
- Registrants will be required to notify the local municipalities and conservation authorities if the water taking is intended to continue for more than 365 days.



Effects Assessment and Mitigation Measures June 2024

Dewatering assessments are recommended for completion during detailed design to specifically determine anticipated dewatering volumes and associated water taking permitting requirements.

When dewatering volumes are projected to be greater than 50,000 L/day, the following mitigation measures are likely to be required for either an EASR or PTTW application:

- Groundwater Discharge Management Establishment of an appropriate dewatering system that will dissipate the energy and reduce the sediment content of discharging water for the purpose of limiting potential erosion effects if groundwater is to be discharged to a receiving surface water feature. Common measures include the use of sediment control basins, erosion pads, geotextile filter bags, and the positioning of straw bale/filter cloth barriers downgradient of the discharge point. The quality of the groundwater discharge must also meet Provincial Water Quality Objectives (PWQO) (MECP, 1994). If groundwater is to be discharged to the regional sewer system for disposal, the quality of this water must not exceed parameter concentrations as listed under Regional Municipality of Waterloo Sewer Use By-Law No. 1-90.
- Private Well Monitoring The monitoring of private wells expected to be located within the
 dewatering ZOI (as estimated from the dewatering assessment) for drawdown interference, which
 could potentially affect the operation of private wells with regards to water quantities. The providing of
 affected well owners with temporary potable water supplies or reducing dewatering rates and/or
 duration would be required if notable interference effects are observed.

A review of the MECP water well records for wells located within 500 m of the Applicant Lands indicates that there are 37 wells identified as being utilized for water supply (i.e., domestic, commercial, livestock, or municipal). One well is located within 20 m of the Applicant Lands (i.e., MECP Well 7318145; Figure 4), with the remaining 36 wells being positioned between 170 m to 500 m away from these lands (Appendix G). The average constructed depth of these private wells is 53 m BGS, indicating that groundwater drawn into these wells originates from the deeper confined Aquifer 2/3 (AFB3/AFD1) and/or the Bedrock Aquifer. As such, construction dewatering activities potentially occurring at the Applicant Lands are highly unlikely to interfere with the yields of these local private wells, given that the shallow overburden where these activities will occur is hydraulically separated from these previously mentioned deeper aquifer systems by the low permeability silt to clay-based glacial tills of Aquitard 1 (ATB1).

5.2.2 Permanent Dewatering

As discussed in Section 4.2.1, during certain periods of the year (i.e., typically from early / mid-fall to the late spring), the groundwater table can be positioned just below ground surface to 0.5 m BGS. As such, future residential buildings constructed with basements on the Subject Lands are likely to be temporarily located below the groundwater table. However, constructing residential foundations below the groundwater table will be manageable using traditional groundwater control techniques (e.g., foundation damp proofing membranes, weeping tiles, and sump pits / pumps), largely due to the low permeability deposits that underlie the site and, subsequently, slow groundwater movement. Details on the groundwater dewatering mitigation strategy that will be employed at the Subject Lands for those



Effects Assessment and Mitigation Measures June 2024

residential foundations that may occur below the groundwater table are discussed in Sections 2.4.1 and 2.4.2 of the Stantec (2024) Functional Servicing Report.

5.3 SOURCE WATER PROTECTION

A drinking-water threat is an activity or condition that adversely affects or has the potential to adversely affect the quality or quantity of any water that is or may be used as a source of drinking water. The following activities are prescribed by the province of Ontario under O. Reg. 287/07 to be drinking water threats (i.e., Significant Drinking Water Threat Policy Categories):

- 1. The establishment, operation, or maintenance of a waste disposal site within the meaning of Part V of the *Environmental Protection Act*.
 - a) Untreated sewage
 - b) Waste disposal
 - c) Mine tailings
- 2. The establishment, operation, or maintenance of a system that collects, stores, transmits, treats, or disposes of sewage.
 - a) Stormwater management
 - b) Wastewater treatment plants/sewer systems
 - c) On-site sewage systems
 - d) Industrial effluent
- 3. The application of agricultural source material to land.
- 4. The storage of agricultural source material.
- 5. The management of agricultural source material.
- 6. The application of non-agricultural source material to land.
- 7. The handling and storage of non-agricultural source material.
- 8. The application of commercial fertilizer to land.
- 9. The handling and storage of commercial fertilizer.
- 10. The application of pesticide to land.
- 11. The handling and storage of pesticide.
- 12. The application of road salt.
- 13. The handling and storage of road salt.
- 14. The storage of snow.
- 15. The handling and storage of fuel.



Effects Assessment and Mitigation Measures June 2024

- 16. The handling and storage of a dense non-aqueous phase liquid (DNAPL).
- 17. The handling and storage of an organic solvent.
- 18. The management of runoff that contains chemicals used in the de-icing of aircraft.
- 19. An activity that takes water from an aquifer or a surface water body without returning the water taken to the same aquifer or surface water body.
- 20. An activity that reduces the recharge of an aguifer.
- 21. The use of land as livestock grazing or pasturing land, an outdoor confinement area or a farm-animal yard.
- 22. The establishment and operation of a liquid hydrocarbon pipeline as per O. Reg. 385/08, s. 3.

As shown in Figure 5, the Applicant Lands are largely intercepted by the WHPA-B, and to a lesser extent WHPA-C and WHPA-D, of the Wellesley Wellfield (Wells WY1, WY5, and WY6). The vulnerability score assigned to these WHPA is 6 (Map A1, Appendix E), indicating that the threat of an activity or condition occurring at ground surface within this area and subsequently adversely affecting the quality and/or quantity of the aquifer system in which these municipal production wells draw their groundwater supply is medium to low.

As per the SPP (LERSPC, 2021b) Map A1 (Appendix E), the Applicant Lands are only subject to the protection policies specified under Significant Drinking Water Threat Policy Category 16 (DNAPLs). Since the planned use for the Applicant Lands will not involve the onsite handling and storage of DNAPLs, the SPP policy under Category 16 does not apply.

Policies in the SPP that address significant threat activities that pose a risk to the quantity of source water available for municipal well use (i.e., Significant Drinking Water Threat Policies 19 and 20) only apply to WHPA-Q. As mentioned previously, no WHPA-Q intercepts the Applicant Lands (Figure E-1, Appendix E).

5.4 SERVICING ALIGNMENTS AND GROUNDWATER FLOW

Proposed development for the Applicant Lands will include the installation of servicing (i.e., storm / sanitary sewers and watermains), with preliminary designs indicating that this servicing will be installed at depths ranging from 1.5 to 3.0 m BGS. Given that preliminary monitoring results indicate that the groundwater table ranges just below ground surface to 4.8 m BGS across the Applicant Lands (Section 4.2.1), these servicing installations are likely to intercept the groundwater table. In areas where site servicing extends below the groundwater table, Stantec recommends that anti-seepage (cut-off) collars be installed to prevent the preferential movement of groundwater along the servicing alignments. The use of anti-seepage collars will likely be required given that the subsurface of the Applicant Lands is characterized by low permeability deposits where groundwater movement is more restricted (e.g., silt to clay-based soils). An assessment for the need, total number, and exact placements of anti-seepage



Effects Assessment and Mitigation Measures June 2024

collars along the servicing alignments can be explored in more detail during the detailed design phase of the project.

5.5 SPILL CONTAINMENT AND RESPONSE

The potential exists for spills during any construction activity, with the most probable type of spill occurring being attributable to the refuelling of major construction equipment that cannot readily leave the Applicant Lands (e.g., earth movers). The potential impacts of a spill could be the contamination of soils, groundwater and/or surface water. By implementing proper protocols for the handling of fuels and lubricants during construction, the risk of a spill occurring will be greatly reduced. The procedures to be implemented to prevent onsite spills are as follows:

- All trucks or other road vehicles would be refuelled and maintained offsite, where practicable.
- Refuelling and lubrication of other construction equipment would not be allowed within 30 m of a drainage system or dewatering excavation.
- Regular inspections of hydraulic and fuel systems on machinery, with leaks being repaired immediately upon detection or the equipment being removed from Site.
- · Spill kits containing absorbent materials would be kept on hand; and
- Implement best management practices and develop an emergency spill response plan.

Given that anticipated construction activities at the Applicant Lands are not expected to involve the storage or use of bulk chemicals or fuels, a potential spill that may occur would be localized and involve a small volume of material. If there were to be an accidental release of a deleterious substance, the low permeability of the soils that cover the Applicant Lands will prevent the rapid infiltration and movement of these substances through the subsurface, allowing response personnel sufficient time to contain and clean-up such a release before it causes potential harm to the quality of the groundwater system. Overall, standard containment facilities and emergency response materials are to be maintained onsite as required, with refuelling, equipment maintenance, and other potentially contaminating activities being confined to designated areas. As appropriate, spills are to be reported immediately to the MECP Spills Action Centre.



Conclusions June 2024

6.0 CONCLUSIONS

The following conclusions are provided based on the completed hydrogeological assessment:

- 1. Stratigraphic conditions beneath the Applicant Lands consist of a 0.3 m to 1.5 m thick mixture of topsoil and pockets of fill and topsoil (sandy silt to silty sand) that is predominantly underlain by a combination of sandy silt, silt, silty clay, and clay glacial till (i.e., Aquitard 1; ATB1), which form a horizontally and vertically contiguous unit that extends up to the termination depth of the boreholes (i.e., up to 25 m BGS; approximately 337 m AMSL). Local MECP water well records suggest that the Aquitard 1 unit extends to a depth of up to 50 m BGS near the Applicant Lands. Layers and seams of sand, silt, and sand and gravel are also present in the glacial till at variable depths.
- 2. Groundwater elevations across the Applicant Lands ranged from just below ground surface to 4.8 m BGS over the monitoring period (i.e., June 2021 to June 2024), equating to elevations ranging from 353.1 m to 361.7 m AMSL. High groundwater conditions typically occur in early to mid-fall (i.e., September / October) and continue into the late spring (i.e., May), with the groundwater table being positioned within 0.5 m of existing grades throughout the Subject Lands over this period.
- 3. In general, groundwater contours generally mimic the prevailing topography of the Applicant Lands, with an interpreted localized groundwater divide occurring somewhere in the northern portion of these lands and potentially being in line with the surface water flow divide that separates Catchments 100 and 101. In the Subject Lands, groundwater flows in a southern direction towards Gerber Road, with this interpretation being in general agreement with regional groundwater flow patterns.
- 4. The horizontal movement of groundwater through Aquitard 1 (ATB1) beneath the Subject Lands is calculated to be in the range of 0.26 m/year (i.e., one meter every 3.9 years) due to the low hydraulic conductivity associated with these deposits (i.e., 10⁻⁶ to 10⁻⁹ m/s, for a geometric average of 10⁻⁸ m/s).
- 5. Estimated vertical hydraulic conductivities for the deposits of Aquitard 1 (ATB1) range from 7.3 x 10⁻⁷ m/s to 5.4 x 10⁻¹⁰ m/s, equating to infiltration rates ranging from 6 mm/hour to 42 mm/hour.
- 6. Groundwater sampled from the onsite monitoring wells (screened in the upper deposits of Aquitard 1) is identified as calcium-bicarbonate type water, which is typical of fresh shallow groundwater in southern Ontario. Groundwater sampled from the offsite private wells is identified as calcium-sulfate type water, suggesting that these wells draw their water supply from a deeper confined aquifer system (e.g., Aquifer 2/3 and/or the Bedrock Aquifer). Overall, no analyzed parameters in the groundwater samples collected from the onsite and offsite wells had concentrations detected above applicable ODWQS health related objectives.



Conclusions June 2024

- 7. As documented in Stantec's (2024) Functional Servicing Report, results of the water balance analyses indicates that the total volume of infiltration occurring across the Applicant Lands under the pre-development condition is approximately 33,660 m³/year, with this volume declining to 13,464 m³/year under an unmitigated post-development condition (i.e., infiltration deficit of 20,196 m³/year). To address this situation, the primary post-development infiltration augmentation measure proposed for the Applicant Lands will be to capture rooftop runoff and return this clean stormwater to the subsurface via a series of lot-level infiltration galleries designed to infiltrate and retain a 25 mm storm event, where possible.
- 8. The Applicant Lands are intercepted by WHPA-B to WHPA-D of the Wellesley Wellfield, which are assigned with a vulnerability score of 6. As per the Source Protection Plan (SPP) (LERSPC, 2021b) Map A1 (Appendix E), the Applicant Lands are only subject to the protection policies specified under Significant Drinking Water Threat Policy Category 16 (DNAPLs). Since the planned use for the Applicant Lands will not involve the onsite handling and storage of DNAPLs, the SPP policy under Category 16 does not apply.
- 9. Construction dewatering will likely be required at the Applicant Lands due to an elevated groundwater table; however, for dewatering occurring in low permeability deposits such as Aquitard 1 (ATB1), the dewatering zone of influence (ZOI) (i.e., horizontal extent of groundwater level declines / drawdown caused by dewatering activities at a point source) is expected to be low and isolated to a small distance around excavations and/or subsurface structures, given that these deposits across these lands are characterized by hydraulic conductivities ranging from 10-6 m/s to 10-9 m/s. Dewatering assessments are recommended for completion during detailed design to specifically determine anticipated dewatering volumes and associated water taking permitting requirements for the proposed future development.
- 10. As discussed in Section 4.2.1, during certain periods of the year (i.e., typically from early / mid-fall to the late spring), the groundwater table can be positioned just below ground surface to 0.5 m BGS. As such, future residential buildings constructed with basements on the Applicant Lands are likely to be temporarily located below the groundwater table. However, constructing residential foundations below the groundwater table will be manageable using traditional groundwater control techniques (e.g., foundation damp proofing membranes, weeping tiles, and sump pits / pumps), largely due to the low permeability of those deposits that underlie the site and, subsequently, slow groundwater movement. Details on the groundwater dewatering mitigation strategy that will be employed at the Applicant Lands for those residential foundations occurring below the groundwater table are discussed in Sections 2.4.1 and 2.4.2 of the Stantec (2024) Functional Servicing Report.



Conclusions June 2024

- 11. A review of the MECP water well records for wells located within 500 m of the Applicant Lands indicates that there are 37 wells identified as being utilized for water supply (i.e., domestic, commercial, livestock, or municipal). One well is located within 20 m of the Applicant Lands, with the remaining 36 wells being positioned between 170 m to 500 m away from these lands. The average constructed depth of these private wells is 53 m BGS, indicating that groundwater drawn into these wells originates from the deeper confined Aquifer 2/3 (AFB3/AFD1) and/or the Bedrock Aquifer. As such, construction dewatering activities potentially occurring at the Applicant Lands are highly unlikely to interfere with the yields of these local private wells, given that the shallow overburden where these activities will occur is hydraulically separated from these previously mentioned deeper aquifer systems by the low permeability silt to clay-based glacial tills of Aquitard 1 (ATB1).
- 12. In areas where site servicing extends below the groundwater table, Stantec recommends that anti-seepage (cut-off) collars be installed to prevent the preferential movement of groundwater along the servicing alignments. The use of anti-seepage collars will likely be required given that most of the subsurface throughout the Applicant Lands is characterized by deposits where groundwater movement is more restricted (e.g., silt to clay-based soils). An assessment for the need, total number, and exact placements of anti-seepage collars along the servicing alignments can be explored in more detail during the detailed design phase of the project.



References June 2024

7.0 REFERENCES

- American Society for Testing and Materials (ASTM) International. 2009. ASTM D2488-09a, Standard Practice for Description and Identification of Soils (Visual-Manual Procedure).
- Armstrong, D.K. and Dodge, J.E.P. 2007. Paleozoic geology of southern Ontario; Ontario Geological Survey, Miscellaneous Release--Data 219.
- Bajc, A.F. and Shirota, J. 2007. Three--dimensional mapping of surficial deposits in the Regional Municipality of Waterloo, Southwestern Ontario; report in Ontario Geological Survey, Groundwater Resources Study 3, 42p.
- Bouwer, H., 1989. The Bouwer and Rice slug test--an update. Ground Water 27 (3): 304-309.
- Bouwer, H., and Rice, R.C., 1976. A slug test method for determining hydraulic conductivity of unconfined aquifers with completely or partially penetrating wells. *Water Resources Research* 12 (3): 423-428.
- Chapman, L.J. and D.F. Putnam. 1984. The Physiography of Southern Ontario. Ontario Geological Survey Special Volume 2, 270 pp.
- Conservation Ontario. 2013. Hydrogeological Assessment Submissions. Conservation Authority Guidelines for Development Applications. June 2013.
- (CVC-TRCA) Credit Valley Conservation Toronto and Region Conservation Authority. 2010. Low Impact Development Stormwater Management Planning and Design Guide Version 1.0.
- Duffield, G.M., 2014. AQTESOLV™ for Windows, Version 4.5 Professional. HydroSOLVE Inc., Reston, VA.
- Environment Canada. 2024. Kitchener-Waterloo Climate Station Historical Data, Climate ID 6144239. [Online] https://climate.weather.gc.ca/historical_data/search_historic_data_e.html. Accessed June 2024.
- Freeze, R.A. and J.A. Cherry. 1979. Groundwater. Prentice Hall, New Jersey, 604 p.
- (GRCA) Grand River Information Network (GRIN). 2021. https://data.grandriver.ca/applications.html.
- (GRCA) Grand River Conservation Authority. 2001. Grand River Regional Groundwater Study, Technical Report. June 2001.
- Karrow, P.F., 1993. Quaternary Geology of the Stratford-Conestogo Area, Southern Ontario. Ontario Geologic Survey Report 283.
- (LERSPC) Lake Erie Region Source Protection Committee. 2021a. Grand River Source Protection Area Draft Updated Assessment Report. Prepared June 17, 2021.
- (LERSPC) Lake Erie Region Source Protection Committee. 2021b. Grand River Source Protection Area, Draft Updated Source Protection Plan. June 17, 2021.



References June 2024

- (MECP) Ministry of Environment, Conservation and Parks. 2021a. Ministry of Environment and Climate Change Water Well Resources Database. Accessed on July 7, 2021.
- (MECP) Ministry of the Environment, Conservation and Parks. 2021b. Source Water Protection Information Atlas. Accessed September 2021.

 https://www.gisapplication.lrc.gov.on.ca/SourceWaterProtection/Index.html?viewer=SourceWaterProtection.SWPViewer&locale=en-US
- (MECP) Ministry of the Environment, Conservation and Parks (formerly Ministry of the Environment). 2018. Ontario Drinking Water Quality Standards. Ontario Regulation 169/03 under the Safe Drinking Water Act, 2002, S.O. 2002, C. 32. January 1, 2018.
- (MECP) Ministry of Environment, Conservation, and Parks (formerly MOE). 2009. Practices for the Collection and Handling of Drinking Water Samples Version 2.0. Ministry of the Environment, Laboratory Services Branch. April 1, 2009.
- (MECP) Ministry of the Environment (formerly MOEE). 1994. Water Management, Policies, Guidelines, Provincial Water Quality Objectives. July 1994.
- (MECP) Ministry of the Environment (formerly MOE). 1990. Wells. Regulation under the Ontario Water Resources Act. Regulation 903 of the Revised Regulations of Ontario, 1990.
- Paragon Engineering Limited. 2001. Wellesley Water Supply Project, Pre-Design Report. November 1991.
- (OGS) Ontario Geological Survey. 2010. Surficial geology of southern Ontario; Ontario Geological Survey, Miscellaneous Release -- Data 128-REV, ISBN 978-1-4435-2483-4.
- Region of Waterloo. 2015. Regional Official Plan (2031). Approved with modifications by the Ontario Municipal Board on June 18, 2015.
- Stantec Consulting Limited. 2024. Revised Functional Servicing Report Strohvest Subdivision Lands, Gerber Road, Township of Wellesley. June 2024.
- Stantec Consulting Limited. 2021. Final Geotechnical Investigation Report for Proposed Subdivision Development Stroh Lands, Gerber Road, Wellesley, Ontario. August 2021.
- Terraqua Investigations Ltd, 1995. The Study of the Hydrogeology of the Waterloo Moraine. December 1995.
- Todd, D.K. 1980. Groundwater Hydrology, 2nd Edition. Wiley, New York, 552 p.



APPENDIX A: Development Plans



use for any purpose other than that authorized by Stantec is forbidden.

Legal Description

Plan 1148, Part Lot 80, Registered Reference Plan 58R-3548, Part 1, Township of Wellesley, Regional Municipality of Waterloo

Information Required

Under Section 51(17) of the Planning Act, R.S.O 1990 c.P 13 as Amended

b) - As Shown c) - As Shown

d) - As Listed Below e) - As Shown f) - As Shown a) - As Shown

 Municipal Water) - Municipal Sanitary and Storm Sewers

- None Surveyor's Certificate

I hereby certify the boundaries of the subject lands and their relationship to the adjoining lands have been accurately and correctly shown.

Middledon Merrill McLean, O.L.S. Stantec Geomatics Ltd.

2024.05.29

Owner's Certificate /

I hereby authorize Stanted Consulting Ltd. to submit this Draft Plan of Subdivision on my behalf

Ron Strøh Date 1 446/24

Land Use Schedule

Lots/Blocks	Land Use	Area (ha)	# of Units (Min - Max)
Lots 1-50, 65-67, 71-74	Single Detached	2.696	57
Lots 51-64, 68-70	Semi Detached	1.046	34
Blocks 1-10	Townhouse	1.316	54
Block 11	Townhouse/Apartment	0.283	12 - 24
Block 12	Park	0.518	
Block 13	Linear Park	0.248	
Block 14	6.0m Walkway	0.019	
Block 15	Stormwater Management	1.276	
Block 16	0.3m Reserve	0.001	
Blocks 17-18	Road Widening	0.134	
Roads		2.612	
TOTAL		10.149	157- 169 Uni

ISSUED FOR DRAFT PLAN PAPROVAL	JJ	GR	2024.05.31
REVISED AS PER TOWNSHIP COMMENTS	JJ	GR	2023.07.26
ISSUED FOR CLIENT REVIEW	JJ	GR	2021.06.14
Revision	Ву	Appd	YYYY.MM.D
File Name: 161413217_R-DP	77 77	GR	2021.04.21

Permit-Seal

I hereby certify that the plan was prepared under the supervision of a Registered Professional Plann within the meaning of the Ontario Professional Planners institute Act, 1994.

STROHVEST ONTARIO INC.

WELLESLEY PROPERTY GERBER ROAD


TOWNSHIP OF WELLESLEY, ON

DRAFT PLAN OF SUBDIVISION

1 of 1


Project No. 1:750 161413217 Revision Sheet

Drawing No.



ORIGINAL SHEET - ARCH D

APPENDIX B: Figures





Legend

Subject Lands

Boundary of Lands Owned by the Applicant (Strohvest Ontario Inc.)

Monitoring Well (Stantec, 2023)

Monitoring Well (Stantec, 2021)

Borehole (Stantec, 2021)

Test Pit (Stantec, 2024)

Private Well Sampling Location

Topographic Contour (m AMSL)

Proposed Development Plan

Stormwater Catchment (Existing Conditions)




1:4,000 (At original document size of 11x17)

NOIes

1. Coordinate System: NAD 1983 UTM Zone 17N

2. Base features produced under license with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2021.

3. Ortholmagery © First Base Solutions, 2024. Imagery Date, 2022.





Project Location Township of Wellesley


161413217 REVA Prepared by CMC on 2024-06-24 Technical Review by GW on 2024-06-24


STROHVEST ONTARIO INC. STROH LANDS, WELLESLEY, ONTARIO HYDROGEOLOGICAL ASSESSMENT


Location Plan






















Manual

Levelogger



• Well Screen

---- Ground Surface



Notes:

- Precipitation and temperature data obtained from Environment Canada for the Kitchener/Waterloo Climate Station (Station ID 6144239), accessed June 2024.
- 2) Data enclosed in orange boxes not included in groundwater elevation ranges.

Client/Project

Strohvest Ontario Inc. Hydrogeological Assessment Strohvest Subdivision, Wellesley, Ontario


Figure No.


8

Title


HYDROGRAPHS MW01-21, MW02-21, and MW03-21














- 1) Precipitation and temperature data obtained from Environment Canada for the Kitchener/Waterloo Climate Station (Station ID 6144239), accessed June 2024.
- 2) Data enclosed in orange boxes not included in groundwater elevation ranges.

Client/Project


Strohvest Ontario Inc. Hydrogeological Assessment Strohvest Subdivision, Wellesley, Ontario


Figure No.


Title

HYDROGRAPHS MW04-21, MW05-21, and MW06-21











Legend

Subject Lands

Boundary of Lands Owned by the Applicant (Strohvest Ontario Inc.)

Monitoring Well (Stantec, 2023)

Monitoring Well (Stantec, 2021)

Borehole (Stantec, 2021)

Test Pit (Stantec, 2024)

Proposed Development Plan


358.54 Groundwater Elevation - June 15, 2021

Groundwater Contour (m

Interpreted Direction of Groundwater Flow

Topographic Contour (m

Stormwater Catchment (Existing Conditions)




NOIes

1. Coordinate System: NAD 1983 UTM Zone 17N

2. Base features produced under license with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2021.

3. Ortholmagery © First Base Solutions, 2024. Imagery Date, 2022.




Project Location Township of Wellesley

161413217 REVA Prepared by CMC on 2024-06-24 Technical Review by GW on 2024-06-24

STROHVEST ONTARIO INC. STROH LANDS, WELLESLEY, ONTARIO HYDROGEOLOGICAL ASSESSMENT

12

Groundwater Flow



APPENDIX C: Tables

TABLE 1
MONITORING WELL CONSTRUCTION DETAILS

Well ID	UTM Cod	ordinates	Eleva	ations			Well	Well		Screene	d Interval		Screened	Probable	Hydraulic
	Northing	Easting	Top of	Ground	Well	Well	Depth	Base	To	ор	Bot	ttom	Material Description (a)	Hydrostratigraphic	Conductivity (b)
			Casing	Surface	Stick-up	Depth		Elevation	Elev	ation	Elev	ation	(% of screened interval)	Unit	
			(m AMSL)	(m AMSL)	(m)	(m BTOC)	(m BGS)	(m AMSL)	(m BGS)	(m AMSL)	(m BGS)	(m AMSL)			(m/s)
MONITORING W	/ELLS														
MW01-21	4812989	518277	357.59	356.75	0.84	6.73	5.89	350.86	2.84	353.91	5.89	350.86	Clay (100%)	ATB1	7.3E-06
MW02-21	4813350	518320	362.03	361.12	0.90	7.06	6.16	354.97	3.11	358.02	6.16	354.97	Clayey Silt (50%), Clay (50%)	ATB1	5.8E-09
MW03-21	4813763	518382	361.02	360.18	0.84	6.97	6.13	354.05	3.08	357.10	6.13	354.05	Silt (100%)	ATB1	1.6E-07
MW04-21	4813019	518544	356.37	355.58	0.79	6.93	6.14	349.44	3.09	352.49	6.14	349.44	Clay (100%)	ATB1	5.4E-09
MW05-21	4813323	518547	362.79	361.96	0.83	7.00	6.17	355.79	3.12	358.84	6.17	355.79	Clay (50%), Silty Sand (50%)	ATB1	9.1E-08
MW06-21	4813624	518561	363.09	362.27	0.82	6.91	6.09	356.18	3.04	359.23	6.09	356.18	Clay (100%)	ATB1	-
MW105-23	4813327	518546	363.02	361.97	1.05	25.38	24.33	337.64	21.28	340.69	24.33	337.64	Clay Till (94%) / Sand (6%)	ATB1	2.8E-09
													GEOMEA	N (Applicant Lands) =	8.0E-08
													GEOME	AN (Subject Lands) =	7.8E-08

- (a) Refer to Appendix G for borehole and well construction logs.
- (b) Refer to Appendix H for hydraulic conductivity analytical solutions. Note that calculated geometric mean horizontal hydraulic conductivities presented in this table do not include results from MW105-23.

m AMSL = meters above mean sea level

m BGS = meters below ground surface

m BTOC = meters below top of well casing

- = data not available

TABLE 2
GROUNDWATER LEVEL DATA - MONITORING WELLS

Well ID	Date	Time		Well Depth		Screen Length	Top of Casing Elevation	Ground Surface Elevation	Pipe Stick-up	Gro	oundwater Le	evel
			(m BTOC)	(m BGS)	(m AMSL)	(m)	(m AMSL)	(m AMSL)	(m)	(m BGS) ⁽¹⁾	(m BTOC)	(m AMSL)
MW01-21	15-Jun-21 27-Aug-21 3-Aug-22 10-Feb-23 12-Apr-23 2-Nov-23 5-Dec-24 2-Apr-24 2-May-24 4-Jun-24	12:43 PM 12:01 PM 10:10 AM 12:55 PM 12:35 PM 12:40 PM 1:37 PM 10:54 AM 4:00 PM 12:12 PM	6.73	5.89	350.86	3.05	357.59	356.75	0.84	1.81 2.19 2.64 1.19 1.31 1.84 1.25 1.40 1.33 1.76	2.65 3.03 3.48 2.03 2.15 2.68 2.09 2.24 2.17 2.60	354.94 354.56 354.11 355.56 355.44 354.91 355.50 355.35 355.42 354.99
MW02-21	15-Jun-21 27-Aug-21 3-Aug-22 10-Feb-23 12-Apr-23 2-Nov-23 5-Dec-24 2-Apr-24 2-May-24 4-Jun-24	12:25 PM 12:20 PM 10:33 AM 12:30 PM 12:10 PM 1:38 PM 11:38 AM 11:09 AM 2:56 PM 12:00 PM	7.06	6.16	354.97	3.05	362.03	361.12	0.90	2.40 2.91 2.88 0.15 0.60 0.86 0.22 0.63 0.65 1.11	3.31 3.81 3.78 1.05 1.50 1.76 1.12 1.53 1.55 2.01	358.72 358.22 358.25 360.98 360.53 360.27 360.91 360.50 360.48 360.02
MW03-21	15-Jun-21 27-Aug-21 3-Aug-22 10-Feb-23 12-Apr-23 2-Nov-23 5-Dec-24 2-Apr-24 2-May-24 4-Jun-24	12:18 PM 12:30 PM 11:10 AM 11:15 AM 11:53 AM 2:05 PM 10:28 AM 11:24 AM 2:43 PM 11:48 AM	6.97	6.13	354.05	3.05	361.02	360.18	0.84	1.50 2.25 3.56 0.29 0.87 1.15 0.64 0.85 0.80	2.34 3.09 4.40 1.13 1.71 1.99 1.48 1.69 1.64	358.68 357.93 356.62 359.89 359.31 359.03 359.54 359.33 359.38

TABLE 2
GROUNDWATER LEVEL DATA - MONITORING WELLS

Well ID	Date	Time		Well Depth		Screen Length	Top of Casing Elevation	Ground Surface Elevation	Pipe Stick-up	Gro	oundwater Le	evel
			(m BTOC)	(m BGS)	(m AMSL)	(m)	(m AMSL)	(m AMSL)	(m)	(m BGS) ⁽¹⁾	(m BTOC)	(m AMSL)
MW04-21	15-Jun-21 27-Aug-21 3-Aug-22 10-Feb-23 12-Apr-23 2-Nov-23 5-Dec-24 2-Apr-24 2-May-24 4-Jun-24	11:19 AM 12:55 PM 9:29 AM 12:42 PM 11:07 AM 12:25 PM 1:05 PM 10:42 AM 3:38 PM 12:26 PM	6.93	6.14	349.44	3.05	356.37	355.58	0.79	2.11 2.34 2.39 0.85 1.18 1.75 0.85 1.14 1.09 1.48	2.90 3.13 3.18 1.64 1.97 2.54 1.64 1.93 1.88 2.27	353.47 353.24 353.19 354.73 354.40 353.83 354.73 354.44 354.49 354.10
MW05-21	15-Jun-21 27-Aug-21 3-Aug-22 10-Feb-23 12-Apr-23 2-Nov-23 5-Dec-24 2-Apr-24 2-May-24 4-Jun-24	11:38 AM 12:47 PM 11:45 AM 12:10 PM 11:29 AM 1:05 PM 12:15 PM 12:35 PM 3:18 PM 12:38 PM	7.00	6.17	355.79	3.05	362.79	361.96	0.83	1.38 2.06 2.24 0.51 0.81 1.17 0.71 0.77 0.71	2.21 2.89 3.07 1.34 1.64 2.00 1.54 1.60 1.54 1.77	360.58 359.90 359.72 361.45 361.15 360.79 361.25 361.19 361.25 361.02
MW06-21	15-Jun-21 27-Aug-21 3-Aug-22 10-Feb-23 12-Apr-23 2-Nov-23 5-Dec-24 2-Apr-24 2-May-24 4-Jun-24	11:44 AM 12:39 PM 11:31 AM 11:47 AM 11:41 AM 2:18 PM 9:57 AM 11:43 AM 2:36 PM 11:36 AM	6.91	6.09	356.18	3.05	363.09	362.27	0.82	3.24 2.80 2.97 0.65 0.84 1.56 0.69 0.87 0.88 1.32	4.06 3.62 3.79 1.47 1.66 2.38 1.51 1.69 1.70 2.14	359.03 359.47 359.30 361.62 361.43 360.71 361.58 361.40 361.39 360.95

TABLE 2
GROUNDWATER LEVEL DATA - MONITORING WELLS

Well ID	Date	Time		Well Depth		Screen Length	Top of Casing Elevation	Ground Surface Elevation	Pipe Stick-up	Gro	oundwater Le	evel
			(m BTOC)	(m BGS)	(m AMSL)	(m)	(m AMSL)	(m AMSL)	(m)	(m BGS) ⁽¹⁾	(m BTOC)	(m AMSL)
MW105-23	2-Nov-23 5-Dec-24 2-Apr-24 2-May-24 4-Jun-24	1:15 PM 9:57 AM 11:53 AM 3:20 PM 12:37 PM	25.38	24.33	337.64	3.05	363.02	361.97	1.05	6.70 5.67 5.08 5.03 5.04	7.75 6.72 6.13 6.08 6.09	355.27 356.30 356.89 356.94 356.93

(1) A negative value indicates that the water level measured in the pipe is located above ground surface

m BGS = meters below ground surface

m BTOC = meters below top of casing

DRY = no groundwater or surface water was observed in the piezometer or watercourse, respectively

- = measurement not available

TABLE 3
INFILTRATION ESTIMATES

Testing	Horizontal	Vertical Hy		Infiltration	Pit Depth	Screened	Soil Substrate Tested
Location	Hydraulic	Conduct	ivity ⁽²⁾	Rate ⁽¹⁾		Interval	(% of screened interval)
ID	Conductivity						
	(m/s)	(cm/s)	(m/s)	(mm/hr)	(m BGS)	(m BGS)	
In-situ Hyd	raulic Response 1	Testing Testing					
MW01-21	7.3E-06	7.3E-05	7.3E-07	42	-	2.8 - 5.8	Clay (100%)
MW02-21	5.8E-09	5.8E-08	5.8E-10	6	-	3.1 - 6.1	Clayey Silt (50%), Clay (50%)
MW03-21	1.6E-07	1.6E-06	1.6E-08	16	-	3.1 - 6.1	Silt (100%)
MW04-21	5.4E-09	5.4E-08	5.4E-10	6	-	3.1 - 6.1	Clay (100%)
MW05-21	9.1E-08	9.1E-07	9.1E-09	13	-	3.1 - 6.1	Clay (50%), Silty Sand (50%)
		GEOMEAN =	8.0E-09	13		<u> </u>	

- (1) Infiltration rate calculated based on established relationship between vertical hydraulic conductivity and infiltration rate presented in *Credit Valley Conservation and Toronto and Region Conservation (2010) Low Impact Stormwater Management Planning and Design Guideline Version 1.0.*
- (2) Vertical hydraulic conductivities assumed to be one order of magnitude lower than in-situ measured horizontal hydraulic conductivities.

TABLE 4 - GROUNDWATER QUALITY RESULTS, ONSITE MONITORING WELLS

Sample Location	1			MW01-21		l ww	02-21	<u> </u>	MW03-21		l ww	04-21		MW)5-21	
Sample Date			27-May-21	13-Apr-23	5-Dec-23	13-Apr-23	5-Dec-23	27-May-21	13-Apr-23	5-Dec-23	13-Apr-23	5-Dec-23	27-May-21	27-May-21	13-Apr-23	5-Dec-23
Sample ID			BH01-21	BH01-21	BH01-21	BH02-21	BH02-21	BH03-21	BH03-21	BH03-21	BH04-21	BH04-21	BH05-21	QC-01	BH05-21	BH05-21
Sampling Company			STANTEC	STANTEC	STANTEC	STANTEC	STANTEC	STANTEC	STANTEC	STANTEC	STANTEC	STANTEC	STANTEC	STANTEC	STANTEC	STANTEC
Laboratory			BV	BV	BV	BV	BV	BV	BV	BV	BV	BV	BV	BV	BV	BV
Laboratory Work Order			C1E5622	C3A5628	C3AV735	C3A5628	C3AV735	C1E5622	C3A5628	C3AV735	C3A5628	C3AV735	C1E5622	C1E5622	C3A5628	C3AV735
Laboratory Sample ID	Units	O. Reg. 169/03	PRQ479	VOD661	XUM771	VOD659	XUM768	PRQ480	VOD660	XUM767	VOD656	XUM770	PRQ481	PRQ482	VOD658	XUM769
Sample Type	Offics	O. Reg. 169/03												Field Duplicate		
General Chemistry																
Alkalinity, Carbonate (as CaCO3) Alkalinity, Total (as CaCO3)	mg/L mg/L	n/v 30-500 ^D	2.8 300	3.1 310	2.1 300	3.2 270	2.6 290	3.1 380	2.9 350	2.5 360	2.7 190	1.7 200	2.5 290	3.2 280	3.0 300	2.4 310
Anion Sum	me/L	n/v	8.85	11.5	9.57	6.83	7.08	8.86	8.68	8.83	5.08	5.03	7.54	7.42	8.21	8.11
Bicarbonate(as CaCO3, Calculated)	mg/L	n/v	300	310	300	270	280	380	350	350	190	200	280	280	290	300
Cation Sum	me/L	n/v	8.86	13.0	9.90	6.95	7.19	9.26	8.98	9.07	5.42	6.10	7.66	7.65	8.57	8.19
Chloride	mg/L	250 ^B	76	140	92	5.3	3.9	5.7	6.0	5.6	13	11	12	11	12	12
Electrical Conductivity, Lab	µmhos/cm	n/v	820	1,200	970	650	660	780	780	800	500	500	680	670	740	750
Hardness (as CaCO3)	mg/L	80-100 ^D	370 ^D	440 ^D	370 ^D	270 ^D	280 ^D	450 [□]	440 ^D	440 ^D	190 ^D	220 ^D	350 ^D	350 ^D	390 ^D	380 ^D
Ion Balance	%	n/v	0.0500 0.919	6.10 1.02	1.71 0.784	0.860 0.833	0.730 0.769	2.22 1.13	1.68 1.08	1.36 1.04	3.22 0.695	9.59 0.580	0.840 0.868	1.56 0.972	2.13 0.987	0.500 0.886
Langelier Index (at 20 C) Langelier Index (at 4 C)	none none	n/v n/v	0.919	0.774	0.784	0.833	0.769	0.878	0.834	0.794	0.695	0.580	0.868	0.972	0.987	0.637
Nitrate (as N)	mg/L	10.0 _d ^A	<0.10	<0.10	<0.10	0.60	0.39	<0.10	<0.10	<0.10	<0.10	<0.10	0.12	<0.10	<0.10	<0.10
Nitrate + Nitrite (as N)	mg/L	10.0 _d ^A	<0.10	<0.10	<0.10	0.60	0.39	<0.10	<0.10	<0.10	<0.10	<0.10	0.12	0.11	<0.10	<0.10
Nitrite (as N)	mg/L	1.0 _d ^A	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	0.015	<0.010	<0.010
pH, lab	S.U.	6.5-8.5 ^D	8.01	8.03	7.88	8.11	7.98	7.94	7.95	7.88	8.19	7.97	7.96	8.08	8.03	7.91
Saturation pH (at 20 C)	none	n/v	7.09	7.01	7.09	7.27	7.21	6.81	6.87	6.84	7.49	7.39	7.10	7.10	7.05	7.03
Saturation pH (at 4 C) Sulfate	none	n/v	7.34 33	7.25 68	7.34 43	7.52 59	7.46 59	7.06 52	7.11 69	7.09 73	7.74 44	7.64 38	7.35 70	7.35 68	7.29 93	7.28 80
Total Dissolved Solids (Calculated)	mg/L mg/L	500 _h ^B 500 ^B	460	660 ^B	520 ^B	370	380	470	460	470	290	300	400	400	450	440
Total Suspended Solids	mg/L	n/v	1,700	-	-	-	-	55,000	400	-	290	-	85.000	59.000	-	- 440
Turbidity, Lab	NTU	5, B, D	1,800 ^B	_	_	_	_	4,700 ^B	_	_	_	_	2,100 ^B	3,500 ^B	_	_
Nutrients	I		,			I					I.			,		
Ammonia (as N)	mg/L	n/v	0.062	0.10	0.11	<0.050	<0.050	0.071	0.070	0.068	0.082	0.15	0.097	0.093	0.090	0.10
Dissolved Organic Carbon (DOC)	mg/L	5 ^B	0.88	1.4	1.2	0.76	0.58	0.90	0.98	1.2	1.3	1.5	0.99	1.0	0.97	1.3
Orthophosphate (as P) Metals	mg/L	n/v	<0.010	<0.010	<0.010	0.017	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
Aluminum	ma/l	0.1 ^D	<0.0049	0.32 ^D	<0.0049	0.015	<0.0049	0.010	<0.0049	<0.0049	<0.0049	0.44 ^D	0.021	0.0053	0.0049	<0.0049
Antimony	mg/L mg/L	0.1 0.006 ^A	<0.0049	<0.00050	<0.0049	<0.0050	<0.0049	<0.0050	<0.0049	<0.0049	<0.0049	<0.00050	<0.0050	<0.0055	<0.0049	<0.0049
Arsenic	mg/L	0.000 0.01 ^A	0.0014	0.0017	0.0020	<0.0010	<0.0010	0.0012	0.0013	0.0015	<0.0000	0.0011	0.0029	0.0027	0.0027	0.0014
Barium	mg/L	1 ^A	0.13	0.16	0.13	0.11	0.11	0.14	0.12	0.098	0.061	0.064	0.13	0.13	0.14	0.11
Beryllium	mg/L	n/v	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040	<0.00040
Boron	mg/L	5 ^A	0.063	0.048	0.060	0.12	0.10	0.016	0.015	0.012	0.14	0.14	0.029	0.029	0.024	0.016
Cadmium Calcium	mg/L mg/L	0.005 ^A n/v	<0.000090 78	<0.000090 100	<0.000090 78	<0.000090 54	<0.000090 59	<0.000090 120	<0.000090 110	<0.000090 120	<0.000090 44	<0.000090 54	<0.000090 78	<0.000090 77	<0.000090 87	<0.000090 87
Chromium	mg/L	0.05 ^A	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050
Cobalt	mg/L	n/v	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	0.00074	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050	<0.00050
Copper	mg/L	1 ^B	<0.00090	0.0014	<0.00090	<0.00090	<0.00090	<0.00090	<0.00090	<0.00090	0.0022	0.0022	<0.00090	<0.00090	0.0010	<0.00090
Iron	mg/L	0.3 ^B	<0.10	0.29	<0.10	<0.10	<0.10	<0.10	0.21	0.45 ^B	<0.10	0.49 ^B	<0.10	<0.10	<0.10	<0.10
Lead	mg/L	0.01 ^A	<0.00050 42	<0.00050 47	<0.00050 41	<0.00050 33	<0.00050 33	<0.00050 37	<0.00050 38	<0.00050 35	<0.00050 19	0.00065 21	<0.00050 38	<0.00050 38	<0.00050 41	<0.00050 39
Magnesium Manganese	mg/L mg/L	n/v 0.05 ^B	0.052 ^B	0.054 ^B	0.044	0.0042	0.0053	0.065 ^B	0.044	0.040	0.053 ^B	0.085 ^B	0.046	0.043	0.076 ^B	0.050
Molybdenum	mg/L	n/v	0.0042	0.0040	0.0046	0.0084	0.0076	0.0012	0.00087	0.00092	0.0085	0.0074	0.0034	0.0036	0.0024	0.0021
Nickel	mg/L	n/v	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	<0.0010	0.0014	<0.0010	<0.0010	0.0015	<0.0010
Phosphorus	mg/L	n/v	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
Potassium Selenium	mg/L mg/L	n/v 0.05 ^A	2.4 <0.0020	2.6 <0.0020	2.4 <0.0020	2.1 <0.0020	2.1 <0.0020	1.7 <0.0020	1.3 <0.0020	1.2 <0.0020	1.3 <0.0020	1.4 <0.0020	2.0 <0.0020	2.0 <0.0020	1.8 <0.0020	1.5 <0.0020
Silicon	mg/L	0.05 n/v	7.3	9.2	8.0	6.2	6.4	8.0	7.9	8.3	6.3	6.8	8.7	8.5	8.6	8.4
Silver	mg/L	n/v	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090	<0.000090
Sodium	mg/L	200 _g ^B 20 _g ^C	33 ^c	93 ^c	58 ^c	34 ^c	34 ^c	5.7	5.4	5.0	37 ^c	36 ^c	13	14	18	14
Strontium Thallium	mg/L	n/v	1.0	1.1	1.1	1.3	1.1	0.36 <0.00050	0.39	0.34 <0.000050	0.59 <0.00050	0.66	0.52	0.53	0.46	0.30
i nailium Titanium	mg/L mg/L	n/v n/v	<0.000050 <0.0050	<0.000050 0.014	<0.000050 <0.0050	<0.000050 <0.0050	<0.000050 <0.0050	<0.00050	<0.000050 <0.0050	<0.00050	<0.00050	<0.000050 0.018	<0.000050 <0.0050	<0.000050 <0.0050	<0.000050 <0.0050	<0.00050 <0.0050
Uranium	mg/L	0.02 ^A	0.0017	0.0037	0.0028	0.0028	0.0029	0.0011	0.00062	0.00053	0.0017	0.0016	0.0027	0.0028	0.0021	0.0021
Vanadium	mg/L	n/v	<0.00050	0.00079	<0.00050	0.00076	0.00083	0.00053	<0.00050	<0.00050	<0.00050	0.0016	<0.00050	<0.00050	<0.00050	<0.00050
Zinc	mg/L	5 ^B	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050	<0.0050



Project No.: 161413217 Page 1 of 2

TABLE 4 - GROUNDWATER QUALITY RESULTS, ONSITE MONITORING WELLS

Sample Location		I	MWO	16-21
Sample Date			13-Apr-23	5-Dec-23
•			•	
Sample ID			BH06-21	BH06-21
Sampling Company			STANTEC	STANTEC
Laboratory Laboratory Work Order			BV C3A5628	BV C3AV735
Laboratory Sample ID			VOD657	XUM766
Sample Type	Units	O. Reg. 169/03		
General Chemistry	T			
Alkalinity, Carbonate (as CaCO3)	mg/L	n/v	3.7	2.7
Alkalinity, Total (as CaCO3) Anion Sum	mg/L me/L	30-500 ^D n/v	280 6.92	290 7.08
Bicarbonate(as CaCO3, Calculated)	mg/L	n/v	280	290
Cation Sum	me/L	n/v	7.08	7.19
Chloride	mg/L	250 ^B	2.2	2.4
Electrical Conductivity, Lab	µmhos/cm	n/v	640	660
Hardness (as CaCO3)	mg/L	80-100 ^D	280 ^D	290 ^D
Ion Balance	%	n/v	1.20	0.780
Langelier Index (at 20 C)	none	n/v	0.871	0.758
Langelier Index (at 4 C)	none	n/v	0.622	0.509
Nitrate (as N)	mg/L	10.0 _d ^A	<0.10	<0.10
Nitrate + Nitrite (as N)	mg/L	10.0 _d ^A	<0.10	<0.10
Nitrite (as N)	mg/L	1.0 _d ^A	<0.010	<0.010
pH, lab	S.U.	6.5-8.5 ^D	8.15	7.99
Saturation pH (at 4.0)	none	n/v	7.28	7.23 7.48
Saturation pH (at 4 C) Sulfate	none mg/L	n/v 500 _h ^B	7.53 60	7.46 55
Total Dissolved Solids (Calculated)	mg/L	500 _h 500 ^B	370	370
Total Suspended Solids	mg/L	500 n/v	-	-
Turbidity, Lab	NTU	5 ^{B D}	-	-
Nutrients		o _l		
Ammonia (as N)	mg/L	n/v	<0.050	<0.050
Dissolved Organic Carbon (DOC)	mg/L	5 ^B	0.83	0.95
Orthophosphate (as P)	mg/L	n/v	<0.010	<0.010
Metals	T			
Aluminum	mg/L	0.1 ^D	0.0072	0.0054
Antimony	mg/L	0.006 ^A	<0.00050	<0.00050
Arsenic	mg/L	0.01 ^A	<0.0010	<0.0010
Barium Beryllium	mg/L mg/L	1 ^A n/v	0.12 <0.00040	0.11 <0.00040
Boron	mg/L	5 ^A	0.13	0.12
Cadmium	mg/L	0.005 ^A	<0.000090	<0.000090
Calcium	mg/L	n/v	52	55
Chromium	mg/L	0.05 ^A	<0.0050	<0.0050
Cobalt	mg/L	n/v	<0.00050	<0.00050
Copper	mg/L	1 ^B	0.0018	<0.00090
Iron	mg/L	0.3 ^B	<0.10	<0.10
Lead	mg/L	0.01 ^A	<0.00050	<0.00050
Magnesium Manganese	mg/L mg/L	n/v 0.05 ^B	37 0.0056	37 0.018
Molybdenum	mg/L	0.05 n/v	0.0063	0.0059
Nickel	mg/L	n/v	<0.0010	<0.0039
Phosphorus	mg/L	n/v	<0.10	<0.10
Potassium	mg/L	n/v	2.0	2.1
Selenium	mg/L	0.05 ^A	<0.0020	<0.0020
Silicon Silver	mg/L mg/L	n/v n/v	6.3 <0.000090	6.5 <0.000090
Sodium	mg/L	200 _g ^B 20 _g ^C	33 ^C	31 ^C
Strontium	mg/L	n/v	1.8	1.5
Thallium	mg/L	n/v	<0.00050	<0.000050
Titanium	mg/L	n/v	<0.0050	<0.0050
Uranium	mg/L	0.02 ^A	0.0032	0.0031
Vanadium Zinc	mg/L mg/l	n/v 5 ^B	0.00084	0.00098 <0.0050
Zinc	mg/L	<u>5</u> -	<0.0050	<0.0050

Notes:

O. Reg. 169/03 Ontario Drinking Water Quality Standards (January 1, 2018)

Applicable for all waters at the point of consumption.

When sulfate levels exceed 500 mg/L, water may have a laxative effect on some people.

The operational guidelines for filtration processes are provided as performance criteria in the Procedure for Disinfection of Drinking Water in Ontario.

Α	Schedule 2 - Chemical Standards (expressed as a maximum acceptable concentration)
В	ODWS Table 4 - Chemical/Physical Objectives and Guidelines, Aesthetic Objectives
С	ODWS Table 4 - Medical Officer of Health Reporting Limit
D	ODWS Table 4 - Chemical/Physical Objectives and Guidelines, Operational Guidelines
6.5 ^A	Concentration exceeds the indicated standard.
15.2	Measured concentration did not exceed the indicated standard.
<0.50	Laboratory reporting limit was greater than the applicable standard.
< 0.03	Analyte was not detected at a concentration greater than the laboratory reporting limit.
n/v	No standard/guideline value.
-	Parameter not analyzed / not available.
d	Where both nitrate and nitrite are present, the total of the two should not exceed 10 mg/L (as nitrogen).
g	The aesthetic objective for sodium in drinking water is 200 mg/L. The local Medical Officer of Health should be notified when the sodium concentration exceeds 20 mg/L so that this information may be communicated to
	local physicians for their use with patients on sodium restricted diets.




TABLE 5 GROUNDWATER QUALITY RESULTS OFFSITE PRIVATE WELLS

Sample Location			RW01	R	W02
Sample Date			15-Jun-21	6-Aug-21	6-Aug-21
Sample ID			RW01	RW02	RW02 Lab-Du
Sampling Company			STANTEC	STANTEC	STANTEC
Laboratory Laboratory Work Order			BV C1G5523	BV C1M2547	BV C1M2547
Laboratory Sample ID			PVV199	QHU792	QHU792
Sample Type	Units	ODWS			Lab Replicate
General Chemistry					
Alkalinity, Carbonate (as CaCO3)	mg/L	n/v	2.1	3.3	_
Alkalinity, Total (as CaCO3)	mg/L	30-500 ^E	230	210	_
Anion Sum	me/L	n/v	9.36	13.0	
			230		-
Bicarbonate(as CaCO3, Calculated)	mg/L	n/v		200	-
Cation Sum	me/L	n/v	8.68	12.3	-
Chloride	mg/L	250 ^C	2.7	2.9	-
Electrical Conductivity, Lab	µmhos/cm	n/v	840	1,200	-
Hardness (as CaCO3)	mg/L	80-100 ^E	420 ^E	580 [€]	-
Ion Balance	%	n/v	3.76	2.50	-
Langelier Index (at 20 C)	none	n/v	0.919	1.21	-
Langelier Index (at 4 C)	none	n/v	0.671	0.958	-
Nitrate (as N)	mg/L	10.0 _d ^B	<0.10	<0.10	<0.10
Nitrate + Nitrite (as N)	mg/L	10.0 _d ^B	-	-	-
Nitrite (as N)	mg/L	1.0 _d ^B	<0.010	<0.010	<0.010
pH, lab	S.U.	6.5-8.5 ^E	7.99	8.23	-
Saturation pH (at 20 C)	none	n/v	7.07	7.03	_
Saturation pH (at 4 C)	none	n/v	7.32	7.28	_
Sulfate	mg/L	500 _h ^C	220	420	_
Total Dissolved Solids (Calculated)	mg/L	500 ^c	530 ^c	780 ^C	
Total Suspended Solids	_	n/v	<10	15	-
•	mg/L	5, ^C , E		49 ^C	48 ^C
Turbidity, Lab Microbiological	NTU	o _i j	1.5	49	40
E. Coli/Fecal Coliform	cfu/100mL	0 ^A	0	0	_
Total Coliform Background	cfu/100mL	n/v	0	Ŭ	
Total Coliforms	cfu/100mL	0 ^A	0	0	-
Nutrients	CIU/ TOUTIL	Ü	U	U	-
Ammonia (as N)	mg/L	n/v	0.33	0.065	_
Dissolved Organic Carbon (DOC)	mg/L	5 ^C	0.60	0.64	_
Orthophosphate (as P)	mg/L	n/v	<0.010	<0.010	_
Metals	mg/L	117 V	-0.010	-0.010	-
Aluminum	mg/L	0.1 ^E	<0.0049	<0.0049	-
Antimony	mg/L	0.006 ^B	<0.00050	<0.00050	_
Arsenic	mg/L	0.01 ^B	<0.0010	0.0010	_
Barium	mg/L	1 ^B	0.064	0.024	
	_	n/v	<0.0044	<0.0040	-
Beryllium	mg/L	5 ^B			-
Boron	mg/L	_	0.024	0.047	-
Cadmium	mg/L	0.005 ^B	<0.000090	<0.000090	-
Calcium	mg/L	n/v	110	150	-
Chromium	mg/L	0.05 ^B	<0.0050	<0.0050	-
Cobalt	mg/L	n/v	<0.00050	<0.00050	-
Copper	mg/L	1 ^c	0.0029	<0.00090	
Iron	mg/L	0.3 ^C	0.43 ^C	5.9 ^c	-
Lead	mg/L	0.01 ^B	<0.00050	<0.00050	-
Lithium	mg/L	n/v	0.0053	0.0087	-
Magnesium	mg/L	n/v	35	50	-
Manganese	mg/L	0.05 ^C	0.013	0.080 ^c	-
Molybdenum	mg/L	n/v	0.0013	0.0016	-
Nickel	mg/L	n/v	<0.0010	<0.0010	_
Phosphorus	mg/L	n/v	<0.10	<0.10	_
Potassium	mg/L	n/v	1.1	1.4	_
Selenium	mg/L	0.05 ^B	<0.0020	<0.0020	_
	_				_
Silicon	mg/L	n/v	6.8	4.7	_
Silver	mg/L	n/v	<0.000090	<0.000090	-
Sodium	mg/L	200 _g ^C 20 _g ^D	6.9	11	-
Strontium	mg/L	n/v	35	38	-
Thallium	mg/L	n/v	<0.000050	<0.000050	-
Titanium	mg/L	n/v	<0.0050	<0.0050	-
Uranium	mg/L	0.02 ^B	0.00090	0.00016	-
Vanadium	mg/L	n/v	<0.00050	<0.00050	_
variadium					


ODWS	Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines (MOE, 2006), in support of O.Reg 169/03 (January 1, 2018)			
A	Schedule 1 - Microbiological Standards (expressed as a maximum)			
В	Schedule 2 - Chemical Standards (expressed as a maximum acceptable concentration)			
С	ODWS Table 4 - Chemical/Physical Objectives and Guidelines, Aesthetic Objectives			
D	ODWS Table 4 - Medical Officer of Health Reporting Limit			
E	ODWS Table 4 - Chemical/Physical Objectives and Guidelines, Operational Guidelines			
6.5 ^A	Concentration exceeds the indicated standard.			
15.2	Measured concentration did not exceed the indicated standard.			
<0.50	Laboratory reporting limit was greater than the applicable standard.			
<0.03	Analyte was not detected at a concentration greater than the laboratory reporting limit.			
n/v	No standard/guideline value.			
-	Parameter not analyzed / not available.			
d	Where both nitrate and nitrite are present, the total of the two should not exceed 10 mg/L (as nitrogen).			
CD g	The aesthetic objective for sodium in drinking water is 200 mg/L. The local Medical Officer of Health should be notified when the sodium concentration			
	exceeds 20 mg/L so that this information may be communicated to local physicians for their use with patients on sodium restricted diets.			
h	When sulfate levels exceed 500 mg/L, water may have a laxative effect on some people.			
i	Applicable for all waters at the point of consumption.			
j	The operational guidelines for filtration processes are provided as performance criteria in the Procedure for Disinfection of Drinking Water in Ontario.			



APPENDIX D:Regional Groundwater Mapping




Source: Grand River Conservation Authority. 2001. Grand River Regional Groundwater Study, Technical Report. June 2001.



Source: Grand River Information Network (GRIN). 2021. https://data.grandriver.ca/applications.html.

APPENDIX E:Source Water Protection Plan Mapping

10.6 Schedule B: Region of Waterloo Groundwater Systems: Map A





Significant Drinking Water Threat Policy Applicability

	Significant Drinking Water	Vulnerability Scores on Map		
	Threat Policy Categories	30	8	2,4,6
1.	Waste Disposal			
2.	Sewage Systems			
3, 4.	Agricultural Source Material			
6, 7.	Non-Agricultural Source Material*			
8, 9.	Commercial Fertilizer*			
10, 11.	Pesticide			
12,13.	Road Salt *			
14.	Storage of Snow			
15.	Fuel			
16.	DNAPLs			
17.	Organic Solvents			
18.	Aircraft De-icing			7
21.	Livestock Area			
22.	Oil Pipelines			


Note: This table provides a summary of the activities listed in the Clean Water Act (2006) that apply as Prescribed Drinking Water Threats | PDWT| within Non-GUDI Wellhead Protection Zones on this map. For details refer to the Drinking Water Threats Tables from the Ministry of the Environment and Climate Change, and the text of this Source Protection Plan. 'Application of Commercial Fertilizer, Non-Agricultural Source Material, and Road Salt may not be a significant drinking water threat in some areas due to the %managed land, livestock density, and/or % impervious surfaccious lives for the services of the text of this plan for further details.





- 1. Updated July 24, 2019
- Larger scale mapping of some map layers, including roads and vulnerability scores, is available at www.sourcewater.ca.
- 3. This map is for illustrative purposes only. Information contained hereen is not a substitute for professional review or a site survey and is subject to change without notice. The Grand River Conservation Authority takes no responsibility for, nor guarantees, the accuracy of the information contained on this map. Any interpretations or conclusions drawn from this map are the sole responsibility of the user.

FIGURE E-1: Water Quantity Vulnerable Areas



Ontario © Queen's Printer for Ontario, 2021

Map Created: 9/21/2021

Map Center: 43.45219 N, -80.71499 W

APPENDIX F:

Region of Waterloo Source Water Protection Land Use Categories

Schedule B: Source Water Protection Land Use Categories

Category 'A'

- Waste treatment and disposal facilities, including lagoons, landfills, communal/municipal sewage treatment facilities and including large sewage vaults at sewage pumping stations, but not including facilities regulated under the Nutrient Management Act.
- Salvage yards, including automobile wrecking yards or premises
- Bulk storage of hazardous chemicals and hazardous substances (as listed in O.Reg. 347 under the <u>Environmental Protection Act</u>), including bulk storage of oil, gasoline or petroleum products, and including transportation terminals for these substances/chemicals (including truck/trailer/container parking, washing or cleaning depots)

Category 'B'

- Bulk storage of road salt and snow disposal sites
- Primary metal manufacturing, including iron and steel mills and ferro-alloy manufacturing; steel product manufacturing from purchased steel; alumina and aluminum production and processing; non-ferrous metal production and processing; and foundries
- Manufacturing of fabricated metal products, including manufacturing of unfinished metal products and metal finishing operations
- Manufacturing and assembly of transportation equipment, including motor vehicles and parts, aerospace products and parts, rail cars, ships and boats
- Manufacturing of machinery, including agricultural, commercial, industrial, and other machinery
- Chemical manufacturing including chemicals; resins; fertilizers, pesticides and other agricultural chemicals; pharmaceutical and medicines; paint, coating and adhesives; inks and other chemicals but excluding soap and cleaning compound manufacturing. Including manufacturing, packaging, repackaging, and bottling. Excludes uses involving bulk storage of hazardous materials which are included under Category 'A'
- Manufacturing of petroleum and coal products, including manufacturing of asphalt materials. Excludes uses involving bulk storage of hazardous materials which are included under Category 'A'
- Manufacturing of electronic components such as semiconductors, printed circuit boards, and cathode ray tubes
- Manufacturing of electrical equipment, appliances and components
- Commercial or industrial dry cleaning of textiles and textile products, excluding depots not performing on-site dry cleaning
- Manufacturing of leather and allied products including footwear
- Wood and wood product preservation and treatment
- Gasoline stations and other retail establishments with gasoline sales
- Wholesale/distributing of cleaning products, pesticides, herbicides, fungicides and chemicals

Category 'C'

- Manufacturing of rubber products
- Manufacturing of soap, cleaning compounds and toilet preparations
- Textile and fabric finishing and fabric coating
- Manufacturing of plastic products
- Manufacturing of wood products including wood furniture, and excluding wood preservation
- Manufacturing of glass and glass products
- Manufacturing of paper and paper products including newsprint and boxes
- Printing and related support activities, excluding business support services such as photocopy services
- Repair and Maintenance of automobiles and automotive machinery, electronic equipment, industrial and commercial machinery, and personal and household goods repair
- Golf courses
- Airports, train and public transit terminals, except terminals with no fuel storage or transfer of shipped goods or materials
- Medical, health and other laboratories (other than clinics generally associated with commercial plazas)
- Miscellaneous manufacturing not included elsewhere, including jewellery, silverware, medical equipment and signs
- Recycling, recovery, or remanufacturing of materials including the collection, processing, manufacturing, or reuse of post-consumer or post-industrial materials, not including recycling or disposal of hazardous materials, and not including salvage yards or facilities with outdoor operations which are Category 'A' uses

Category 'D'

- Underground parking garages
- Geothermal wells
- Mineral aggregate operations including wayside pits and quarries

Schedule C: Other information and materials that may be required to process an application

Digital Plans

Subdivision/Condominium Plan(s)

Cultural

- Archaeological Assessment
- Cultural Heritage Impact Assessment

Environmental

- Aggregate/Mineral Resource Analysis
- Local Air Quality Study

- Salt Impact Assessment
- Salt Management Plans
- Cut & Fill Analysis
- Environmental Impact Statement
- Comprehensive Environmental Impact Statement
- Natural Habitat Inventory
- Environmental Management Plan
- Tree Conservation and Planting Plans
- Provincial and Federal Requirements for Fish Habitat
- Slope Stability Study and Report
- Floodline Delineation Study/Hydraulics Study
- Hydrologic and Hydrogeologic Studies
- Source Water Protection Studies
- Best Management Practices for development within the Regional Recharge Area
- Best Management Practices (for golf courses)
- Environmental Site Assessment and/or Record of Site Condition
- Cumulative Impact Assessment
- Site Plan, Spill Protection Measures and other Best Management Practices for Mineral Aggregate Operations
- Final Rehabilitation Plan (for mineral aggregate operations)

Construction, Servicing and Infrastructure

- Preliminary Grading Plan
- Preliminary Stormwater Management Report/Plan and/or update to an existing Stormwater Management Plan
- Soils/Geotechnical Study
- Construction Methods and Spills Protection Measures
- Servicing Options Report
- Development Phasing Plan
- Water and Wastewater Servicing Plans and associated studies
- Hydrogeologic Studies for Privately Serviced Developments
- Impact on Existing Infrastructure Study

Land Use Compatibility

- Air Quality Assessment
- Dust Impact Analysis
- Land Use Compatibility Study
- Landfill Impact Study
- Agricultural Impact Assessment
- Minimum Distance Separation
- Noise Study
- Odour Impact Assessment
- Vibration Study
- Written Provincial approval (pursuant to the Environmental Protection Act for development within former waste management facilities)

- Provincial and Federal Requirements for Alternative and/or Renewable Energy Systems and Fish Habitat
- Approval from the Grand River Conservation Authority

Planning

- Affordable Housing Report/Rental Conversion Assessment
- Detailed Property Assessment of Affordable Rental Housing
- Farm Viability Study
- Planning Report
- Land Use Study for Retail/Commercial Land Uses in Support of the Planned Community Structure or Retail/Commercial Impact Analysis
- Retail Commercial Market Impact Study
- Urban Design Report/Brief

Transportation

- Transportation Impact Study
- Transportation System Impact Study
- Parking Analysis
- Pedestrian Route and Sidewalk Analysis
- Roundabout Feasibility Analysis
- Traffic Calming Options Report
- Transit Assessment
- Transportation Demand Management Options Report
- Provincial Requirements and Permits under the Public Transportation Act and Highway Improvements Act
- Environmental Assessment and Other Appropriate Studies for development adjacent to Proposed Regional and Provincial Corridors

APPENDIX G:Borehole Logs

	s	tantec	В	OR	REH	IOI 812 9	LE 89 I	RE (E: 518	COR	BH/MW01-21 Sheet 1 of 1
	LIENT _ OCATIO	Strohvest Ontario Inc. Stroh Properties, Wellesley								PROJECT No161413217 DATUM
D	ATES: B	ORING May 6, 2021				WAT	ER I	LEVEL	<u>June</u>	2 15, 2021 TPC ELEVATION
<u> </u>	_		TC	EL			SAI	MPLES	3	UNDRAINED SHEAR STRENGTH (kPa)
DEРТН (m)	ELEVATION (m)	STRATA DESCRIPTION	STRATA PLOT	WATER LEVEL	DEPTH (ft)	М	3ER	RECOVERY (mm) TCR(%) / SCR(%)	.VALUE RQD(%)	- 50 100 150 200
□	🗇		STE	WA		TYPE	NUMBER	OVEF	-VAI	DYNAMIC CONE PENETRATION TEST, BLOWS/0.3m ▼ REMARKS & GRAIN SIZE STANDARD PENETRATION TEST, BLOWS/0.3m ● GRAIN SIZE
	356.7	Edge of Plowed Field					_	ZEC TCR(Ş K	10 20 30 40 50 60 70 80 90 100 GR SA SI CI
0 -	356.6	Dark brown to black, sandy silt	X		0	M				GR SA SI CI
	356.4	topsoil FILL	<u></u>		1 -	SS	1	$\frac{610}{610}$	7	 • • • • • • • • • • • • • • • • • • •
-		- moist Brown, silty sand FILL	1/. 1/		2 -					
1 -		Dark brown to black, sandy silt	7. 7 7. 7		3 -	V		100	4.0	
•		TOPSOIL	· <u>\'\'</u> .		4 -	SS	2	100 610	10	• 0
_	355.2	- moist	√. 7		5 -					1
	355.1	Compact, brown, silty SAND (SM) - wet	14	Ā	6 -	\parallel_{SS}	3	610	15	
2 -		- slightly dilatant			7 -			610	10	
		Hard to very stiff, brown, silty				\vdash				2 8 55 35
-	-	CLAY (CL) TILL - trace sand and gravel			8 -	SS	4	<u>610</u> 610	19	99 → >>>Δ
		- DTPL to APL			9 -	1		010		4
3 -		- grey below 3.1 m BGS			10-	\mathbf{M}				-
					11 -	SS	5	610 610	11	● O >>>Δ
					12 -	<u> </u>				
4 -					13 -					<u> </u>
					14-					
_	-				15-]
						\mathbb{I}_{aa}		460	10	
5 -		accurate amained cond and amovel				SS	6	<u>460</u> 610	19	Q ♥
-	-	- coarse grained sand and gravel seam/layer, saturated			17-					7
-		•			18-					1
					19-					
6 -					20-	 				-
					21 -	$\ _{SS}$	7	<u>510</u> 610	12	● ○ △ F
-	350.0				22	Λ		610		<u> </u>
7 -	1	Borehole terminated at 6.7 m BGS. 50 mm diameter PVC well installed			23 -					
' -		with 3.1 m screen across 3.1 - 6.1 m								
-		BGS. Sand from 6.1 m up to 2.7 m,			24 -	†				
		and bentonite from 2.7 m to 0.3 m BGS. Concrete and above ground			25-	†				
8 -		casing. MECP Well Tag # A313918			26-	 				
]				27-	$\ \cdot\ $				1

□ Field Vane Test, kPa
 ■ Remoulded Vane Test, kPa
 △ Pocket Penetrometer Test, kPa

C	s	tantec	В	OR	EH N: 48	[OI 813 3:	LE 50 I	RE (E: 518	COR	D					Bl	H/N	ЛW	/02	sh -21	eet 1 of 1
LC	OCATIO]	Strohvest Ontario Inc. Stroh Properties, Wellesley							т.					_	DAT	UM	Γ No –			1413217
D	ATES: E	ORING May 5, 2021				WAT														
DEPTH (m)	ELEVATION (m)	STRATA DESCRIPTION	STRATA PLOT	WATER LEVEL	DEPTH (ft)	TYPE	NUMBER	RECOVERY (mm) 70 TCR(%) / SCR(%)	N-VALUE OR RQD(%)	WA DYI	TER	50 CONTI	ENT & IE PEN	10 ATTER	00 	I LIMI	TS BLOW	W _P	200 W	W _L →I REMARKS & GRAIN SIZE DISTRIBUTION
0 -	361.1	Grassed			0					1	0	20	30 4	10 5	0 6	0 7	0 8	80 9	0 100	(%) GR SA SI CL
-	360.8	Dark brown, sandy silt topsoil FILL wet Brown, sandy silt FILL trace gravel			1 - 2 -	ss	1	610 610	5	•										
1 -	360.2 359.9	Brown, silty sand FILL - some gravel			3 - 4 -	ss	2	610 610	5	•						Δ				
2 -		- saturated Very stiff to hard, brown, clayey SILT (CL-ML) TILL	A V A		5 - 6 - 7 -	SS	3	610 610	13		•									
-		- some to trace gravel - APL to DTPL	A A A	⊻	8 - 9 -	SS	4	610 610	14		•								- - - - - - - - - - - - - - - - - - -	
3 -		weeks land 2.5 m DCC	A V A			SS	5	610 610	14		•						Δ.		-	
4 -		- grey below 3.5 m BGS	V A V		12 - 13 - 14 -															
5 -	356.6	Very stiff to stiff, grey, CLAY (CL) TILL - trace gravel			15- 16-	SS	6	610 610	16		•					Δ			-	
-		occasional cobbles and bouldersAPL	*/ S/		17- 18- 19-															
6 -		- wet gravelly pocket	N N		20 – 21 –	SS	7	610 610	11		•					Δ.			-	
7 -	354.4	Borehole terminated at 6.7 m BGS. 50 mm diameter PVC well installed with 3.1 m screen across 3.1 - 6.1 m	19		22 23 –														-	
		BGS. Sand from 6.1 m up to 2.7 m, and bentonite from 2.7 m to 0.3 m BGS. Concrete and above ground			24 - 25 - 26 -															
8 -		casing. MECP Well Tag # A313723			27 -						Fie	eld V	ane To	est. kl	Pa				-	

■ Remoulded Vane Test, kPa△ Pocket Penetrometer Test, kPa

C	S	tantec	В	OR	REH N: 48	OI 313 7	LE 63 I	RE (E: 518	COR 382	D					Bl	H/N	ΛV	V03	-2	Sheet 1 of 1	l
	LIENT _														PRO		Γ Νο		_1	61413217	<i>1</i> -
		N Stroh Properties, Wellesley ORING May 5, 2021							June						DAT		– Vat	ION			-
		<u></u>	 -	یا				MPLES					IED S								_
(m)	NOI		PLO	EVE	H (ft)						-	50		1	00	+	150	+	2	00	
DEРТН (m)	ELEVATION (m)	STRATA DESCRIPTION	STRATA PLOT	WATER LEVEL	DEPTH (Ä	3ER	RECOVERY (mm) TCR(%) / SCR(%)	-VALUE RQD(%)	WA ⁻	TER (CONT	ENT &	ATTE	RBERG	3 LIMI	TS	W _P ⊢	W	$W_{\rm L}$	
□			STE	WA		TYPE	NUMBER	OVEF (%)/	N-VAI OR RQ				IE PEN ENETR						m V	GRAIN SIZ	ZE
0 -	360.2	Grassed			0		_	REC	0			20							0 1	DISTRIBUT (%) GR SA SI	
-	359.9	Dark brown, sandy silt topsoil FILL some clay, trace gravel	\bigotimes			SS	1	610 610	7	•		0								-	
-		l- wet		}	2 -		1	610	,											-	
-	359.4	Brown, sandy silt FILL - some clay, trace gravel			3 -	\int														- - -	
1 -		- wet			4 -	SS	2	$\frac{610}{610}$	9	•	· : : : :		O			Δ				- - -	
-	358.7	Loose, mottled brown, sandy SILT (ML)		Ψ	5 -															-	
-		- trace to some clay		-	6 -	SS	3	610	16		•) :::: k						 		- - -	
2 -	257.0	- wet Compact, brown, silty SAND (SM)			7 -			610	10				1::::							-	
-	357.9	- wet	H1.	-	8 -															0 2 91 7	
-		- very stiff, brown, sandy silt, some clay layers, APL			9 -	SS	4	<u>510</u> 610	18												
3 -		Compact, brown to grey, SILT			10-															-	
-		(ML) - trace sand and clay			11-	SS	5	610 610	16		•							<u></u>		-	
-		- wet			12 -	Λ		610												-	
4 -		- slightly dilatant - grey below 3.4 m BGS			13 -															-	
-		- very stiff, grey, clayey silt layer, APL			14-															- - -	
-		ALL			15-															<u>-</u> -	
- -					16-	SS	6	<u>560</u> 610	24		C	•								- - -	
5 -		- slightly dilatant seam			17-	1		010												-	
-					18-																
-					19-																
6 -					20 -															-	
-	353.8	Very stiff, grey, clayey SILT		-	21 -	ss	7	<u>610</u> 610	21		0	•							>>.	<u> </u>	
-	353.5	(CL-ML) TILL			22	1														-	
7 -		- DTPL Borehole terminated at 6.7 m BGS.			23 -								:::::							<u>- </u>	
-		50 mm diameter PVC well installed			24-															 	
-		with 3.1 m screen across 3.1 - 6.1 m BGS. Sand from 6.1 m up to 2.7 m,			25 -															- - -	
8 -		and bentonite from 2.7 m to 0.3 m			26-																
-		BGS. Concrete and above ground casing. MECP Well Tag # A069634			27 -															- - -	

□ Field Vane Test, kPa
 ■ Remoulded Vane Test, kPa
 △ Pocket Penetrometer Test, kPa

C	s	tantec	В	OR	EH N: 48	[OI	LE 19 I	RE (E: 518	COR	D					B	H/N	ЛW	/04	-21	neet 1 of 1
LO		N Stroh Properties, Wellesley													PRO DAT		Γ No.	•	16	1413217
D.	ATES: E	ORING May 6, 2021				WAT	ER I	LEVEL	June											
DEPTH (m)	ELEVATION (m)	STRATA DESCRIPTION	STRATA PLOT	WATER LEVEL	DEРТН (ft)	TYPE	NUMBER	RECOVERY (mm) TOR(%) TOR(%)	N-VALUE OR RQD(%)	WA'	TER (50 CONTI	ENT &	ATTEI	00 RBER	G LIMI TEST,	TS BLOW	W _P	200 W	W _L REMARKS GRAIN SIZE DISTRIBUTION
0 -	355.6	Grassed			0			M _C		1	0 2	20 :	30 4	10 5	50 <i>6</i>	50 7	70 8	0 9	0 100	GR SA SI CL
-	355.0 354.8	Dark brown, sandy silt topsoil FILL - moist			1 - 2 -	ss	1	460 610	4	•										
1 -		Brown, clay till FILL - trace gravel - DTPL	No.		3 - 4 -	ss	2	<u>560</u> 610	15		● C)				Δ				
2 -	353.6	Hard, brown, CLAY (CL) TILL - trace sand and gravel - occasional silt seams - APL to DTPL	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	Ţ	5 - 6 - 7 -	ss	3	<u>560</u> 610	9	•	O								>>A	
3 -	353.0	Compact, brown, sandy SILT (ML) TILL - trace to some clay - some gravel			8 - 9 - 10-	ss	4	<u>460</u> 610	12		• 0								>> <u>A</u>	
- - -		- wet - 100 mm thick silty sand and gravel seam, saturated	\$ \\ \phi\\ \phi			ss	5	610 610	12		• ()						Δ		
4 -		Hard to very stiff, brown, CLAY (CL) TILL - trace gravel - DTPL to APL - some silt seams	X X		13 - 14 - 15 -															
5 -		- grey below 3.1 m BGS				SS	6	610 610	15			Φ:				Δ				
6 -			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		18- 19-															
-	348.9	- WTPL	X D X		20 - 21 -	SS	7	410 610	10			О			Δ					
7 -		Borehole terminated at 6.7 m BGS. 50 mm diameter PVC well installed with 3.1 m screen across 3.1 - 6.1 m BGS. Sand from 6.1 m up to 2.7 m,			23 - 24 -															
8 -		and bentonite from 2.7 m to 0.3 m BGS. Concrete and above ground casing.MECP Well Tag # A074962			25 - 26 - 27 -															
-					21					 	Fie	ld V	ane To	est k	Pa					

■ Remoulded Vane Test, kPa△ Pocket Penetrometer Test, kPa

C	S	tantec	B	OR	REH N: 48	IOI 813 3	E 23 I	RE (E: 518	C OR 547	D								Bl	H/]	M	W	05	-2]	he	et 1 of 1
	LIENT _	Strohvest Ontario Inc. Stroh Properties, Wellesley														_			JEC TUM		No.		1	61	413217
D.	ATES: B	ORING <u>May 6, 2021</u>				WAT	ER I	LEVEL	<u>June</u>	15,	20)2	1				Τ	РС	ELI	EVA	TI	ON			
(m)	NO		LOT	EVEL	(#)		SAI	MPLES		L	JN	DF	RAI 5	INE 0	ED S	SHE	100		TRE	NG 15		l (kF	Pa) 20	00	
ОЕРТН (m)	ELEVATION (m)	STRATA DESCRIPTION	STRATA PLOT	WATER LEVEL	ОЕРТН (Щ	3ER	RY (mr SCR(9	.VALUE RQD(%)	WA	TE	R	CON	I ITEI	NT &	ATT	ERE	BERG	G LIM	IITS		W _P	W		<i>W</i> L -1
			STE	WA		TYPE	NUMBER	RECOVERY (mm) TCR(%) / SCR(%)	N-VAI OR RG	STA	ANI	DAI	RD I	PEN	IETR	RATIO	T NC	EST	Γ, BLC	ows.	/0.3	m	n ▼		REMARKS & GRAIN SIZE DISTRIBUTION
0 -	362.0	Grassed	.*/.*		0	_		流인		1	10	2	20	30)	40	50	6	50	70	80) 9	0 10	00 6	(%) GR SA SI CL
-	361.7	Loose, dark brown, sandy silt TOPSOIL - moist				SS	1	<u>510</u> 610	8	•															
-	361.2	Loose, brown, sandy SILT (ML) TILL			3 -																				5 20 51 24
1 -		- some gravel - trace clay	<i>//</i>	Σ	4 -	SS	2	<u>510</u> 610	15				1										>>-/		
-		- moist Very stiff to hard, motlled brown,		1	5 - 6 -	SS	3	610 610	23														>>.4		
2 -	359.7	CLAY with Sand (CL) TILL - silty			7 -		3	610																11.1.1.	
-		- trace gravel - DTPL to APL - frequent silt seams			8 -	SS	4	610 610	44							•								L.L.L.	
3 -	358.9	- occasional silty sand layers			9 - 10-	/ \		010																	
-		Dense, light brown, silty SAND (SM) - moist	Ay.		11 -	ss	5	<u>560</u> 610	44							•							>>4		
-		- occasional clayey pockets Hard, grey-brown, CLAY (CL)	3		12 -																			Jack of all a	
4 -		TILL - DTPL	15/		14 -	 																		L. L. J. J. J.	
-	357.4	- silt seams - silty sand layers			15-	M		610																	
5 -		Very dense, grey, silty SAND (SM) - moist to wet			16 - 17 -	SS	6	610 610	73											•				J. J. J. J.	
-		slightly dilatantoccasional clayey pockets			18-	 																			
6 -					19 - 20 -	•																			
-					21 -	ss	7	610 610	53									•						and all all all	
	355.3	Borehole terminated at 6.7 m BGS.	<u> </u>	_	22	/ \																			
7 -		50 mm diameter PVC well installed with 3.1 m screen across 3.1 - 6.1 m			23 -																			I I I I I	
-		BGS. Sand from 6.1 m up to 2.7 m, and bentonite from 2.7 m to 0.3 m			25 -																				
8 -		BGS. Concrete and above ground casing. MECP Well Tag # A245818			26-																				
-					27 -	 					:													H	

□ Field Vane Test, kPa
 ■ Remoulded Vane Test, kPa
 △ Pocket Penetrometer Test, kPa

C	S	tantec	В	OR	REH N: 4	IOI 813 6	LE 24 F	RE (E: 518	C OR	D					В	H/I	MW	/06	sı 5-21	neet 1 of 1
	LIENT _	Strohvest Ontario Inc. Stroh Properties, Wellesley													PRO DA		T No.		16	51413217
D.	ATES: B	ORING <u>May 5, 2021</u>				WAT	ER I	EVEL	<u>June</u>	15, 2	202	21			TPC	ELE	EVAT	ION		
٦ آ	N		101	VEL	(#)		SAI	MPLES		U	ND	RAII 5			AR S 100	TRE	NGTI 150		Pa) 20	0
DЕРТН (m)	ELEVATION (m)	STRATA DESCRIPTION	STRATA PLOT	WATER LEVEL	ОЕРТН (TYPE	NUMBER	RECOVERY (mm) TCR(%) / SCR(%)	.VALUE RQD(%)						= ERBER ATION		IITS , BLOW	W _P	W →	W _L REMARKS
			S	3		<u> </u>	Ž	20V R(%)	N-V OR F) DWS/0.3		•	& GRAIN SIZE DISTRIBUTION
0 -	362.3	Grassed			0	ļ.,		판 2		10	0	20	30	40	50	60	70 8	0 9	0 10	GR SA SI CL
-	361.8	Dark brown, sandy silt topsoil FILL - moist Brown, sandy silt FILL				SS	1	<u>560</u> 610	8	•		0								_
-	361.5	- some clay - wet			3 -															
1 -	361.0	Compact, mottled brown, sandy SILT (ML)			4 -	SS	2	610 610	10		D								Δ:	
2 -	360.3	- some gravel - wet Very stiff, mottled brown, clayey	A P		6 -	SS	3	610 610	13		•								>> 4	
		SILT (CL-ML) TILL - occasional cobbles	No.		7 - 8 -			(10												
-		- DTPL - silty sand layer, wet	N N N N N N N N N N N N N N N N N N N		9 -	SS	4	610 610	15		•								>> ∆	
3 -		Hard to very stiff, brown, CLAY (CL) TILL	6		10 -	$\sqrt{}$		(10												
_		trace sand and gravelAPL	17		11 - 12 -	SS	5	610 610	12		● :C						Δ:			
4 -		- occasional sand seams -grey below 3.4 m BGS	A G		13 -	<u> </u>														_
-			X/		14-															
- - -		occasional silt seamoccasional cobbles	1		15- 16-	SS	6	610 610	15			φ							>> <u></u>	
5 -			1		17-	/\		010												
-			1		18-	<u> </u>														
6 -			\\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\		19 - 20 -															-
-		- stiff	7		21 -	SS	7	<u>510</u> 610	9	•)	0		<u></u>						
-	355.6	Borehole terminated at 6.7 m BGS.	//		22	/\														
7 -		50 mm diameter PVC well installed with 3.1 m screen across 3.1 - 6.1 m			23 -	†														
-		BGS. Sand from 6.1 m up to 2.7 m, and bentonite from 2.7 m to 0.3 m			24 - 25 -															
8 -		BGS. Concrete and above ground casing.MECP Well Tag # A313952			26 -															
0 -		8			27-															

□ Field Vane Test, kPa
 ■ Remoulded Vane Test, kPa
 △ Pocket Penetrometer Test, kPa

(S	tantec	В	OF	REF N: 4	IOI 813 1	LE 70 1	RE (E: 518	C OR	D				E	3H()7-2	21	Sh	eet 1 of 1
C	LIENT _	Strohvest Ontario Inc.												PR	OIE	CT No	,	16	1413217
		N Stroh Properties, Wellesley													ATUN		•		
		ORING May 5, 2021				WA	TER I	LEVEL						_ TP	C EL	EVAT	ION		
			I -				SA	MPLES		ι	JNDI	RAIN	ED SI	HEAR	STR	ENGT	H (kF	Pa)	
(m)	ELEVATION (m)		STRATA PLOT	LEVEL	Œ						_	50		100		150		200)
ОЕРТН (m)	E (m)	STRATA DESCRIPTION	ΙŽ	R	DEРТН (ft)		<u>م</u>	F. (3)	ш%					<u>'</u>			Wp	w	$W_{ m L}$
DEF			₹	WATER	H	TYPE	NUMBER	S	ALU				ENT & A				⊢ NS/0.3r	 m ▼	REMARKS
	Ш		S	≥		<u> </u>	Ž	RECOVERY (mm) TCR(%) / SCR(%)	N-VALUE OR RQD(%)				NETRA					•	& GRAIN SIZE DISTRIBUTION
0	356.1	Plowed Field						F N		1	.0 2	20 3	30 40	50	60	70	80 9	0 100	(%) GR SA SI CL
0 -	355.8	Dark brown, sandy silt topsoil FILL	\boxtimes		0	M		410											
-	333.6	7- wet			1 -	SS	1	$\frac{410}{610}$	3	•		0							
-		Brown, sandy silt FILL - trace gravel	\otimes	4	2 -	H													
1	355.2	- some topsoil inclusions			3 -	$\sqrt{}$		510											
1 -	354.9	- wet			4 -	SS	2	<u>510</u> 610	5	•			:O:						
-	354.6	Loose, brown, sandy SILT (ML)				1				1									
-		- trace clay and gravel - wet	7		5 -	M		(10											
2 -		- occasional silty sand seams			6 -	SS	3	610 610	15		•	0:						>> <u>4</u>	
-		Very stiff, mottled brown, clayey			7 -														
		SILT (CL-ML) TILL	1	1	8 -	$\sqrt{}$		610											
-		- APL Hard to stiff, brown, CLAY (CL)		1	9 -	SS	4	$\frac{610}{610}$	17		•	0:::						:>> ∆	
3 -		TILL			10-					<u> : : : : : </u>								<u> </u>	
-		- some gravel				M_{-}		610											
-		- DTPL to APL	10		11 -	SS	5	$\frac{610}{610}$	9	•		0	· · · · · · · ·						
-				1	12 -	1				1									
4 -					13-	$\left\{ \left \right. \right $::::	: : : :	1 : : : :						-	
-			1/2		14-														
-			18	1	15-														
-		- occcasional silt seams, wet	17					610	11										
5 -	350.9			1		SS	6	610 610	11			0:::					4× : : : : : : : : : : : : : : : : : : :		
-	330.7	Borehole terminated at 5.2 m BGS.	T ×		17														
_		Borehole open and dry. Backfilled			18-														
-		with bentonite and cuttings to surface.			19-														
6 -					20-													-	
-					21 -														
-																			
-					22 -]													
7 -					23 -														
-					24-														
					25-														
					26-														
8 -					27-]												-	
_ -																			
						_							ne Tes						
													ded Va						
											Po	cket l	Penetro	meter '	ı est, l	cra			

	s	tantec	B	OR	REF N: 4	IOI 813 4	LE 37 I	RE (E: 518	C OR	RD	BH08-21	Sheet 1 of 1
	LIENT _ DCATIO	Strohvest Ontario Inc. Stroh Properties, Wellesley									PROJECT No	161413217
		ORING May 5, 2021				WAT	ER I	LEVEL			TPC ELEVATION _	
			—	یر			SAI	MPLES	3	UNDRAINED SHE	AR STRENGTH (kPa)
DEPTH (m)	ELEVATION (m)	STRATA DESCRIPTION	STRATA PLOT	WATER LEVEL	DEPTH (ft)	TYPE	NUMBER	RECOVERY (mm) TCR(%) / SCR(%)	N-VALUE OR RQD(%)	WATER CONTENT & ATT	ERBERG LIMITS	200 W WL → I REMARKS GRAIN SIZE DISTRIBUTION
	361.5	Plowed Field					_	ECR.	2 g	STANDARD PENETRATION	50 60 70 80 90	DISTRIBUTION
0 -	361.2	Loose, dark brown, sandy silt TOPSOIL - trace clay	<u>.\''</u> .		1 - 2 -	SS	1	610 610	8	• 0	Δ	GR SA SI CL
1-		Very stiff, mottled brown, clayey SILT (CL-ML) TILL - some sand	VAV		3 -	ss	2	<u>460</u> 610	9	-	Д	-
2 -		- trace gravel - rootlets to 1.4 m BGS - APL	AVA		5 - 6 - 7 -	SS	3	610 610	12	● Ø	Δ	
3 -	359.1 358.4	Compact, brown, SILT (ML) TILL - trace to some clay - trace sand and gravel	\(\frac{1}{D}\) \(\frac{1}D\) \(\frac{1}		8 - 9 -	SS	4	610 610	23	- Φ •		
	_358.3	- moist - frequently laminated with silt seams Compact, grey, silty SAND (SM)			10 - 11 - 12 -	SS	5	610 610	29	o •		
4 -	356.9	- moist Hard, grey, clayey SILT (CL-ML) TILL - DTPL	AVA		13 - 14 -	-						-
5 -		- silty fine sand layers, moist Very stiff, grey, CLAY (CL) TILL - trace gravel - occasional silt seams	4		15- 16- 17	SS	6	610 610	12	• 0	Δ	
6 -		- APL Borehole terminated at 5.2 m BGS. Borehole open and dry. Backfilled			18 - 19 -							
-		with bentonite and cuttings to surface.			20 - 21 - 22 -							
7 -					23 - 24 -	- - -						
8 -					25 - 26 - 27 -							
_ _										□ Field Vane Test, □ Remoulded Vane △ Pocket Penetrom	e Test, kPa	<u>::::}- </u>

Monitoring Well: MW105-23

Project: Strohvest Subdivision, Hydrogeological Assessment

Client: Strohvest Ontario Inc. Location: Wellesley ON 161413217 Number: Field investigator: Scott Hutchinson

Contractor:

Aardvark Drilling Inc.

Method: CME 850, Hollow-stem Date started/completed: 16-Oct-2023 / 17-Oct-2023

4813327

Ground surface elevation: 361.97 m AMSL Top of casing elevation: 363.02 m AMSL Easting: 518546

Northing:

		SUBSURFACE PROFILE			SAMPLE	E DETA	ILS	IN	STALLATION DETAILS
Depth (ft) (m)	Graphic Log	Stratigraphic Description	Elevation (m AMSL) Depth (m BGS)	Sample Number	Sample Type	Recovery	N Value	Diagram	Description
-		Ground Surface	361.97						Above Ground C 1.05 m stick up
0 0		Should started TOPSOIL Sandy silt, very dark brown (10YR 2/2), dry SAND	0.00 361.51 0.46	1	ss	20" 83%	n/a	KK	
}		Fine, light yellowish brown (10YR 6/4), dry, compact SANDY SILT Trace gravel, subangular to subround, dark brown (10YR 3/3), moist, compact	361.21 / 0.76	2	SS	12" 50%	5-9-8-13 (17)		
5 —		SAND	360.29 1.68	3	SS	23"	3-8-12-14		
2 		Fine, some silt, light brown (10YR 6/4), moist, compact SANDY SILT Dark brown (10YR 3/3), moist, compact	359.99 / 1.98 359.38	4	SS	96%	(20) 1-8-13-18		
0 📑		SILT Trace gravel, subangular to subround, brown (10YR 4/3), dry, compact SANDY SILT	2.59 358.92 3.05			100%	(21) 8-12-15		
-4		Gray (10YR 6/1), dry, compact SILT (TILL) Trace gravel, subangular to subround, dark brown (10YR 3/3), dry, very dense	358.44	5	SS	100%	(27)		
5 —		silty sand	357.40	-		0011	0.00.04.00	N	
1		Gray (10YR 6/1), wet SANDY SILT (TILL) Dark gray (10YR 4/1), moist, very dense	\\357.27 4.70	6	SS	20" 83%	8-28-34-33 (62)		Water Level 2-May-2024
0 - 6								RR	5.03 m BGS
+				7	SS	19" 79%	9-25-34-27 (59)		
5 - 8		SILTY SAND	354.10 7.87	8	SS	24"	8-12-13-11		
+		\Dark gray (10YR 4/1), moist, compact CLAYEY SILT Dark gray (10YR 4/1), moist, firm	353.79 / 8.18			100%	(25)		
		SILTY CLAY (TILL) Dark grayish brown (10YR 4/2), moist, very stiff	352.82 9.14	9	SS	24"	4-8-11-15	ИR	
10						100%	(19)		■— Bentonite Grout 0 to 20.06 m BG
5 —				10	SS	24"	3-8-11-15		203 mm Borehole Diameter
-				10		100%	(19)	M	0 to 24.99 m BG
12				11	SS	21"	n/a		
-				- ''	00	88%	11/4		
5 —		CLAY (TILL)	348.25 13.72			24"	5-10-10-4		
Screen Ir Sand Pac Well Sea	ck Interva I Interval:	SS - split-spoon sample n/a - not available	el	12 AGS -	Above 0			KLKI	
	St	cantec Drawn By/Checked By: SH/ G	N						Sheet 1 of 2





Monitoring Well: MW105-23

Project: Strohvest Subdivision, Hydrogeological Assessment

Client: Strohvest Ontario Inc.
Location: Wellesley ON
Number: 161413217

Field investigator: Scott Hutchinson

Contractor: Aardvark Drilling Inc.


Method: CME 850, Hollow-stem

Date started/completed: 16-Oct-2023 / 17-Oct-2023 **Ground surface elevation:** 361.97 m AMSL

 Top of casing elevation:
 363.02 m AMSL

 Easting:
 518546

 Northing:
 4813327



Screen Interval: Sand Pack Interval: Well Seal Interval: 21.28 - 24.33 m BGS 20.67 - 24.33 m BGS 0.00 - 20.67 m BGS Notes: m AMSL - metres above mean sea level m BGS - metres below ground surface SS - spilt-spoon sample n/a - not available




Test Pit: TP01-24

Project: Strohvest Subdivision, Hydrogeological Assessment Method: Rubber Tire Backhoe Client: Strohvest Ontario Inc. Date started/completed: 01-May-2024 / 02-May-2024

Ground surface elevation: 356.70 m AMSL Wellesley ON Location:

161413217 Top of casing elevation: n/a Number: Field investigator: Drew Smith Easting: 518328 Northing: 4813349 Contractor: Strohvest Ontario Inc.






Test Pit: TP02-24

Project: Strohvest Subdivision, Hydrogeological Assessment Method: Rubber Tire Backhoe Client: 01-May-2024 / 02-May-2024 Strohvest Ontario Inc. Date started/completed:

Ground surface elevation: 361.10 m AMSL Wellesley ON Location:

161413217 Number: Top of casing elevation: n/a Easting: Field investigator: Drew Smith 518532 Contractor: 4813329 Strohvest Ontario Inc. Northing:



Notes: m AMSL - metres above mean sea level m BGS - metres below ground surface n/a - not available

Depths and elevations are approximate.




Test Pit: TP03-24

Project: Strohvest Subdivision, Hydrogeological Assessment Method: Rubber Tire Backhoe Client: 01-May-2024 / 02-May-2024 Strohvest Ontario Inc. Date started/completed:

Ground surface elevation: 360.00 m AMSL Wellesley ON Location:

161413217 Number: Top of casing elevation: n/a Easting: Field investigator: Drew Smith 518471 Strohvest Ontario Inc. Northing: 4813225 Contractor:





Notes: m AMSL - metres above mean sea level m BGS - metres below ground surface n/a - not available

Depths and elevations are approximate.



Test Pit: TP04-24

Project: Strohvest Subdivision, Hydrogeological Assessment Method: Rubber Tire Backhoe Client: Strohvest Ontario Inc. Date started/completed: 01-May-2024 / 02-May-2024

Wellesley ON Ground surface elevation: 355.60 m AMSL Location:

161413217 Top of casing elevation: n/a Number: 518280 Field investigator: Drew Smith Easting: Northing: 4813005 Contractor: Strohvest Ontario Inc.

		SUBSURFACE PROFILE		INS.	TALLATION DETAILS
Depth	Graphic Log	Stratigraphic Description	Elevation (m AMSL) Depth (m BGS)	ő	Description
(ft) (m)		Cravelly sand seam at 1.8 m BGS on eastern test pit wall; slow flowing water noted into test pit immediately after completion GRAVELLY SAND Trace fine sand. Layer observed on all test pit walls; slow flowing water into test pit noted immediately after completion Water level in test pit at 2.5 m BGS one day after completion SILTY CLAY Grey End of Test Pit	355.60 0.00 355.00 0.60 354.60 1.00 353.10 2.50 352.85 2.75 352.10 3.50	50000000000000000000000000000000000000	— Backfilled with Nat Cave/ Cuttings 0 to 3.5 m BGS
		Notes: Depths and elevation: m AMSL - metres above mean sea level m BGS - metres below ground surface n/a - not available	s are approxin	nate.	
	St	Drawn By/Checked By: DS/ GW			Sheet 1 of 1




Test Pit: TP05-24

Project: Strohvest Subdivision, Hydrogeological Assessment Method: Rubber Tire Backhoe 01-May-2024 / 02-May-2024 Client: Strohvest Ontario Inc. Date started/completed:

Wellesley ON Ground surface elevation: 362.00 m AMSL Location:

161413217 Number: Top of casing elevation: n/a Easting: Field investigator: Drew Smith 518532 Northing: 4813026 Contractor: Strohvest Ontario Inc.






Notes: m AMSL - metres above mean sea level m BGS - metres below ground surface n/a - not available







Sa	mple	Depth (m)	Description	W%	WL	Wp	Ip	%Gravel	%Sand	%Silt	%Clay
•	TP01-24	0.7	SILTY CLAY(CL-ML)	15				0	4	76	20
	TP01-24	1.1	LEAN CLAY(CL)	16	25	15	10	1	7	53	39
	TP04-24	0.6	SANDY LEAN CLAY(CL)	23	30	17	13	9	32	30	29
*	TP04-24	1.1	LEAN CLAY(CL)	20				1	5	38	56



Project: Strohvest Subdivision


Location:

Project No.: 161413217

GRADATION CURVE (ASTM D422)

Figure: 1 Remarks:

PLASTICITY CHART



	Specimen	Depth (m)	LL	PL	PI	Fines	W%	Classification
•	TP01-24	1.1	25	15	10	92	16	LEAN CLAY(CL)
	TP04-24	0.6	30	17	13	59	23	SANDY LEAN CLAY(CL)



Project: Strohvest Subdivision **ATTERBERG LIMITS** (ASTM D4318)

Location:

Figure: 2 Remarks:

Project No.: 161413217



PROJECT # 161413217

LAB#: 1343

DATE: May21,2024

PROJECT: Strohvest Subdivision

MOISTURE CONTENT

ВН	DEPTH (ff)	SAMPLE	Moisture Content %
TP01-24	2.2	1	14.7
TP01-24	3.5	2	16.3
TP04-24	2	1a	23.2
TP04-24	3.5	2	20.4

Well ID	Easting	Northing	Ground	Geologic I	Unit Depth	Geologic Ui	nit Elevation	Geologic Descri	ption	
			Surface	Тор	Bottom	Тор	Bottom			
			Elevation							
			(m AMSL)	(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Primary	Secondary	Tertiary
6501877	518834	4813363	362.95	0.00	7.62	362.95	355.33	DUG		
6501877	518834	4813363	362.95	7.62	38.40	355.33	324.55	CLAY		
6501877	518834	4813363	362.95	38.40	65.53	324.55	297.42	MEDIUM SAND		
6501877	518834	4813363	362.95	65.53	70.71	297.42	292.24	SHALE		
6501878	518954	4813503	356.64	0.00	8.23	356.64	348.41	CLAY	MEDIUM SAND	
6501878	518954	4813503	356.64	8.23	60.05	348.41	296.59	MEDIUM SAND		
6501878	518954	4813503	356.64	60.05	78.03	296.59	278.61	ROCK		
6501879	519054	4813363	359.13	0.00	0.91	359.13	358.22	CLAY		
6501879	519054	4813363	359.13	0.91	1.52	358.22	357.61	MEDIUM SAND		
6501879	519054	4813363	359.13	1.52	30.48	357.61	328.65	CLAY		
6501879	519054	4813363	359.13	30.48	49.07	328.65	310.06	MEDIUM SAND		
6501879	519054	4813363	359.13	49.07	60.35	310.06	298.78	MEDIUM SAND	GRAVEL	
6501879	519054	4813363	359.13	60.35	63.40	298.78	295.73	MEDIUM SAND		
6501879	519054	4813363	359.13	63.40	70.10	295.73	289.03	LIMESTONE		
6501880	518974	4813163	359.36	0.00	17.68	359.36	341.68	CLAY		
6501880	518974	4813163	359.36	17.68	27.74	341.68	331.63	HARDPAN		
6501880	518974	4813163	359.36	27.74	29.57	331.63	329.80	GRAVEL	HARDPAN	
6501880	518974	4813163	359.36	29.57	30.48	329.80	328.88	GRAVEL	COARSE SAND	
6501881	518764	4813753	357.57	0.00	7.01	357.57	350.56	DUG		
6501881	518764	4813753	357.57	7.01	18.29	350.56	339.28	CLAY		
6501881	518764	4813753	357.57	18.29	21.34	339.28	336.23	MEDIUM SAND	CLAY	
6501881	518764	4813753	357.57	21.34	42.67	336.23	314.89	HARDPAN		
6501881	518764	4813753	357.57	42.67	60.35	314.89	297.22	GRAVEL		
6501881	518764	4813753	357.57	60.35	68.88	297.22	288.68	LIMESTONE		
6501881	518764	4813753	357.57	68.88	69.49	288.68	288.07	LIMESTONE		
6501882	518974	4813083	357.34	0.00	9.14	357.34	348.20	CLAY		
6501882	518974	4813083	357.34	9.14	38.40	348.20	318.94	HARDPAN	BOULDERS	
6501882	518974	4813083	357.34	38.40	39.01	318.94	318.33	QUICKSAND		
6501882	518974	4813083	357.34	39.01	49.99	318.33	307.35	HARDPAN		
6501882	518974	4813083	357.34	49.99	54.25	307.35	303.09	LIMESTONE		
6501883	519044	4813343	359.17	0.00	0.61	359.17	358.56	FILL		
6501883	519044	4813343	359.17	0.61	3.96	358.56	355.21	CLAY		

Well ID	Easting	Northing	Ground	Geologic	Unit Depth	Geologic Ui	nit Elevation	Geologic Descri	ogic Description		
			Surface	Тор	Bottom	Тор	Bottom				
			Elevation								
			(m AMSL)	(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Primary	Secondary	Tertiary	
6501883	519044	4813343	359.17	3.96	26.52	355.21	332.65	CLAY			
6501883	519044	4813343	359.17	26.52	27.13	332.65	332.04	FINE SAND			
6501883	519044	4813343	359.17	27.13	32.92	332.04	326.25	CLAY	MEDIUM SAND		
6501883	519044	4813343	359.17	32.92	37.80	326.25	321.37	HARDPAN	GRAVEL		
6501883	519044	4813343	359.17	37.80	46.63	321.37	312.53	CLAY	MEDIUM SAND		
6501883	519044	4813343	359.17	46.63	48.46	312.53	310.70	HARDPAN	GRAVEL		
6501883	519044	4813343	359.17	48.46	54.25	310.70	304.91	SHALE			
6501883	519044	4813343	359.17	54.25	56.39	304.91	302.78	ROCK			
6501884	519014	4813623	349.84	0.00	0.91	349.84	348.93	FILL			
6501884	519014	4813623	349.84	0.91	36.58	348.93	313.27	CLAY			
6501884	519014	4813623	349.84	36.58	42.67	313.27	307.17	CLAY	STONES		
6501884	519014	4813623	349.84	42.67	43.59	307.17	306.26	MEDIUM SAND			
6501884	519014	4813623	349.84	43.59	43.89	306.26	305.95	GRAVEL			
6501886	518894	4813188	361.05	0.00	0.61	361.05	360.44	TOPSOIL			
6501886	518894	4813188	361.05	0.61	36.58	360.44	324.47	CLAY	MEDIUM SAND		
6501886	518894	4813188	361.05	36.58	44.20	324.47	316.85	FINE SAND			
6501886	518894	4813188	361.05	44.20	46.63	316.85	314.41	MEDIUM SAND			
6501887	518304	4813923	361.15	0.00	0.91	361.15	360.23	FILL			
6501887	518304	4813923	361.15	0.91	14.33	360.23	346.82	MEDIUM SAND	CLAY		
6501887	518304	4813923	361.15	14.33	30.78	346.82	330.36	HARDPAN			
6501887	518304	4813923	361.15	30.78	34.75	330.36	326.40	GRAVEL			
6501887	518304	4813923	361.15	34.75	49.99	326.40	311.16	HARDPAN			
6501887	518304	4813923	361.15	49.99	54.25	311.16	306.89	QUICKSAND			
6501887	518304	4813923	361.15	54.25	60.35	306.89	300.80	GRAVEL	MEDIUM SAND		
6501887	518304	4813923	361.15	60.35	61.57	300.80	299.58	SHALE			
6501887	518304	4813923	361.15	61.57	70.41	299.58	290.74	LIMESTONE			
6501896	518694	4813968	351.69	0.00	0.61	351.69	351.08	TOPSOIL			
6501896	518694	4813968	351.69	0.61	8.53	351.08	343.15	CLAY			
6501896	518694	4813968	351.69	8.53	27.43	343.15	324.26	HARDPAN			
6501896	518694	4813968	351.69	27.43	28.04	324.26	323.65	GRAVEL			
6501897	518844	4813963	354.63	0.00	6.10	354.63	348.53	CLAY			
6501897	518844	4813963	354.63	6.10	15.24	348.53	339.39	MEDIUM SAND	CLAY		

Well ID	Easting	Northing	Ground	Geologic	Unit Depth	Geologic Ui	nit Elevation	Geologic Descri	Geologic Description		
			Surface	Тор	Bottom	Тор	Bottom				
			Elevation								
			(m AMSL)	(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Primary	Secondary	Tertiary	
6501897	518844	4813963	354.63	15.24	27.43	339.39	327.20	HARDPAN			
6501897	518844	4813963	354.63	27.43	30.48	327.20	324.15	GRAVEL			
6501898	518234	4814013	363.50	0.00	0.61	363.50	362.89	TOPSOIL			
6501898	518234	4814013	363.50	0.61	15.54	362.89	347.96	CLAY			
6501898	518234	4814013	363.50	15.54	26.21	347.96	337.29	HARDPAN			
6501898	518234	4814013	363.50	26.21	28.35	337.29	335.16	MEDIUM SAND			
6501898	518234	4814013	363.50	28.35	51.82	335.16	311.69	CLAY			
6501898	518234	4814013	363.50	51.82	54.56	311.69	308.94	HARDPAN			
6501898	518234	4814013	363.50	54.56	57.30	308.94	306.20	MEDIUM SAND			
6502334	518714	4812803	351.23	0.00	2.13	351.23	349.10	GRAVEL			
6502334	518714	4812803	351.23	2.13	4.27	349.10	346.96	MEDIUM SAND			
6502334	518714	4812803	351.23	4.27	11.58	346.96	339.65	CLAY			
6502334	518714	4812803	351.23	11.58	32.00	339.65	319.23	CLAY	MEDIUM SAND		
6502334	518714	4812803	351.23	32.00	39.62	319.23	311.61	MEDIUM SAND			
6502334	518714	4812803	351.23	39.62	43.89	311.61	307.34	CLAY	MEDIUM SAND		
6502334	518714	4812803	351.23	43.89	52.43	307.34	298.80	SHALE			
6502334	518714	4812803	351.23	52.43	59.13	298.80	292.10	LIMESTONE			
6503598	519104	4813473	355.41	0.00	1.52	355.41	353.89	DUG			
6503598	519104	4813473	355.41	1.52	3.66	353.89	351.75	CLAY			
6503598	519104	4813473	355.41	3.66	19.81	351.75	335.60	CLAY			
6503598	519104	4813473	355.41	19.81	21.03	335.60	334.38	BOULDERS			
6503598	519104	4813473	355.41	21.03	33.22	334.38	322.19	CLAY	SILT		
6503598	519104	4813473	355.41	33.22	39.32	322.19	316.09	CLAY	SAND	STONES	
6503598	519104	4813473	355.41	39.32	41.15	316.09	314.26	CLAY			
6503598	519104	4813473	355.41	41.15	43.28	314.26	312.13	SAND			
6503993	518888	4813145	359.80	0.00	3.66	359.80	356.15	CLAY			
6503993	518888	4813145	359.80	3.66	17.37	356.15	342.43	CLAY			
6503993	518888	4813145	359.80	17.37	26.52	342.43	333.29	CLAY			
6503993	518888	4813145	359.80	26.52	40.23	333.29	319.57	CLAY			
6503993	518888	4813145	359.80	40.23	43.28	319.57	316.52	CLAY			
6503993	518888	4813145	359.80	43.28	45.11	316.52	314.69	GRAVEL	SAND		
6504338	518914	4813583	354.00	0.00	0.91	354.00	353.08	CLAY			

Well ID	Easting	Northing	Ground	Geologic	Unit Depth	Geologic Ui	nit Elevation	Geologic Desc	Geologic Description		
			Surface	Тор	Bottom	Тор	Bottom		•		
			Elevation								
			(m AMSL)	(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Primary	Secondary	Tertiary	
6504338	518914	4813583	354.00	0.91	3.66	353.08	350.34	CLAY			
6504338	518914	4813583	354.00	3.66	10.06	350.34	343.94	CLAY	FRAGMENTS		
6504338	518914	4813583	354.00	10.06	23.47	343.94	330.53	CLAY			
6504338	518914	4813583	354.00	23.47	29.26	330.53	324.73	SAND	SILT		
6504338	518914	4813583	354.00	29.26	33.53	324.73	320.47	CLAY			
6504338	518914	4813583	354.00	33.53	34.75	320.47	319.25	CLAY			
6504338	518914	4813583	354.00	34.75	55.78	319.25	298.22	CLAY	SAND		
6504338	518914	4813583	354.00	55.78	58.83	298.22	295.17	CLAY	STONES	SHALE	
6504338	518914	4813583	354.00	58.83	59.13	295.17	294.86	SAND	GRAVEL		
6504339	518894	4813183	360.92	0.00	3.66	360.92	357.26	CLAY			
6504339	518894	4813183	360.92	3.66	35.36	357.26	325.56	CLAY	STICKY		
6504339	518894	4813183	360.92	35.36	48.16	325.56	312.76	CLAY	SILT		
6504339	518894	4813183	360.92	48.16	53.64	312.76	307.27	CLAY			
6504339	518894	4813183	360.92	53.64	57.91	307.27	303.01	CLAY			
6504339	518894	4813183	360.92	57.91	58.83	303.01	302.09	CLAY			
6504339	518894	4813183	360.92	58.83	59.44	302.09	301.48	CLAY			
6504339	518894	4813183	360.92	59.44	59.74	301.48	301.18	LIMESTONE			
6504340	518894	4813163	360.39	0.00	3.35	360.39	357.04	CLAY			
6504340	518894	4813163	360.39	3.35	33.83	357.04	326.56	CLAY	STICKY		
6504340	518894	4813163	360.39	33.83	37.49	326.56	322.90	CLAY	SILTY		
6504340	518894	4813163	360.39	37.49	42.98	322.90	317.41	CLAY	SAND	SILTY	
6504340	518894	4813163	360.39	42.98	47.24	317.41	313.14	SAND	SILT		
6504340	518894	4813163	360.39	47.24	57.91	313.14	302.48	CLAY	SANDY		
6504340	518894	4813163	360.39	57.91	58.52	302.48	301.87	SAND			
6504340	518894	4813163	360.39	58.52	59.13	301.87	301.26	CLAY			
6504340	518894	4813163	360.39	59.13	59.74	301.26	300.65	SHALE			
6504340	518894	4813163	360.39	59.74	59.74	300.65	300.65	LIMESTONE			
6504341	518894	4813123	359.16	0.00	3.35	359.16	355.80	CLAY			
6504341	518894	4813123	359.16	3.35	32.61	355.80	326.54	CLAY			
6504341	518894	4813123	359.16	32.61	36.88	326.54	322.28	CLAY	SILT		
6504341	518894	4813123	359.16	36.88	43.89	322.28	315.27	CLAY			
6504341	518894	4813123	359.16	43.89	48.77	315.27	310.39	GRAVEL			

Well ID	Easting	Northing	Ground	Geologic	Unit Depth	Geologic Ui	nit Elevation	Geologic Description		
			Surface	Тор	Bottom	Тор	Bottom			
			Elevation							
			(m AMSL)	(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Primary	Secondary	Tertiary
6504341	518894	4813123	359.16	48.77	49.07	310.39	310.08	LIMESTONE	FRACTURED	
6504342	518894	4813083	357.62	0.00	3.35	357.62	354.27	CLAY		
6504342	518894	4813083	357.62	3.35	32.61	354.27	325.01	CLAY		
6504342	518894	4813083	357.62	32.61	36.88	325.01	320.74	CLAY	SILT	
6504342	518894	4813083	357.62	36.88	43.89	320.74	313.73	CLAY		
6504342	518894	4813083	357.62	43.89	48.46	313.73	309.16	GRAVEL		
6504711	519074	4813443	357.44	0.00	1.83	357.44	355.61	GRAVEL	FILL	LOOSE
6504711	519074	4813443	357.44	1.83	9.75	355.61	347.68	CLAY	STONES	HARD
6504711	519074	4813443	357.44	9.75	39.01	347.68	318.42	CLAY	HARD	
6504711	519074	4813443	357.44	39.01	44.50	318.42	312.93	SAND	CLAY	LOOSE
6504711	519074	4813443	357.44	44.50	45.72	312.93	311.72	FINE GRAVEL	LOOSE	
6504797	518874	4813603	355.67	0.00	0.30	355.67	355.36	TOPSOIL		
6504797	518874	4813603	355.67	0.30	2.74	355.36	352.92	CLAY		
6504797	518874	4813603	355.67	2.74	25.91	352.92	329.76	CLAY		
6504797	518874	4813603	355.67	25.91	26.21	329.76	329.45	GRAVEL		
6504797	518874	4813603	355.67	26.21	39.32	329.45	316.35	CLAY		
6504797	518874	4813603	355.67	39.32	44.50	316.35	311.17	SAND	CLAY	
6505158	519047	4813387	359.78	0.00	8.53	359.78	351.24	CLAY	GRAVEL	LOOSE
6505158	519047	4813387	359.78	8.53	30.48	351.24	329.30	CLAY	HARD	
6505158	519047	4813387	359.78	30.48	45.11	329.30	314.67	CLAY	SAND	LOOSE
6505158	519047	4813387	359.78	45.11	47.85	314.67	311.93	SAND	SILT	LOOSE
6505158	519047	4813387	359.78	47.85	62.48	311.93	297.30	CLAY	STONES	SAND
6505158	519047	4813387	359.78	62.48	64.31	297.30	295.47	SHALE	HARD	
6505158	519047	4813387	359.78	64.31	65.84	295.47	293.94	LIMESTONE	HARD	
6505684	518877	4813894	354.68	0.00	5.79	354.68	348.88	CLAY		SANDY
6505684	518877	4813894	354.68	5.79	10.36	348.88	344.31	CLAY	STONES	HARD
6505684	518877	4813894	354.68	10.36	13.11	344.31	341.57	SAND	GRAVEL	SOFT
6505684	518877	4813894	354.68	13.11	33.22	341.57	321.45	CLAY	SAND	SOFT
6505684	518877	4813894	354.68	33.22	41.15	321.45	313.53	SAND	CLAY	
6505684	518877	4813894	354.68	41.15	51.21	313.53	303.47	HARDPAN	STONES	HARD
6505684	518877	4813894	354.68	51.21	62.79	303.47	291.89	SAND	CLAY	
6505684	518877	4813894	354.68	62.79	64.31	291.89	290.36	SAND	GRAVEL	SOFT

Well ID	Easting	Northing	Ground	Geologic	Unit Depth	Geologic Ui	nit Elevation	Geologic Description		
			Surface	Тор	Bottom	Тор	Bottom		•	
			Elevation							
			(m AMSL)	(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Primary	Secondary	Tertiary
6505684	518877	4813894	354.68	64.31	67.67	290.36	287.01	GRAVEL	BOULDERS	SOFT
6505710	518519	4814053	363.44	0.00	2.44	363.44	361.00	CLAY		
6505710	518519	4814053	363.44	2.44	3.66	361.00	359.78	SAND		
6505710	518519	4814053	363.44	3.66	6.10	359.78	357.34	CLAY		
6505710	518519	4814053	363.44	6.10	6.40	357.34	357.04	CLAY	SAND	LAYERED
6505710	518519	4814053	363.44	6.40	10.97	357.04	352.47	CLAY		
6505710	518519	4814053	363.44	10.97	11.58	352.47	351.86	CLAY		HARD
6506203	518993	4812967	352.61	0.00	6.40	352.61	346.21	CLAY		SOFT
6506203	518993	4812967	352.61	6.40	35.36	346.21	317.25	STONES	BOULDERS	HARD
6506203	518993	4812967	352.61	35.36	43.59	317.25	309.02	STONES	BOULDERS	SAND
6506203	518993	4812967	352.61	43.59	44.50	309.02	308.11	GRAVEL		LOOSE
6506729	518240	4812662	346.31	0.00	0.61	346.31	345.70	TOPSOIL	SOFT	
6506729	518240	4812662	346.31	0.61	7.01	345.70	339.30	CLAY	HARD	STICKY
6506729	518240	4812662	346.31	7.01	26.21	339.30	320.10	CLAY	STONES	SOFT
6506729	518240	4812662	346.31	26.21	29.57	320.10	316.74	SILT	SAND	LOOSE
6506729	518240	4812662	346.31	29.57	29.57	316.74	316.74	CLAY	SOFT	
6506729	518240	4812662	346.31	29.57	33.22	316.74	313.09	CLAY	SOFT	
6506729	518240	4812662	346.31	33.22	36.27	313.09	310.04	SILT	CLAY	LOOSE
6506729	518240	4812662	346.31	36.27	41.15	310.04	305.16	SAND	SILT	LOOSE
6506729	518240	4812662	346.31	41.15	46.02	305.16	300.28	SAND	LOOSE	
6506729	518240	4812662	346.31	46.02	47.85	300.28	298.46	SAND	LOOSE	
6506729	518240	4812662	346.31	47.85	49.38	298.46	296.93	SAND	CLAY	STONES
6506767	517936	4812932	357.43	0.00	5.49	357.43	351.94	CLAY		
6506767	517936	4812932	357.43	5.49	12.19	351.94	345.23	CLAY	STONES	
6506767	517936	4812932	357.43	12.19	35.05	345.23	322.37	CLAY		SANDY
6506767	517936	4812932	357.43	35.05	37.19	322.37	320.24	FINE SAND		
6506767	517936	4812932	357.43	37.19	44.20	320.24	313.23	HARDPAN		
6506767	517936	4812932	357.43	44.20	48.16	313.23	309.27	LIMESTONE		
6507285	518829	4813110	358.19	0.00	0.61	358.19	357.58	FILL	CLAY	
6507285	518829	4813110	358.19	0.61	2.74	357.58	355.44	CLAY		
6507285	518829	4813110	358.19	2.74	17.98	355.44	340.20	CLAY		
6507285	518829	4813110	358.19	17.98	32.00	340.20	326.18	CLAY	FINE SAND	GRAVEL

Well ID	Easting	Northing	Ground	Geologic	Unit Depth	Geologic Ui	nit Elevation	Geologic Description		
			Surface	Тор	Bottom	Тор	Bottom		•	
			Elevation							
			(m AMSL)	(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Primary	Secondary	Tertiary
6507285	518829	4813110	358.19	32.00	40.54	326.18	317.65	CLAY	GRAVEL	STONES
6507285	518829	4813110	358.19	40.54	43.28	317.65	314.90	CLAY	STONES	
6507285	518829	4813110	358.19	43.28	49.38	314.90	308.81	GRAVEL	SILT	LAYERED
6507285	518829	4813110	358.19	49.38	50.90	308.81	307.28	LIMESTONE		
6507285	518829	4813110	358.19	50.90	51.51	307.28	306.67	LIMESTONE	SHALE	LAYERED
6507285	518829	4813110	358.19	51.51	52.43	306.67	305.76	LIMESTONE		
6507870	518479	4814084	363.94	0.00	0.61	363.94	363.33	CLAY		
6507870	518479	4814084	363.94	0.61	4.57	363.33	359.37	SAND		
6507870	518479	4814084	363.94	4.57	21.34	359.37	342.60	CLAY		SANDY
6507870	518479	4814084	363.94	21.34	32.00	342.60	331.93	CLAY		
6507870	518479	4814084	363.94	32.00	35.05	331.93	328.89	GRAVEL		DIRTY
6507870	518479	4814084	363.94	35.05	59.44	328.89	304.50	TILL	GRAVEL	SANDY
6507870	518479	4814084	363.94	59.44	60.35	304.50	303.59	CLAY	GRAVEL	
6507870	518479	4814084	363.94	60.35	62.18	303.59	301.76	SHALE		
6708237	518480	4814083	363.95	0.00	0.61	363.95	363.34	TOPSOIL	CLAY	
6708237	518480	4814083	363.95	0.61	4.57	363.34	359.37	SAND		
6708237	518480	4814083	363.95	4.57	21.34	359.37	342.61	SAND	CLAY	
6708237	518480	4814083	363.95	21.34	32.00	342.61	331.94	CLAY		
6708237	518480	4814083	363.95	32.00	35.05	331.94	328.89	GRAVEL		
6708237	518480	4814083	363.95	35.05	59.44	328.89	304.51	SAND	TILL	GRAVEL
6708237	518480	4814083	363.95	59.44	62.18	304.51	301.77	CLAY	GRAVEL	LAYERED
6508521	519025	4813269	359.01	0.00	5.49	359.01	353.52	CLAY	STONES	
6508521	519025	4813269	359.01	5.49	23.77	353.52	335.23	CLAY		
6508521	519025	4813269	359.01	23.77	26.21	335.23	332.79	GRAVEL		
6508521	519025	4813269	359.01	26.21	60.05	332.79	298.96	HARDPAN		
6508521	519025	4813269	359.01	60.05	61.87	298.96	297.13	SAND	STONES	
6508521	519025	4813269	359.01	61.87	64.01	297.13	295.00	GRAVEL	SAND	
6508521	519025	4813269	359.01	64.01	65.84	295.00	293.17	HARDPAN		
7046752	518804	4813120	358.46	0.00	3.66	358.46	354.80	GRAVEL	FILL	
7046752	518804	4813120	358.46	3.66	25.91	354.80	332.55	CLAY		
7046752	518804	4813120	358.46	25.91	45.42	332.55	313.04	CLAY	STONES	SILTY
7046752	518804	4813120	358.46	45.42	47.85	313.04	310.60	GRAVEL	SAND	


Well ID	Easting	Northing	Ground	Geologic	Unit Depth	Geologic Ur	nit Elevation	Geologic Descrip	Geologic Description		
	J		Surface	Тор	Bottom	Тор	Bottom				
			Elevation								
			(m AMSL)	(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Primary	Secondary	Tertiary	
7046752	518804	4813120	358.46	47.85	50.90	310.60	307.55	MEDIUM SAND			
7046752	518804	4813120	358.46	50.90	52.43	307.55	306.03	LIMESTONE			
7136166	518730	4812736	350.67	0.00	58.83	350.67	291.84				
7177219	518837	4813894	353.87	0.00	2.13	353.87	351.74	GRAVEL	SAND	FILL	
7177219	518837	4813894	353.87	2.13	6.10	351.74	347.77	CLAY	TILL		
7185327	518991	4812953	351.97	0.00	7.92	351.97	344.05	CLAY			
7185327	518991	4812953	351.97	7.92	9.75	344.05	342.22	CLAY	STONES		
7185327	518991	4812953	351.97	9.75	11.58	342.22	340.39	SILT	SAND		
7185327	518991	4812953	351.97	11.58	44.81	340.39	307.17	CLAY	STONES		
7185327	518991	4812953	351.97	44.81	47.85	307.17	304.12	LIMESTONE			
7185953	518941	4813100	358.30	0.00	0.30	358.30	358.00	TOPSOIL			
7185953	518941	4813100	358.30	0.30	1.20	358.00	357.10	SAND	FINE GRAVEL	BEARING	
7185953	518941	4813100	358.30	1.20	2.40	357.10	355.90	CLAY	SILT		
7185953	518941	4813100	358.30	2.40	4.00	355.90	354.30	CLAY		DENSE	
7185954	518951	4813092	357.94	0.00	0.30	357.94	357.64	TOPSOIL			
7185954	518951	4813092	357.94	0.30	2.40	357.64	355.54	CLAY	SILT		
7185954	518951	4813092	357.94	2.40	3.30	355.54	354.64	SILT	CLAY	BEARING	
7185954	518951	4813092	357.94	3.30	4.60	354.64	353.34	SILT	CLAY	DENSE	
7185955	518929	4813085	357.86	0.00	0.30	357.86	357.56	TOPSOIL			
7185955	518929	4813085	357.86	0.30	1.80	357.56	356.06	CLAY	SILT		
7185955	518929	4813085	357.86	1.80	3.30	356.06	354.56	SILT	CLAY	BEARING	
7185955	518929	4813085	357.86	3.30	4.60	354.56	353.26	SILT	CLAY	DENSE	
7288580	519034	4813143	354.30	0.00	1.52	354.30	352.78	CLAY	SILT	FILL	
7288580	519034	4813143	354.30	1.52	3.05	352.78	351.26	CLAY		HARD	
7288580	519034	4813143	354.30	3.05	6.10	351.26	348.21	CLAY		SOFT	
7288580	519034	4813143	354.30	6.10	6.71	348.21	347.60	SAND	GRAVEL	LOOSE	
7288580	519034	4813143	354.30	6.71	7.62	347.60	346.68	CLAY		SOFT	
7288581	519019	4813076	353.69	0.00	0.30	353.69	353.38	TOPSOIL		SOFT	
7288581	519019	4813076	353.69	0.30	6.10	353.38	347.59	CLAY		HARD	
7288581	519019	4813076	353.69	6.10	9.14	347.59	344.54	CLAY		SOFT	
7288581	519019	4813076	353.69	9.14	10.67	344.54	343.02	SILT	CLAY	HARD	
7288582	519017	4813207	358.29	0.00	0.61	358.29	357.68	TOPSOIL		SOFT	

Well ID	Easting	Northing	Ground	Geologic I	Jnit Depth	Geologic Ur	nit Elevation	Geologic Description		
			Surface	Тор	Bottom	Тор	Bottom		•	
			Elevation							
			(m AMSL)	(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Primary	Secondary	Tertiary
7288582	519017	4813207	358.29	0.61	1.52	357.68	356.76	CLAY	SILT	FILL
7288582	519017	4813207	358.29	1.52	2.44	356.76	355.85	CLAY	SILT	FILL
7288582	519017	4813207	358.29	2.44	4.57	355.85	353.71	CLAY	SILT	HARD
7288582	519017	4813207	358.29	4.57	9.14	353.71	349.14	CLAY		SOFT
7318145	518251	4813001		0.00	5.49			SAND	SILT	CLAY
7318145	518251	4813001		5.49	12.19			CLAY		HARD
7318145	518251	4813001		12.19	44.20			CLAY	STONES	SOFT
7318145	518251	4813001		44.20	51.21			CLAY		HARD
7318145	518251	4813001		51.21	55.78			LIMESTONE		
7318145	518251	4813001		55.78	57.91			LIMESTONE		
7318145	518251	4813001		57.91	67.67			LIMESTONE	SHALE	LAYERED
7327048	518804	4813120		0.00	3.66			GRAVEL	FILL	
7327048	518804	4813120		3.66	25.91			CLAY		
7327048	518804	4813120		25.91	45.42			CLAY	STONES	SILTY
7327048	518804	4813120		45.42	47.85			GRAVEL	STONES	SAND
7327048	518804	4813120		47.85	50.90			MEDIUM SAND		
7327048	518804	4813120		50.90	52.43			LIMESTONE		

Well ID	Distance	Easting	Northing	Depth to	Well	Ground	Well Base	Well	Use	Date
	from Site			Bedrock	Depth	Surface	Elevation			Constructed
	(m)			(m BGS)	(m BGS)	(m AMSL)	(m AMSL)	Туре	Use	
7185953	401	518941	4813100	,	4.00	358.30	354.30		Test Hole	05-Jun-12
7185955	388	518929	4813085		4.60	357.86	353.26		Test Hole	05-Jun-12
7257398	394	518934	4813097			358.26		Alteration		19-Jan-16
7177219	372	518837	4813894		6.10	353.87	347.77	Observation	Monitoring	08-Jul-11
7288580	495	519034	4813143		7.62	354.30	346.68	Observation	Monitoring	05-May-17
7288581	477	519019	4813076		10.67	353.69	343.02	Observation	Monitoring	05-May-17
7288582	474	519017	4813207		9.14	358.29	349.14	Observation	Monitoring	05-May-17
6504339	353	518894	4813183	59.44	59.74	360.92	301.18	Test Hole	Not Used	07-Aug-75
6504340	354	518894	4813163	59.13	59.74	360.39	300.65	Test Hole	Not Used	12-Aug-75
6504341	356	518894	4813123	48.77	49.07	359.16	310.08	Test Hole	Not Used	14-Aug-75
7185954	410	518951	4813092		4.60	357.94	353.34	Test Hole	Test Hole	05-Jun-12
6501877	267	518834	4813363	65.53	70.71	362.95	292.24	Water Supply	Domestic	10-Oct-49
6501878	341	518954	4813503	60.05	78.03	356.64	278.61	Water Supply	Domestic	14-Jun-54
6501879	466	519054	4813363	63.40	70.10	359.13	289.03	Water Supply	Domestic	01-Nov-54
6501880	434	518974	4813163		30.48	359.36	328.88	Water Supply	Domestic	09-Feb-55
6501881	237	518764	4813753	60.35	69.49	357.57	288.07	Water Supply	Domestic	18-Aug-55
6501882	432	518974	4813083	49.99	54.25	357.34	303.09	Water Supply	Domestic	18-Jan-57
6501883	463	519044	4813343	48.46	56.39	359.17	302.78	Water Supply	Domestic	29-May-59
6501884	416	519014	4813623		43.89	349.84	305.95	Water Supply	Domestic	30-Jan-67
6501886	352	518894	4813188		46.63	361.05	314.41	Water Supply	Domestic	24-Feb-67
6501887	169	518304	4813923	60.35	70.41	361.15	290.74	Water Supply	Domestic	21-May-57
6501896	290	518694	4813968		28.04	351.69	323.65	Water Supply	Domestic	12-Aug-57
6501897	407	518844	4813963		30.48	354.63	324.15	Water Supply	Industrial	18-May-52
6501898	283	518234	4814013		57.30	363.50	306.20	Water Supply	Domestic	06-Oct-67
6502334	269	518714	4812803	43.89	59.13	351.23	292.10	Water Supply	Livestock	05-May-54
6503598	493	519104	4813473		43.28	355.41	312.13	Water Supply	Domestic	08-May-72
6503993	349	518888	4813145		45.11	359.80	314.69	Water Supply	Domestic	20-Aug-73
6504338	309	518914	4813583	55.78	59.13	354.00	294.86	Water Supply	Livestock	12-Sep-75
6504342	353	518894	4813083		48.46	357.62	309.16	Water Supply	Municipal	05-Sep-74
6504711	466	519074	4813443		45.72	357.44	311.72	Water Supply	Domestic	23-Aug-77
6504797	276	518874	4813603		44.50	355.67	311.17	Water Supply	Domestic	01-Jun-78
6505158	452	519047	4813387	62.48	65.84	359.78	293.94	Water Supply	Domestic	10-Oct-80
6505684	409	518877	4813894		67.67	354.68	287.01	Water Supply	Public	31-May-85
6505710	291	518519	4814053		11.58	363.44	351.86	Water Supply	Domestic	31-Oct-85
6506203	449	518993	4812967		44.50	352.61	308.11	Water Supply	Domestic	03-Nov-87
6506729	327	518240	4812662		49.38	346.31	296.93	Water Supply	Domestic	02-Aug-89
6506767	337	517936	4812932	44.20	48.16	357.43	309.27	Water Supply	Domestic	12-Jan-89
6507285	290	518829	4813110	49.38	52.43	358.19	305.76	Water Supply	Municipal	10-Apr-92
6507870	318	518479	4814084	60.35	62.18	363.94	301.76	Water Supply	Domestic	30-Aug-84
6508521	479	519025	4813269		65.84	359.01	293.17	Water Supply	Domestic	27-Aug-99
6708237	317	518480	4814083		62.18	363.95	301.77	Water Supply	Domestic	30-Aug-84
7046752	266	518804	4813120		52.43	358.46	306.03	Water Supply	Domestic	29-Jun-07
7136166	333	518730	4812736		58.83	350.67	291.84	Water Supply	Domestic	04-Jun-09
7185327	449	518991	4812953		47.85	351.97	304.12	Water Supply	Commerical	20-Jun-12
7211359	294	518833	4813104			358.00		Water Supply	Municipal	16-Oct-13
7217068	294	518833	4813104			358.00		Water Supply	Municipal	16-Oct-13
7318145	19	518251	4813001		67.67			Water Supply		27-Aug-18
7327048	266	518804	4813120		52.43			Water Supply	Municipal	29-Jun-07

HYDROGEOLOGICAL ASSESSMENT, STROHVEST SUBDIVISION, TOWNSHIP OF WELLESLEY, ONTARIO

APPENDIX H:Hydraulic Conductivity Testing Solutions



MW01-21 - TEST 2

Data Set: \...\mw01-21 2 ah JK.aqt

Date: 07/05/21 Time: 09:41:05

PROJECT INFORMATION

Company: Stantec Consulting, Ltd

Project: 161413217 Location: Wellesley, ON Test Well: MW01-21 Test Date: 31-May-21

AQUIFER DATA

Saturated Thickness: 5.095 m Anisotropy Ratio (Kz/Kr): 0.2

WELL DATA (MW01-21)

Initial Displacement: 0.4739 m

Total Well Penetration Depth: 4.285 m

Static Water Column Height: 4.285 m

Casing Radius: 0.0254 m

Screen Length: 3.05 m

Well Radius: 0.105 m


SOLUTION

Aquifer Model: Unconfined

Solution Method: Bouwer-Rice

K = 7.3E-6 m/sec

y0 = 0.4422 m



MW02-21

Data Set: \...\mw02-21 1 ah JK.aqt

Date: 07/05/21 Time: 11:12:41

PROJECT INFORMATION

Company: Stantec Consulting, Ltd

Project: 161413217 Location: Wellesley, ON Test Well: MW02-21 Test Date: 31-May-21

AQUIFER DATA

Saturated Thickness: 5.11 m Anisotropy Ratio (Kz/Kr): 0.2

WELL DATA (MW02-21)

Static Water Column Height: 4.57 m Initial Displacement: 2.847 m


Total Well Penetration Depth: 4.57 m Screen Length: 3.05 m Casing Radius: 0.0254 m

Well Radius: 0.105 m

SOLUTION

Aquifer Model: Unconfined Solution Method: Bouwer-Rice

K = 5.8E-9 m/secy0 = 169. m



MW03-21 - TEST 1

Data Set: \...\mw03-21 1 ah JK.aqt

Date: <u>07/05/21</u> Time: <u>11:24:09</u>

PROJECT INFORMATION

Company: Stantec Consulting, Ltd

Project: 161413217 Location: Wellesley, ON Test Well: MW03-21 Test Date: 31-May-21

AQUIFER DATA

Saturated Thickness: 4.87 m Anisotropy Ratio (Kz/Kr): 0.2

WELL DATA (MW03-21)

Initial Displacement: 1.319 m

Total Well Penetration Depth: 4.87 m

Casing Radius: 0.0254 m


Static Water Column Height: 4.87 m

Screen Length: 3.05 m Well Radius: 0.105 m

SOLUTION

Aquifer Model: Unconfined Solution Method: Bouwer-Rice

K = 1.8E-7 m/sec y0 = 0.9849 m



MW03-21 - TEST 2

Data Set: \...\mw03-21 2 ah JK.aqt

Date: <u>07/05/21</u> Time: <u>11:25:43</u>

PROJECT INFORMATION

Company: Stantec Consulting, Ltd

Project: 161413217 Location: Wellesley, ON Test Well: MW03-21 Test Date: 31-May-21

AQUIFER DATA

Saturated Thickness: 4.87 m Anisotropy Ratio (Kz/Kr): 0.2

WELL DATA (MW03-21)

Initial Displacement: 0.3872 m

Total Well Penetration Depth: 4.87 m.

Total Well Penetration Depth: 4.87 m

Casing Radius: 0.0254 m


Static Water Column Height: 4.87 m

Screen Length: 3.05 m Well Radius: 0.105 m

SOLUTION

Aquifer Model: Unconfined Solution Method: Bouwer-Rice

K = 1.4E-7 m/sec y0 = 0.2644 m



MW04-21

 $\label{logger_data-logger_da$

Date: <u>07/05/21</u> Time: <u>11:32:19</u>

PROJECT INFORMATION

Company: Stantec Consulting, Ltd

Project: 161413217 Location: Wellesley, ON Test Well: MW04-21 Test Date: 31-May-21

AQUIFER DATA

Saturated Thickness: 4.11 m Anisotropy Ratio (Kz/Kr): 0.2

WELL DATA (MW04-21)


Initial Displacement: 3.067 m Static Water Column Height: 4.11 m

Total Well Penetration Depth: 4.11 m Screen Length: 3.05 m Casing Radius: 0.0254 m Well Radius: 0.105 m

SOLUTION

Aquifer Model: Unconfined Solution Method: Bouwer-Rice

K = 5.4E-9 m/sec y0 = 351.1 m



MW05-21 - TEST 2

Data Set: \...\mw05-21 2 ah JK.aqt

Date: <u>07/05/21</u> Time: <u>11:37:03</u>

PROJECT INFORMATION

Company: Stantec Consulting, Ltd

Project: 161413217 Location: Wellesley, ON Test Well: MW05-21 Test Date: 31-May-21

AQUIFER DATA

Saturated Thickness: 5.4 m Anisotropy Ratio (Kz/Kr): 0.2

WELL DATA (MW05-21)

Initial Displacement: 0.3264 m
Total Well Penetration Depth: 4.9 m

Casing Radius: 0.0254 m


Static Water Column Height: 4.9 m

Screen Length: 3.05 m Well Radius: 0.105 m

SOLUTION

Aquifer Model: Unconfined Solution Method: Bouwer-Rice

K = 9.1E-8 m/sec y0 = 0.2612 m



MW105-23 - RISING HEAD TEST

Data Set: \...\MW105-23_ST_JK.aqt

Date: 04/04/24 Time: 11:13:08

PROJECT INFORMATION

Company: Stantec

Client: Strohvest Ontario Inc.

Project: 161413217

Location: Stroh Lands, Wellesley, ON

Test Well: MW105-23 Test Date: April 2, 2024

AQUIFER DATA

Saturated Thickness: 19.21 m Anisotropy Ratio (Kz/Kr): 0.1

WELL DATA (MW105-23)

Initial Displacement: 0.462 m

. <u>0.402</u> III

Static Water Column Height: 19.21 m

Total Well Penetration Depth: 19.21 m

Screen Length: 3.05 m Well Radius: 0.105 m

Casing Radius: 0.0254 m

K = 2.8E-9 m/sec

SOLUTION

Aguifer Model: Unconfined

Solution Method: Bouwer-Rice

y0 = 0.3432 m

HYDROGEOLOGICAL ASSESSMENT, STROHVEST SUBDIVISION, TOWNSHIP OF WELLESLEY, ONTARIO

APPENDIX I:Laboratory Certificates of Analysis



Your Project #: 161413217.777 Site Location: WELLESLEY Your C.O.C. #: 158433

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2021/06/04

Report #: R6661365 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C1E5622 Received: 2021/05/28, 10:25

Sample Matrix: Water # Samples Received: 4

·		Date	Date		
Analyses	Quantity	Extracted	Analyzed	Laboratory Method	Analytical Method
Alkalinity	4	N/A	2021/06/01	CAM SOP-00448	SM 23 2320 B m
Carbonate, Bicarbonate and Hydroxide	4	N/A	2021/06/02	CAM SOP-00102	APHA 4500-CO2 D
Chloride by Automated Colourimetry	2	N/A	2021/06/02	CAM SOP-00463	SM 23 4500-Cl E m
Chloride by Automated Colourimetry	2	N/A	2021/06/03	CAM SOP-00463	SM 23 4500-Cl E m
Conductivity	4	N/A	2021/06/01	CAM SOP-00414	SM 23 2510 m
Dissolved Organic Carbon (DOC) (1)	3	N/A	2021/05/31	CAM SOP-00446	SM 23 5310 B m
Dissolved Organic Carbon (DOC) (1)	1	N/A	2021/06/01	CAM SOP-00446	SM 23 5310 B m
Hardness (calculated as CaCO3)	4	N/A	2021/06/03	CAM SOP 00102/00408/00447	SM 2340 B
Dissolved Metals by ICPMS	4	N/A	2021/06/02	CAM SOP-00447	EPA 6020B m
Ion Balance (% Difference)	4	N/A	2021/06/03		
Anion and Cation Sum	4	N/A	2021/06/03		
Total Ammonia-N	4	N/A	2021/06/03	CAM SOP-00441	USGS I-2522-90 m
Nitrate (NO3) and Nitrite (NO2) in Water (2)	4	N/A	2021/06/01	CAM SOP-00440	SM 23 4500-NO3I/NO2B
рН	4	2021/05/31	2021/06/01	CAM SOP-00413	SM 4500H+ B m
Orthophosphate	2	N/A	2021/06/02	CAM SOP-00461	EPA 365.1 m
Orthophosphate	2	N/A	2021/06/03	CAM SOP-00461	EPA 365.1 m
Sat. pH and Langelier Index (@ 20C)	4	N/A	2021/06/03		Auto Calc
Sat. pH and Langelier Index (@ 4C)	4	N/A	2021/06/03		Auto Calc
Sulphate by Automated Colourimetry	2	N/A	2021/06/02	CAM SOP-00464	EPA 375.4 m
Sulphate by Automated Colourimetry	2	N/A	2021/06/03	CAM SOP-00464	EPA 375.4 m
Total Dissolved Solids (TDS calc)	4	N/A	2021/06/03		Auto Calc
Total Suspended Solids	4	2021/06/01	2021/06/02	CAM SOP-00428	SM 23 2540D m
Turbidity	4	N/A	2021/05/31	CAM SOP-00417	SM 23 2130 B m

Remarks:

Bureau Veritas is accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Bureau Veritas are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Bureau Veritas' profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Bureau Veritas in



Your Project #: 161413217.777 Site Location: WELLESLEY Your C.O.C. #: 158433

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2021/06/04

Report #: R6661365 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C1E5622

Received: 2021/05/28, 10:25

writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

Bureau Veritas liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Bureau Veritas has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Bureau Veritas, unless otherwise agreed in writing. Bureau Veritas is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by Bureau Veritas, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

- * RPDs calculated using raw data. The rounding of final results may result in the apparent difference.
- (1) Dissolved Organic Carbon (DOC) present in the sample should be considered as non-purgeable DOC.
- (2) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

Encryption Key

Ronklin Gracian Project Manager 04 Jun 2021 15:18:43

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Ronklin Gracian, Project Manager

Email: Ronklin.Gracian@bureauveritas.com

Phone# (905)817-5752

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Client Project #: 161413217.777 Site Location: WELLESLEY

Sampler Initials: AH

RCAP - COMPREHENSIVE (WATER)

BV Labs ID		PRQ479	PRQ480		PRQ481			
Samuling Date		2021/05/27	2021/05/27		2021/05/27			
Sampling Date		14:30	16:15		15:00			
COC Number		158433	158433		158433			
	UNITS	BH01-21	BH03-21	QC Batch	BH05-21	RDL	QC Batch	
Calculated Parameters								
Anion Sum	me/L	8.85	8.86	7378596	7.54	N/A	7378596	
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	300	380	7378589	280	1.0	7378589	
Calculated TDS	mg/L	460	470	7378601	400	1.0	7378601	
Carb. Alkalinity (calc. as CaCO3)	mg/L	2.8	3.1	7378589	2.5	1.0	7378589	
Cation Sum	me/L	8.86	9.26	7378596	7.66	N/A	7378596	
Hardness (CaCO3)	mg/L	370	450	7378593	350	1.0	7378593	
Ion Balance (% Difference)	%	0.0500	2.22	7378595	0.840	N/A	7378595	
Langelier Index (@ 20C)	N/A	0.919	1.13	7378599	0.868		7378599	
Langelier Index (@ 4C)	N/A	0.671	0.878	7378600	0.619		7378600	
Saturation pH (@ 20C)	N/A	7.09	6.81	7378599	7.10		7378599	
Saturation pH (@ 4C)	N/A	7.34	7.06	7378600	7.35		7378600	
Inorganics								
Total Ammonia-N	mg/L	0.062	0.071	7382520	0.097	0.050	7382520	
Conductivity	umho/cm	820	780	7380237	680	1.0	7380953	
Dissolved Organic Carbon	mg/L	0.88	0.90	7380569	0.99	0.40	7379930	
Orthophosphate (P)	mg/L	<0.010	<0.010	7380186	<0.010	0.010	7380176	
рН	рН	8.01	7.94	7380241	7.96		7380962	
Dissolved Sulphate (SO4)	mg/L	33	52	7380196	70	1.0	7380185	
Alkalinity (Total as CaCO3)	mg/L	300	380	7380240	290	1.0	7380946	
Dissolved Chloride (Cl-)	mg/L	76	5.7	7380194	12	1.0	7380181	
Nitrite (N)	mg/L	<0.010	<0.010	7380282	<0.010	0.010	7380287	
Nitrate (N)	mg/L	<0.10	<0.10	7380282	0.12	0.10	7380287	
Nitrate + Nitrite (N)	mg/L	<0.10	<0.10	7380282	0.12	0.10	7380287	
Metals								
Dissolved Aluminum (AI)	mg/L	<0.0049	0.010	7379961	0.021	0.0049	7379961	
Dissolved Antimony (Sb)	mg/L	<0.00050	<0.00050	7379961	<0.00050	0.00050	7379961	
Dissolved Arsenic (As)	mg/L	0.0014	0.0012	7379961	0.0029	0.0010	7379961	
Dissolved Barium (Ba)	mg/L	0.13	0.14	7379961	0.13	0.0020	7379961	
Dissolved Beryllium (Be)	mg/L	<0.00040	<0.00040	7379961	<0.00040	0.00040	7379961	
Dissolved Boron (B)	mg/L	0.063	0.016	7379961	0.029	0.010	7379961	
RDL = Reportable Detection Limit								

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Client Project #: 161413217.777
Site Location: WELLESLEY

Sampler Initials: AH

RCAP - COMPREHENSIVE (WATER)

BV Labs ID		PRQ479	PRQ480		PRQ481		
Samulina Data		2021/05/27	2021/05/27		2021/05/27		
Sampling Date		14:30	16:15		15:00		
COC Number		158433	158433		158433		
	UNITS	BH01-21	BH03-21	QC Batch	BH05-21	RDL	QC Batch
Dissolved Cadmium (Cd)	mg/L	<0.000090	<0.000090	7379961	<0.000090	0.000090	7379961
Dissolved Calcium (Ca)	mg/L	78	120	7379961	78	0.20	7379961
Dissolved Chromium (Cr)	mg/L	<0.0050	<0.0050	7379961	<0.0050	0.0050	7379961
Dissolved Cobalt (Co)	mg/L	<0.00050	0.00074	7379961	<0.00050	0.00050	7379961
Dissolved Copper (Cu)	mg/L	<0.00090	<0.00090	7379961	<0.00090	0.00090	7379961
Dissolved Iron (Fe)	mg/L	<0.10	<0.10	7379961	<0.10	0.10	7379961
Dissolved Lead (Pb)	mg/L	<0.00050	<0.00050	7379961	<0.00050	0.00050	7379961
Dissolved Magnesium (Mg)	mg/L	42	37	7379961	38	0.050	7379961
Dissolved Manganese (Mn)	mg/L	0.052	0.065	7379961	0.046	0.0020	7379961
Dissolved Molybdenum (Mo)	mg/L	0.0042	0.0012	7379961	0.0034	0.00050	7379961
Dissolved Nickel (Ni)	mg/L	<0.0010	<0.0010	7379961	<0.0010	0.0010	7379961
Dissolved Phosphorus (P)	mg/L	<0.10	<0.10	7379961	<0.10	0.10	7379961
Dissolved Potassium (K)	mg/L	2.4	1.7	7379961	2.0	0.20	7379961
Dissolved Selenium (Se)	mg/L	<0.0020	<0.0020	7379961	<0.0020	0.0020	7379961
Dissolved Silicon (Si)	mg/L	7.3	8.0	7379961	8.7	0.050	7379961
Dissolved Silver (Ag)	mg/L	<0.000090	<0.000090	7379961	<0.000090	0.000090	7379961
Dissolved Sodium (Na)	mg/L	33	5.7	7379961	13	0.10	7379961
Dissolved Strontium (Sr)	mg/L	1.0	0.36	7379961	0.52	0.0010	7379961
Dissolved Thallium (TI)	mg/L	<0.000050	<0.000050	7379961	<0.000050	0.000050	7379961
Dissolved Titanium (Ti)	mg/L	<0.0050	<0.0050	7379961	<0.0050	0.0050	7379961
Dissolved Uranium (U)	mg/L	0.0017	0.0011	7379961	0.0027	0.00010	7379961
Dissolved Vanadium (V)	mg/L	<0.00050	0.00053	7379961	<0.00050	0.00050	7379961
Dissolved Zinc (Zn)	mg/L	<0.0050	<0.0050	7379961	<0.0050	0.0050	7379961

RDL = Reportable Detection Limit QC Batch = Quality Control Batch



Client Project #: 161413217.777 Site Location: WELLESLEY

Sampler Initials: AH

RCAP - COMPREHENSIVE (WATER)

BV Labs ID		PRQ481			PRQ482		
Compline Date		2021/05/27			2021/05/27		
Sampling Date		15:00			15:05		
COC Number		158433			158433		
	UNITS	BH05-21 Lab-Dup	RDL	QC Batch	QC-01	RDL	QC Batch
Calculated Parameters							
Anion Sum	me/L				7.42	N/A	7378596
Bicarb. Alkalinity (calc. as CaCO3)	mg/L				280	1.0	7378589
Calculated TDS	mg/L				400	1.0	7378601
Carb. Alkalinity (calc. as CaCO3)	mg/L				3.2	1.0	7378589
Cation Sum	me/L				7.65	N/A	7378596
Hardness (CaCO3)	mg/L				350	1.0	7378593
Ion Balance (% Difference)	%				1.56	N/A	7378595
Langelier Index (@ 20C)	N/A				0.972		7378599
Langelier Index (@ 4C)	N/A				0.724		7378600
Saturation pH (@ 20C)	N/A				7.10		7378599
Saturation pH (@ 4C)	N/A				7.35		7378600
Inorganics	•		•	'		•	•
Total Ammonia-N	mg/L				0.093	0.050	7382520
Conductivity	umho/cm				670	1.0	7380237
Dissolved Organic Carbon	mg/L				1.0	0.40	7380569
Orthophosphate (P)	mg/L	<0.010	0.010	7380176	<0.010	0.010	7380176
рН	рН				8.08		7380241
Dissolved Sulphate (SO4)	mg/L	70	1.0	7380185	68	1.0	7380185
Alkalinity (Total as CaCO3)	mg/L				280	1.0	7380240
Dissolved Chloride (Cl-)	mg/L	12	1.0	7380181	11	1.0	7380181
Nitrite (N)	mg/L	<0.010	0.010	7380287	0.015	0.010	7380282
Nitrate (N)	mg/L	0.12	0.10	7380287	<0.10	0.10	7380282
Nitrate + Nitrite (N)	mg/L	0.12	0.10	7380287	0.11	0.10	7380282
Metals							
Dissolved Aluminum (AI)	mg/L				0.0053	0.0049	7379961
Dissolved Antimony (Sb)	mg/L				<0.00050	0.00050	7379961
Dissolved Arsenic (As)	mg/L				0.0027	0.0010	7379961
Dissolved Barium (Ba)	mg/L				0.13	0.0020	7379961
Dissolved Beryllium (Be)	mg/L				<0.00040	0.00040	7379961
RDL = Reportable Detection Limit							

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Client Project #: 161413217.777 Site Location: WELLESLEY

Sampler Initials: AH

RCAP - COMPREHENSIVE (WATER)

BV Labs ID		PRQ481			PRQ482		
Sampling Data		2021/05/27			2021/05/27		
Sampling Date		15:00			15:05		
COC Number		158433			158433		
	UNITS	BH05-21 Lab-Dup	RDL	QC Batch	QC-01	RDL	QC Batch
Dissolved Boron (B)	mg/L				0.029	0.010	7379961
Dissolved Cadmium (Cd)	mg/L				<0.000090	0.000090	7379961
Dissolved Calcium (Ca)	mg/L				77	0.20	7379961
Dissolved Chromium (Cr)	mg/L				<0.0050	0.0050	7379961
Dissolved Cobalt (Co)	mg/L				<0.00050	0.00050	7379961
Dissolved Copper (Cu)	mg/L				<0.00090	0.00090	7379961
Dissolved Iron (Fe)	mg/L				<0.10	0.10	7379961
Dissolved Lead (Pb)	mg/L				<0.00050	0.00050	7379961
Dissolved Magnesium (Mg)	mg/L				38	0.050	7379961
Dissolved Manganese (Mn)	mg/L				0.043	0.0020	7379961
Dissolved Molybdenum (Mo)	mg/L				0.0036	0.00050	7379961
Dissolved Nickel (Ni)	mg/L				<0.0010	0.0010	7379961
Dissolved Phosphorus (P)	mg/L				<0.10	0.10	7379961
Dissolved Potassium (K)	mg/L				2.0	0.20	7379961
Dissolved Selenium (Se)	mg/L				<0.0020	0.0020	7379961
Dissolved Silicon (Si)	mg/L				8.5	0.050	7379961
Dissolved Silver (Ag)	mg/L				<0.000090	0.000090	7379961
Dissolved Sodium (Na)	mg/L				14	0.10	7379961
Dissolved Strontium (Sr)	mg/L				0.53	0.0010	7379961
Dissolved Thallium (TI)	mg/L				<0.000050	0.000050	7379961
Dissolved Titanium (Ti)	mg/L				<0.0050	0.0050	7379961
Dissolved Uranium (U)	mg/L				0.0028	0.00010	7379961
Dissolved Vanadium (V)	mg/L	_			<0.00050	0.00050	7379961
Dissolved Zinc (Zn)	mg/L	_			<0.0050	0.0050	7379961

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate



/ Labs Job #: C1E5622 Stantec Consulting Ltd

Client Project #: 161413217.777 Site Location: WELLESLEY

Sampler Initials: AH

RESULTS OF ANALYSES OF WATER

BV Labs ID		PRQ479		PRQ480	PRQ481	PRQ482			
Sampling Date		2021/05/27		2021/05/27	2021/05/27	2021/05/27			
Sampling Date		14:30		16:15	15:00	15:05			
COC Number		158433		158433	158433	158433			
	UNITS	BH01-21	RDL	BH03-21	BH05-21	QC-01	RDL	QC Batch	
Inorganics									
Total Suspended Solids	mg/L	1700	20	55000	85000	59000	100	7379053	
Total Suspended Solids Turbidity	mg/L NTU	1700 1800	20 0.5	55000 4700	85000 2100	59000 3500	100 0.5	7379053 7379924	
<u> </u>	NTU		_						



Client Project #: 161413217.777 Site Location: WELLESLEY

Sampler Initials: AH

TEST SUMMARY

BV Labs ID: PRQ479 Sample ID: BH01-21 Matrix: Water **Collected:** 2021/05/27

Shipped:

Received: 2021/05/28

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7380240	N/A	2021/06/01	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7378589	N/A	2021/06/02	Automated Statchk
Chloride by Automated Colourimetry	KONE	7380194	N/A	2021/06/02	Avneet Kour Sudan
Conductivity	AT	7380237	N/A	2021/06/01	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7380569	N/A	2021/05/31	Nimarta Singh
Hardness (calculated as CaCO3)		7378593	N/A	2021/06/03	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	7379961	N/A	2021/06/02	Azita Fazaeli
Ion Balance (% Difference)	CALC	7378595	N/A	2021/06/03	Automated Statchk
Anion and Cation Sum	CALC	7378596	N/A	2021/06/03	Automated Statchk
Total Ammonia-N	LACH/NH4	7382520	N/A	2021/06/03	Amanpreet Sappal
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	7380282	N/A	2021/06/01	Chandra Nandlal
рН	AT	7380241	2021/05/31	2021/06/01	Surinder Rai
Orthophosphate	KONE	7380186	N/A	2021/06/02	Avneet Kour Sudan
Sat. pH and Langelier Index (@ 20C)	CALC	7378599	N/A	2021/06/03	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	7378600	N/A	2021/06/03	Automated Statchk
Sulphate by Automated Colourimetry	KONE	7380196	N/A	2021/06/02	Avneet Kour Sudan
Total Dissolved Solids (TDS calc)	CALC	7378601	N/A	2021/06/03	Automated Statchk
Total Suspended Solids	BAL	7379053	2021/06/01	2021/06/02	Sandeep Kaur
Turbidity	AT	7379924	N/A	2021/05/31	Neil Dassanayake

BV Labs ID: PRQ480 Sample ID: BH03-21 Matrix: Water Collected: 2021/05/27 Shipped:

Received: 2021/05/28

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7380240	N/A	2021/06/01	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7378589	N/A	2021/06/02	Automated Statchk
Chloride by Automated Colourimetry	KONE	7380194	N/A	2021/06/02	Avneet Kour Sudan
Conductivity	AT	7380237	N/A	2021/06/01	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7380569	N/A	2021/05/31	Nimarta Singh
Hardness (calculated as CaCO3)		7378593	N/A	2021/06/03	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	7379961	N/A	2021/06/02	Azita Fazaeli
Ion Balance (% Difference)	CALC	7378595	N/A	2021/06/03	Automated Statchk
Anion and Cation Sum	CALC	7378596	N/A	2021/06/03	Automated Statchk
Total Ammonia-N	LACH/NH4	7382520	N/A	2021/06/03	Amanpreet Sappal
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	7380282	N/A	2021/06/01	Chandra Nandlal
рН	AT	7380241	2021/05/31	2021/06/01	Surinder Rai
Orthophosphate	KONE	7380186	N/A	2021/06/02	Avneet Kour Sudan
Sat. pH and Langelier Index (@ 20C)	CALC	7378599	N/A	2021/06/03	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	7378600	N/A	2021/06/03	Automated Statchk
Sulphate by Automated Colourimetry	KONE	7380196	N/A	2021/06/02	Avneet Kour Sudan
Total Dissolved Solids (TDS calc)	CALC	7378601	N/A	2021/06/03	Automated Statchk
Total Suspended Solids	BAL	7379053	2021/06/01	2021/06/02	Sandeep Kaur
Turbidity	AT	7379924	N/A	2021/05/31	Neil Dassanayake



Report Date: 2021/06/04

Stantec Consulting Ltd

Client Project #: 161413217.777 Site Location: WELLESLEY

Sampler Initials: AH

TEST SUMMARY

BV Labs ID: PRQ481 Sample ID: BH05-21 Matrix: Water

Collected:

2021/05/27

Shipped:

Received: 2021/05/28

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7380946	N/A	2021/06/01	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7378589	N/A	2021/06/02	Automated Statchk
Chloride by Automated Colourimetry	KONE	7380181	N/A	2021/06/03	Avneet Kour Sudan
Conductivity	AT	7380953	N/A	2021/06/01	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7379930	N/A	2021/06/01	Nimarta Singh
Hardness (calculated as CaCO3)		7378593	N/A	2021/06/03	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	7379961	N/A	2021/06/02	Azita Fazaeli
Ion Balance (% Difference)	CALC	7378595	N/A	2021/06/03	Automated Statchk
Anion and Cation Sum	CALC	7378596	N/A	2021/06/03	Automated Statchk
Total Ammonia-N	LACH/NH4	7382520	N/A	2021/06/03	Amanpreet Sappal
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	7380287	N/A	2021/06/01	Chandra Nandlal
pH	AT	7380962	2021/05/31	2021/06/01	Surinder Rai
Orthophosphate	KONE	7380176	N/A	2021/06/03	Avneet Kour Sudan
Sat. pH and Langelier Index (@ 20C)	CALC	7378599	N/A	2021/06/03	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	7378600	N/A	2021/06/03	Automated Statchk
Sulphate by Automated Colourimetry	KONE	7380185	N/A	2021/06/03	Avneet Kour Sudan
Total Dissolved Solids (TDS calc)	CALC	7378601	N/A	2021/06/03	Automated Statchk
Total Suspended Solids	BAL	7379053	2021/06/01	2021/06/02	Sandeep Kaur
Turbidity	AT	7379924	N/A	2021/05/31	Neil Dassanayake

BV Labs ID: PRQ481 Dup Sample ID: BH05-21 Matrix: Water

Collected:

2021/05/27

Shipped:

Received: 2021/05/28

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride by Automated Colourimetry	KONE	7380181	N/A	2021/06/03	Avneet Kour Sudan
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	7380287	N/A	2021/06/01	Chandra Nandlal
Orthophosphate	KONE	7380176	N/A	2021/06/03	Avneet Kour Sudan
Sulphate by Automated Colourimetry	KONE	7380185	N/A	2021/06/03	Avneet Kour Sudan

BV Labs ID: PRQ482 Sample ID: QC-01 Matrix:

Water

Collected: Shipped:

2021/05/27

Received:

2021/05/28

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7380240	N/A	2021/06/01	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7378589	N/A	2021/06/02	Automated Statchk
Chloride by Automated Colourimetry	KONE	7380181	N/A	2021/06/03	Avneet Kour Sudan
Conductivity	AT	7380237	N/A	2021/06/01	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7380569	N/A	2021/05/31	Nimarta Singh
Hardness (calculated as CaCO3)		7378593	N/A	2021/06/03	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	7379961	N/A	2021/06/02	Azita Fazaeli
Ion Balance (% Difference)	CALC	7378595	N/A	2021/06/03	Automated Statchk
Anion and Cation Sum	CALC	7378596	N/A	2021/06/03	Automated Statchk



Client Project #: 161413217.777
Site Location: WELLESLEY

Sampler Initials: AH

TEST SUMMARY

BV Labs ID: PRQ482 **Collected:** 2021/05/27

Sample ID: QC-01 Shipped:

Matrix: Water Received: 2021/05/28

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Total Ammonia-N	LACH/NH4	7382520	N/A	2021/06/03	Amanpreet Sappal
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	7380282	N/A	2021/06/01	Chandra Nandlal
рН	AT	7380241	2021/05/31	2021/06/01	Surinder Rai
Orthophosphate	KONE	7380176	N/A	2021/06/03	Avneet Kour Sudan
Sat. pH and Langelier Index (@ 20C)	CALC	7378599	N/A	2021/06/03	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	7378600	N/A	2021/06/03	Automated Statchk
Sulphate by Automated Colourimetry	KONE	7380185	N/A	2021/06/03	Avneet Kour Sudan
Total Dissolved Solids (TDS calc)	CALC	7378601	N/A	2021/06/03	Automated Statchk
Total Suspended Solids	BAL	7379053	2021/06/01	2021/06/02	Sandeep Kaur
Turbidity	AT	7379924	N/A	2021/05/31	Neil Dassanayake



Client Project #: 161413217.777
Site Location: WELLESLEY

Sampler Initials: AH

GENERAL COMMENTS

Each te	emperature is the	average of up to t	three cooler temperatures taken at receipt
	Package 1	0.7°C	
Result	s relate only to the	e items tested.	



QUALITY ASSURANCE REPORT

Stantec Consulting Ltd

Client Project #: 161413217.777

Site Location: WELLESLEY

Sampler Initials: AH

			Matrix	Spike	SPIKED	BLANK	Method I	Blank	RP	D	QC Sta	ndard
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
7379053	Total Suspended Solids	2021/06/02					<10	mg/L	13	25	99	85 - 115
7379924	Turbidity	2021/05/31			96	85 - 115	<0.1	NTU	5.5	20		
7379930	Dissolved Organic Carbon	2021/05/31	92	80 - 120	95	80 - 120	<0.40	mg/L	3.5	20		
7379961	Dissolved Aluminum (Al)	2021/06/02	104	80 - 120	104	80 - 120	<0.0049	mg/L	11	20		
7379961	Dissolved Antimony (Sb)	2021/06/02	107	80 - 120	102	80 - 120	<0.00050	mg/L				
7379961	Dissolved Arsenic (As)	2021/06/02	103	80 - 120	99	80 - 120	<0.0010	mg/L				
7379961	Dissolved Barium (Ba)	2021/06/02	103	80 - 120	101	80 - 120	<0.0020	mg/L				
7379961	Dissolved Beryllium (Be)	2021/06/02	103	80 - 120	99	80 - 120	<0.00040	mg/L				
7379961	Dissolved Boron (B)	2021/06/02	NC	80 - 120	98	80 - 120	<0.010	mg/L				
7379961	Dissolved Cadmium (Cd)	2021/06/02	102	80 - 120	100	80 - 120	<0.000090	mg/L				
7379961	Dissolved Calcium (Ca)	2021/06/02	NC	80 - 120	99	80 - 120	<0.20	mg/L				
7379961	Dissolved Chromium (Cr)	2021/06/02	104	80 - 120	100	80 - 120	<0.0050	mg/L				
7379961	Dissolved Cobalt (Co)	2021/06/02	101	80 - 120	99	80 - 120	<0.00050	mg/L				
7379961	Dissolved Copper (Cu)	2021/06/02	104	80 - 120	100	80 - 120	<0.00090	mg/L				
7379961	Dissolved Iron (Fe)	2021/06/02	98	80 - 120	96	80 - 120	<0.10	mg/L	NC	20		
7379961	Dissolved Lead (Pb)	2021/06/02	98	80 - 120	96	80 - 120	<0.00050	mg/L				
7379961	Dissolved Magnesium (Mg)	2021/06/02	NC	80 - 120	100	80 - 120	<0.050	mg/L				
7379961	Dissolved Manganese (Mn)	2021/06/02	101	80 - 120	99	80 - 120	<0.0020	mg/L				
7379961	Dissolved Molybdenum (Mo)	2021/06/02	108	80 - 120	102	80 - 120	<0.00050	mg/L				
7379961	Dissolved Nickel (Ni)	2021/06/02	100	80 - 120	100	80 - 120	<0.0010	mg/L				
7379961	Dissolved Phosphorus (P)	2021/06/02	111	80 - 120	110	80 - 120	<0.10	mg/L				
7379961	Dissolved Potassium (K)	2021/06/02	102	80 - 120	99	80 - 120	<0.20	mg/L				
7379961	Dissolved Selenium (Se)	2021/06/02	101	80 - 120	99	80 - 120	<0.0020	mg/L				
7379961	Dissolved Silicon (Si)	2021/06/02	102	80 - 120	99	80 - 120	<0.050	mg/L				
7379961	Dissolved Silver (Ag)	2021/06/02	91	80 - 120	100	80 - 120	<0.000090	mg/L				
7379961	Dissolved Sodium (Na)	2021/06/02	NC	80 - 120	101	80 - 120	<0.10	mg/L				
7379961	Dissolved Strontium (Sr)	2021/06/02	NC	80 - 120	99	80 - 120	<0.0010	mg/L				
7379961	Dissolved Thallium (TI)	2021/06/02	98	80 - 120	95	80 - 120	<0.000050	mg/L				
7379961	Dissolved Titanium (Ti)	2021/06/02	100	80 - 120	93	80 - 120	<0.0050	mg/L				
7379961	Dissolved Uranium (U)	2021/06/02	105	80 - 120	103	80 - 120	<0.00010	mg/L				
7379961	Dissolved Vanadium (V)	2021/06/02	105	80 - 120	101	80 - 120	<0.00050	mg/L	7.8	20		



QUALITY ASSURANCE REPORT(CONT'D)

Stantec Consulting Ltd

Client Project #: 161413217.777

Site Location: WELLESLEY

Sampler Initials: AH

			Matrix	Matrix Spike		SPIKED BLANK		Method Blank		RPD		QC Standard	
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits	
7379961	Dissolved Zinc (Zn)	2021/06/02	99	80 - 120	99	80 - 120	<0.0050	mg/L	4.6	20			
7380176	Orthophosphate (P)	2021/06/03	114	75 - 125	101	80 - 120	<0.010	mg/L	NC	25			
7380181	Dissolved Chloride (CI-)	2021/06/03	101	80 - 120	105	80 - 120	<1.0	mg/L	0.41	20			
7380185	Dissolved Sulphate (SO4)	2021/06/03	NC	75 - 125	104	80 - 120	<1.0	mg/L	0.023	20			
7380186	Orthophosphate (P)	2021/06/02	108	75 - 125	101	80 - 120	<0.010	mg/L	NC	25			
7380194	Dissolved Chloride (CI-)	2021/06/02	NC	80 - 120	100	80 - 120	<1.0	mg/L	1.7	20			
7380196	Dissolved Sulphate (SO4)	2021/06/02	NC	75 - 125	105	80 - 120	<1.0	mg/L	1.4	20			
7380237	Conductivity	2021/06/01			100	85 - 115	<1.0	umho/c m	0.39	25			
7380240	Alkalinity (Total as CaCO3)	2021/06/01			95	85 - 115	<1.0	mg/L	0.39	20			
7380241	рН	2021/06/01			102	98 - 103			0.45	N/A			
7380282	Nitrate (N)	2021/06/01	96	80 - 120	96	80 - 120	<0.10	mg/L	NC	20			
7380282	Nitrite (N)	2021/06/01	104	80 - 120	105	80 - 120	<0.010	mg/L	NC	20			
7380287	Nitrate (N)	2021/06/01	93	80 - 120	91	80 - 120	<0.10	mg/L	3.3	20			
7380287	Nitrite (N)	2021/06/01	107	80 - 120	105	80 - 120	<0.010	mg/L	NC	20			
7380569	Dissolved Organic Carbon	2021/05/31	93	80 - 120	96	80 - 120	<0.40	mg/L	0.41	20			
7380946	Alkalinity (Total as CaCO3)	2021/06/01			96	85 - 115	<1.0	mg/L	3.4	20			
7380953	Conductivity	2021/06/01			101	85 - 115	<1.0	umho/c m	0.33	25			
7380962	рН	2021/06/01			102	98 - 103			1.2	N/A			
7382520	Total Ammonia-N	2021/06/03	NC	75 - 125	98	80 - 120	<0.050	mg/L	0.11	20			

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).



Client Project #: 161413217.777
Site Location: WELLESLEY

Sampler Initials: AH

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by:

Brad Newman, B.Sc., C.Chem., Scientific Service Specialist

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



6740 Campobello Road, Mississauga, Ontario L5N 2L8 Phone: 905-817-5700 Fax: 905-817-5779 Toll Free: 800-563-6266 CAM FCD-01191/6

CHAIN OF CUSTODY RECORD 158433 Page / of /

Invoice Information	1	Report Inform	mation (if diffe	ers from invol	ce)		Project li	nformation (where a	pplicable)	Turnaround Time (TAT) Required
Company Name: 49197 Stantec Cons	Sutting Company	Name:	7/4		14.13	Quotation	n: _C	01624		Regular TAT (5-7 days) Most analyses
Contact Name: ACCOUNTS Paya 40	Contact N	lame: 6v	autw)	nite he	ad	P.O. II/ AFE	n:			PLEASE PROVIDE ADVANCE NOTICE FOR RUSH PROJECTS
Address: 100-300 tagey boulevard Waterlov on 1200A	Address:				N TELEVISION	Project #:	16	14/32/7.7	177	Rush TAT (Surcharges will be applied)
Waterbook N2LOA	4				The sylventer	Site Location	on: W	ellestry	THE PARTY OF	1 Day 2 Days 3-4 Days
Phone: \$195794410 Fax: \$1957	9 6933 Phone:	51958571	400	Fax: eclo	estante	C . Site #:		111	01 11 20	
Email: SAPINVOICES (Stadec	Com Email: C	jvant. White	eheadle	Stade	C-com					Date Required:
MOE REGULATED DRINKING WATER OR WATER INTENDED FOR HUMAN I			LABORATORIES'	DRINKING WATE	CHAIN OF CUSTO			Healey		Rush Confirmation #:
Regulation 153 Table 1 Res/Park Med/ Fine	Other Reg	ry Sewer Bylaw *	1			Analysis	Requested		1 1 1 1 1 1 1 1 1	LABORATORY USE ONLY
Table 2 Ind/Comm Coarse	CONTRACT CONTRACT	Sewer Bylaw .		2			V			CUSTODY SEAL COOLER TEMPERATURES
Table 3 Agri/ Other	PWQO Regio	DWS		# / C/	18 X		3			Present Intact
Table FOR RSC (PLEASE CIRCLE) Y / N	REG 558 (MIN. 3 DA	TAT REQUIRED)	8		NICS	N - 8	7	5		1/1/0
Include Criteria on Certificate of Analysis: Y / N	REG 406 Table		THE REAL PROPERTY.	NEI S	VORGA	ALS rais, HV	013		YZE	
SAMPLES MUST BE KEPT COOL (< 10 °C) FROM TIME	OF SAMPLING UNTIL DELIVERY	TO BUREAU VERITA	9	o loso	115.8.11	S MET	J. Com	at a	TANA	
	DATE SAMPLED	TIME SAMPLED	1	LTEREI HC F1	3 MET/	S ICPMS M S METALS VI, ICPMS I	90	old William	DO NOT	CODLING MEDIA PRESENT: (Y) N
SAMPLE IDENTIFICATION	(YYYY/MM/DD)	(HH MM)	MOF CO	FIELD F	PHCs F2 VDCs REG 15	REG 153 REG 153 PAL Cr V	RCAD TOTAL	3/3-	HOLD- I	COMMENTS
1 Bt01-21	27+2021/04	14:30 1	NG 5	y			XX	X		
2 BH03-21	2021/05/27	16:15 h	14 5	Y			XX	X		THE TENT
3 BHOS-21	2621/05/27	15:00 N	46 5	Y			$\times \times$	λ		IMMEDIATE TEST
4 QC-01	2021/0927	15:05 N	NG 5	Y			XX		R liet	Taria at
5						12 feet 1			(Vende	
6			1							
7										
8	JUL 18								RET'D	IN WATERLOO
9	To the second				m 2					4594
10	C AND DE								74.15	28-May-21 10:25
RELINQUISHED BY: (Signature/Print)	DATE: (YYYY/MM/DD)	TIME: (HH:MM)	/		Y: (Signature/Pi			(YYYY/MM/DD)	TIME: (HH:MM)	Ronklin Gracian
Shaley/AlisonHealey	200105128	10:25	Tout	8UZ	S (MOM	m1)5/2/	700	1/0/28	10.25	
11 wsonnearey	integley 2021/05/28 10:25 Tomber Jamen Davison 2021/0		21/05/28 13:08		C1E5622					
Unless otherwise agreed to in writing, work submitted on this		Lucian Varitar I al	100	1.5	9 / 3					LURE ENV-1327
Unless otherwise agreed to in writing, work submitted on this and-conditions	chain of Custody is subject to	duredu Veritas Labora	nores stunda	u reims una	conamons, sigi	mig of this chain	o _j custody	V 1/	H 39313	4 1/0/1
COC-1004 (06/19)				V				15	11	White: BV Labs - Yellow: Client



Your Project #: 161413217.777 Your C.O.C. #: 829092-01-01

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2021/06/23

Report #: R6689237 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C1G5523 Received: 2021/06/16, 08:31

Sample Matrix: Water # Samples Received: 1

·		Date	Date		
Analyses	Quantity	Extracted	Analyzed	Laboratory Method	Analytical Method
Alkalinity	1	N/A	2021/06/18	CAM SOP-00448	SM 23 2320 B m
Carbonate, Bicarbonate and Hydroxide	1	N/A	2021/06/21	CAM SOP-00102	APHA 4500-CO2 D
Chloride by Automated Colourimetry	1	N/A	2021/06/18	CAM SOP-00463	SM 23 4500-Cl E m
Conductivity	1	N/A	2021/06/18	CAM SOP-00414	SM 23 2510 m
Dissolved Organic Carbon (DOC) (1)	1	N/A	2021/06/19	CAM SOP-00446	SM 23 5310 B m
Hardness (calculated as CaCO3)	1	N/A	2021/06/18	CAM SOP 00102/00408/00447	SM 2340 B
Metals Analysis by ICPMS (as received) (2)	1	N/A	2021/06/18	CAM SOP-00447	EPA 6020B m
Ion Balance (% Difference)	1	N/A	2021/06/21		
Anion and Cation Sum	1	N/A	2021/06/21		
Total Coliforms/ E. coli, CFU/100mL	1	N/A	2021/06/16	CAM SOP-00551	MOE E3407
Total Ammonia-N	1	N/A	2021/06/21	CAM SOP-00441	USGS I-2522-90 m
Nitrate (NO3) and Nitrite (NO2) in Water (3)	1	N/A	2021/06/22	CAM SOP-00440	SM 23 4500-NO3I/NO2B
рН	1	2021/06/18	2021/06/18	CAM SOP-00413	SM 4500H+ B m
Orthophosphate	1	N/A	2021/06/18	CAM SOP-00461	EPA 365.1 m
Sat. pH and Langelier Index (@ 20C)	1	N/A	2021/06/21		Auto Calc
Sat. pH and Langelier Index (@ 4C)	1	N/A	2021/06/21		Auto Calc
Sulphate by Automated Colourimetry	1	N/A	2021/06/18	CAM SOP-00464	EPA 375.4 m
Total Dissolved Solids (TDS calc)	1	N/A	2021/06/21		Auto Calc
Total Suspended Solids	1	2021/06/19	2021/06/21	CAM SOP-00428	SM 23 2540D m
Turbidity	1	N/A	2021/06/17	CAM SOP-00417	SM 23 2130 B m

Remarks:

Bureau Veritas is accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Bureau Veritas are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Bureau Veritas' profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Bureau Veritas in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.



Your Project #: 161413217.777 Your C.O.C. #: 829092-01-01

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2021/06/23

Report #: R6689237 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C1G5523 Received: 2021/06/16, 08:31

Bureau Veritas liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Bureau Veritas has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Bureau Veritas, unless otherwise agreed in writing. Bureau Veritas is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by Bureau Veritas, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

- * RPDs calculated using raw data. The rounding of final results may result in the apparent difference.
- (1) Dissolved Organic Carbon (DOC) present in the sample should be considered as non-purgeable DOC.
- (2) Metals analysis was performed on the sample 'as received'.
- (3) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

Encryption Key



Bureau Veritas

23 Jun 2021 16:34:21

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Ronklin Gracian, Project Manager

Email: Ronklin. Gracian @bureauveritas.com

Phone# (905)817-5752

This report has been generated and distributed using a secure automated process.

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Client Project #: 161413217.777

Sampler Initials: AH

RCAP - COMPREHENSIVE (DRINKING WATER)

BV Labs ID		PVV199		
Sampling Date		2021/06/15 15:27		
COC Number		829092-01-01		
	UNITS	RW01	RDL	QC Batch
Calculated Parameters				
Anion Sum	me/L	9.36	N/A	7412409
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	230	1.0	7411294
Calculated TDS	mg/L	530	1.0	7412416
Carb. Alkalinity (calc. as CaCO3)	mg/L	2.1	1.0	7411294
Cation Sum	me/L	8.68	N/A	7412409
Hardness (CaCO3)	mg/L	420	1.0	7411169
Ion Balance (% Difference)	%	3.76	N/A	7411296
Langelier Index (@ 20C)	N/A	0.919		7412412
Langelier Index (@ 4C)	N/A	0.671		7412414
Saturation pH (@ 20C)	N/A	7.07		7412412
Saturation pH (@ 4C)	N/A	7.32		7412414
Inorganics	'		•	
Total Ammonia-N	mg/L	0.33	0.050	7416599
Conductivity	umho/cm	840	1.0	7416565
Dissolved Organic Carbon	mg/L	0.60	0.40	7417389
Orthophosphate (P)	mg/L	<0.010	0.010	7414881
рН	рН	7.99		7416562
Dissolved Sulphate (SO4)	mg/L	220	1.0	7414879
Alkalinity (Total as CaCO3)	mg/L	230	1.0	7416560
Dissolved Chloride (Cl-)	mg/L	2.7	1.0	7414878
Nitrite (N)	mg/L	<0.010	0.010	7417724
Nitrate (N)	mg/L	<0.10	0.10	7417724
Metals				
Aluminum (Al)	mg/L	<0.0049	0.0049	7415349
Antimony (Sb)	mg/L	<0.00050	0.00050	7415349
Arsenic (As)	mg/L	<0.0010	0.0010	7415349
Barium (Ba)	mg/L	0.064	0.0020	7415349
Beryllium (Be)	mg/L	<0.00040	0.00040	7415349
Boron (B)	mg/L	0.024	0.010	7415349
Cadmium (Cd)	mg/L	<0.000090	0.000090	7415349
Calcium (Ca)	mg/L	110	1.0	7415349
RDL = Reportable Detection Limit QC Batch = Quality Control Batch N/A = Not Applicable				



Client Project #: 161413217.777

Sampler Initials: AH

RCAP - COMPREHENSIVE (DRINKING WATER)

BV Labs ID		PVV199		
Sampling Date		2021/06/15 15:27		
COC Number		829092-01-01		
	UNITS	RW01	RDL	QC Batch
Chromium (Cr)	mg/L	<0.0050	0.0050	7415349
Cobalt (Co)	mg/L	<0.00050	0.00050	7415349
Copper (Cu)	mg/L	0.0029	0.00090	7415349
Iron (Fe)	mg/L	0.43	0.10	7415349
Lead (Pb)	mg/L	<0.00050	0.00050	7415349
Lithium (Li)	mg/L	0.0053	0.0050	7415349
Magnesium (Mg)	mg/L	35	0.050	7415349
Manganese (Mn)	mg/L	0.013	0.0020	7415349
Molybdenum (Mo)	mg/L	0.0013	0.00050	7415349
Nickel (Ni)	mg/L	<0.0010	0.0010	7415349
Phosphorus (P)	mg/L	<0.10	0.10	7415349
Potassium (K)	mg/L	1.1	0.20	7415349
Selenium (Se)	mg/L	<0.0020	0.0020	7415349
Silicon (Si)	mg/L	6.8	0.050	7415349
Silver (Ag)	mg/L	<0.000090	0.000090	7415349
Sodium (Na)	mg/L	6.9	0.10	7415349
Strontium (Sr)	mg/L	35	0.0010	7415349
Thallium (TI)	mg/L	<0.000050	0.000050	7415349
Titanium (Ti)	mg/L	<0.0050	0.0050	7415349
Uranium (U)	mg/L	0.00090	0.00010	7415349
Vanadium (V)	mg/L	<0.00050	0.00050	7415349
Zinc (Zn)	mg/L	0.021	0.0050	7415349
RDL = Reportable Detection Limit				
OC Batala Constitut Cantural Batala				

QC Batch = Quality Control Batch



Client Project #: 161413217.777

Sampler Initials: AH

RESULTS OF ANALYSES OF WATER

	PVV199										
	2021/06/15										
	15:27										
	829092-01-01										
UNITS	RW01	RDL	QC Batch								
mg/L	<10	10	7416785								
NTU	1.5	0.1	7413299								
imit											
RDL = Reportable Detection Limit QC Batch = Quality Control Batch											
	mg/L NTU imit	2021/06/15 15:27 829092-01-01 UNITS RW01 mg/L <10 NTU 1.5 imit	2021/06/15 15:27 829092-01-01 UNITS RW01 RDL RDL								



Client Project #: 161413217.777

Sampler Initials: AH

MICROBIOLOGY (WATER)

BV Labs ID		PVV199							
Sampling Date		2021/06/15 15:27							
COC Number		829092-01-01							
	UNITS	RW01	QC Batch						
Microbiological									
Background	CFU/100mL	0	7412803						
Total Coliforms	CFU/100mL	0	7412803						
Escherichia coli	CFU/100mL	0	7412803						
QC Batch = Quality Control Batch									



Client Project #: 161413217.777

Sampler Initials: AH

TEST SUMMARY

BV Labs ID: PVV199

Collected: 2021/06/15

Sample ID: RW01 Matrix: Water

Shipped:

Received: 2021/06/16

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7416560	N/A	2021/06/18	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7411294	N/A	2021/06/21	Automated Statchk
Chloride by Automated Colourimetry	KONE	7414878	N/A	2021/06/18	Alina Dobreanu
Conductivity	AT	7416565	N/A	2021/06/18	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7417389	N/A	2021/06/19	Nimarta Singh
Hardness (calculated as CaCO3)		7411169	N/A	2021/06/18	Automated Statchk
Metals Analysis by ICPMS (as received)	ICP/MS	7415349	N/A	2021/06/18	Arefa Dabhad
Ion Balance (% Difference)	CALC	7411296	N/A	2021/06/21	Automated Statchk
Anion and Cation Sum	CALC	7412409	N/A	2021/06/21	Automated Statchk
Total Coliforms/ E. coli, CFU/100mL	PL	7412803	N/A	2021/06/16	Ranju Chaudhari
Total Ammonia-N	LACH/NH4	7416599	N/A	2021/06/21	Amanpreet Sappal
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	7417724	N/A	2021/06/22	Chandra Nandlal
pH	AT	7416562	2021/06/18	2021/06/18	Surinder Rai
Orthophosphate	KONE	7414881	N/A	2021/06/18	Avneet Kour Sudan
Sat. pH and Langelier Index (@ 20C)	CALC	7412412	N/A	2021/06/21	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	7412414	N/A	2021/06/21	Automated Statchk
Sulphate by Automated Colourimetry	KONE	7414879	N/A	2021/06/18	Avneet Kour Sudan
Total Dissolved Solids (TDS calc)	CALC	7412416	N/A	2021/06/21	Automated Statchk
Total Suspended Solids	BAL	7416785	2021/06/19	2021/06/21	Sandeep Kaur
Turbidity	AT	7413299	N/A	2021/06/17	Khushbu Vijay kumar Patel



Client Project #: 161413217.777

Sampler Initials: AH

GENERAL COMMENTS

Each te	emperature is the	average of up to	three cooler temperatures taken at receipt
	Package 1	0.3°C	
Result	s relate only to the	e items tested.	



QUALITY ASSURANCE REPORT

Stantec Consulting Ltd

Client Project #: 161413217.777

Sampler Initials: AH

			Matrix	Spike	SPIKED	BLANK	Method E	Blank	RP	D	QC Sta	ındard
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
7413299	Turbidity	2021/06/17			94	85 - 115	<0.1	NTU				
7414878	Dissolved Chloride (Cl-)	2021/06/18	NC	80 - 120	104	80 - 120	<1.0	mg/L	7.5	20		
7414879	Dissolved Sulphate (SO4)	2021/06/18	83	75 - 125	103	80 - 120	<1.0	mg/L	1.0	20		
7414881	Orthophosphate (P)	2021/06/18	108	75 - 125	101	80 - 120	<0.010	mg/L	NC	25		
7415349	Aluminum (Al)	2021/06/18	104	80 - 120	103	80 - 120	<0.0049	mg/L	NC	20		
7415349	Antimony (Sb)	2021/06/18	108	80 - 120	100	80 - 120	<0.00050	mg/L	NC	20		
7415349	Arsenic (As)	2021/06/18	104	80 - 120	101	80 - 120	<0.0010	mg/L	NC	20		
7415349	Barium (Ba)	2021/06/18	99	80 - 120	99	80 - 120	<0.0020	mg/L	0.17	20		
7415349	Beryllium (Be)	2021/06/18	111	80 - 120	103	80 - 120	<0.00040	mg/L	NC	20		
7415349	Boron (B)	2021/06/18	105	80 - 120	96	80 - 120	<0.010	mg/L	0.67	20		
7415349	Cadmium (Cd)	2021/06/18	104	80 - 120	99	80 - 120	<0.000090	mg/L	NC	20		
7415349	Calcium (Ca)	2021/06/18	NC	80 - 120	101	80 - 120	<0.20	mg/L	4.0	20		
7415349	Chromium (Cr)	2021/06/18	100	80 - 120	97	80 - 120	<0.0050	mg/L	NC	20		
7415349	Cobalt (Co)	2021/06/18	100	80 - 120	97	80 - 120	<0.00050	mg/L	2.2	20		
7415349	Copper (Cu)	2021/06/18	100	80 - 120	96	80 - 120	<0.00090	mg/L	NC	20		
7415349	Iron (Fe)	2021/06/18	102	80 - 120	99	80 - 120	<0.10	mg/L	1.4	20		
7415349	Lead (Pb)	2021/06/18	102	80 - 120	100	80 - 120	<0.00050	mg/L	NC	20		
7415349	Lithium (Li)	2021/06/18	107	80 - 120	102	80 - 120	<0.0050	mg/L	2.7	20		
7415349	Magnesium (Mg)	2021/06/18	NC	80 - 120	101	80 - 120	<0.050	mg/L	3.1	20		
7415349	Manganese (Mn)	2021/06/18	100	80 - 120	98	80 - 120	<0.0020	mg/L	4.3	20		
7415349	Molybdenum (Mo)	2021/06/18	110	80 - 120	101	80 - 120	<0.00050	mg/L	4.1	20		
7415349	Nickel (Ni)	2021/06/18	100	80 - 120	98	80 - 120	<0.0010	mg/L	0.52	20		
7415349	Phosphorus (P)	2021/06/18	105	80 - 120	104	80 - 120	<0.10	mg/L	NC	20		
7415349	Potassium (K)	2021/06/18	109	80 - 120	103	80 - 120	<0.20	mg/L	2.7	20		
7415349	Selenium (Se)	2021/06/18	105	80 - 120	104	80 - 120	<0.0020	mg/L	NC	20		
7415349	Silicon (Si)	2021/06/18	104	80 - 120	102	80 - 120	<0.050	mg/L	3.7	20		
7415349	Silver (Ag)	2021/06/18	100	80 - 120	99	80 - 120	<0.000090	mg/L	NC	20		
7415349	Sodium (Na)	2021/06/18	NC	80 - 120	101	80 - 120	<0.10	mg/L	1.9	20		
7415349	Strontium (Sr)	2021/06/18	NC	80 - 120	96	80 - 120	<0.0010	mg/L	5.3	20		
7415349	Thallium (TI)	2021/06/18	105	80 - 120	99	80 - 120	<0.000050	mg/L	NC	20		
7415349	Titanium (Ti)	2021/06/18	101	80 - 120	98	80 - 120	<0.0050	mg/L	NC	20		



QUALITY ASSURANCE REPORT(CONT'D)

Stantec Consulting Ltd

Client Project #: 161413217.777

Sampler Initials: AH

			Matrix	Spike	SPIKED	BLANK	Method E	Blank	RPD		QC Standard	
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
7415349	Uranium (U)	2021/06/18	106	80 - 120	101	80 - 120	<0.00010	mg/L	4.3	20		
7415349	Vanadium (V)	2021/06/18	104	80 - 120	98	80 - 120	<0.00050	mg/L	NC	20		İ
7415349	Zinc (Zn)	2021/06/18	101	80 - 120	98	80 - 120	<0.0050	mg/L	1.1	20		
7416560	Alkalinity (Total as CaCO3)	2021/06/18			98	85 - 115	<1.0	mg/L	1.8	20		<u> </u>
7416562	рН	2021/06/18			102	98 - 103			0.26	N/A		<u> </u>
7416565	Conductivity	2021/06/18			100	85 - 115	<1.0	umho/c m	0.32	25		
7416599	Total Ammonia-N	2021/06/21	97	75 - 125	98	80 - 120	<0.050	mg/L	0.36	20		
7416785	Total Suspended Solids	2021/06/21					<10	mg/L	NC	25	97	85 - 115
7417389	Dissolved Organic Carbon	2021/06/18	94	80 - 120	99	80 - 120	<0.40	mg/L	3.0	20		
7417724	Nitrate (N)	2021/06/22	106	80 - 120	105	80 - 120	<0.10	mg/L	0.25	20		
7417724	Nitrite (N)	2021/06/22	107	80 - 120	106	80 - 120	<0.010	mg/L	NC	20		1

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).



Client Project #: 161413217.777

Sampler Initials: AH

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by:

assemb	
Anastassia Hamanov, Scientific Specialist	
Ranju Chaudhari, Senior Analyst	

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

%	05) 817-5700	Toll-free:800-	-563-6266 Fax:905-8	317-5779				×	Not regulate	318/319 ed (however	water is	24		cons	170Pb				*		
VOICE TO:					REPORT T	O:			CAM FCD-0	***************************************	COCCEPTED AT				e of						
ompany Name: #9197 Stantec Cons	sulting Ltd				Same as Ir	rvoice To		-					A	- County	is Reque	sted	Arth III				
tention: Accounts Payable					Company	Name:	***************************************				-			교	1 6						
dress: 300 Hagey Blvd Suite 100 W	aterloo ON N	N2L 0A4			Attention: Grant Whitehead								-								
	oject: 1614:		********************		Address:								,								
	O. #:	13217.777																			
	O. #:				Tel: (519) 585-7400 Fax: (519) 579-4239																
mail: SAPinvoices@Stantec.com					************		************					her	S p	3/ E.							
*DRINKING WATER T	Date	D: [R=Ra	*WATER TYPE	MOE/MO	H Adverse	7			watertrax	-	# of	Comprehensive	Total Suspended Solids	Coliforms/							
Sample Identification/Location	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Sampled	(R,T,D,P,S,F)		cation iired?	Chlorin	W136 (4.55)	Field pH	SPL#	Y/N?	Bottles	Ü	Total Sus	0 0						*	
				Yes	No	Free To	tal	I B				RCAp -	otal	Total		[4					
2001	15 hm21	15:27	P	103	x	1.180	0.48	7.26	· ·		6	-		15		+	-	t:			
100	a June	13.67	- K.		×		0.10	11.26			0	1	1			+	+	9			
	1		6		Х						1										
	16-Jun-	21 00.2	r.		X																
			L	_	X	-		-					-	\vdash		-	+				
TOIL	lin Graci			_	X			+				\vdash	+	+	-	+	+				
	1G5523	Machine Control			- ^			R AT	CD	<u>n</u>		\vdash	+				-				
	I G332.	3						IVI	Ch	\cup	REC	'D I	NV	AT	RLOG	11	\Box		*		
DSG	FNV		Ĭ								110										
AT (TURNAROUND TIME):	*IT IS MA	NDATORY TH	AT ALL NOTIFICATION	N INFORMAT	ON BELOW E	CATION INF	ED PRIOR TO AL	NALYSIS FOR F	REGULATED DRIN	IKING WATER SU	UBMISSION	ıs,*	LAB	DRATO	RY USE ONLY	A 1.25	CO	1	3		
RUSH TAT MUST HAVE PRIOR	Waterworks	Name: .				4	Medical (Officer of Hea	alth/Public Hea	th Unit	Receive	ed By (I	Print):	YA	SPREE	TVO	18				
APPROVAL	Waterworks	Number: .				N	ame/Region:				Receiv	ed By (Sign):		310/16						
Regular (5-15 Working Days)	Address:					C	ontact:				Date:	20	210	6 16	Time:	28:3	1				
RUSH (Specify Below)	Contact:					A	ddress:				Comme	nts	Bbe	2	Tice.	D. W.	1				
ate Due:	Tel:		Fax:				el:						1	-		51.5					
RUSH #	Cell: Email:	34		.v.i			ter Hours:				Receiv	ving To	mn:	10/0	10						
ampled By (Print): A. Healey	L	1. I Control 2012	led By (Sign):				Date:	12.1		Time:		- Ing le			lia Present Y/	N?	M				
relinquished By (Print): A Healer	1		quished By (Sign):				Date:	BJUN		7	9165	0			vation Check	Y/N?	囡				



Your Project #: 161413217.777 Site Location: WELLESLEY

Your C.O.C. #: 15552

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2021/08/12

Report #: R6762261 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C1M2547 Received: 2021/08/06, 14:25

Sample Matrix: Water # Samples Received: 1

·		Date	Date		
Analyses	Quantity	Extracted	Analyzed	Laboratory Method	Analytical Method
Alkalinity	1	N/A	2021/08/10	CAM SOP-00448	SM 23 2320 B m
Carbonate, Bicarbonate and Hydroxide	1	N/A	2021/08/10	CAM SOP-00102	APHA 4500-CO2 D
Chloride by Automated Colourimetry	1	N/A	2021/08/10	CAM SOP-00463	SM 23 4500-Cl E m
Conductivity	1	N/A	2021/08/10	CAM SOP-00414	SM 23 2510 m
Dissolved Organic Carbon (DOC) (1)	1	N/A	2021/08/10	CAM SOP-00446	SM 23 5310 B m
Hardness (calculated as CaCO3)	1	N/A	2021/08/12	CAM SOP 00102/00408/00447	SM 2340 B
Metals Analysis by ICPMS (as received) (2)	1	N/A	2021/08/11	CAM SOP-00447	EPA 6020B m
Ion Balance (% Difference)	1	N/A	2021/08/12		
Anion and Cation Sum	1	N/A	2021/08/12		
Total Coliforms/ E. coli, CFU/100mL	1	N/A	2021/08/06	CAM SOP-00551	MOE E3407
Total Ammonia-N	1	N/A	2021/08/10	CAM SOP-00441	USGS I-2522-90 m
Nitrate (NO3) and Nitrite (NO2) in Water (3)	1	N/A	2021/08/09	CAM SOP-00440	SM 23 4500-NO3I/NO2B
рН	1	2021/08/07	2021/08/10	CAM SOP-00413	SM 4500H+ B m
Orthophosphate	1	N/A	2021/08/09	CAM SOP-00461	EPA 365.1 m
Sat. pH and Langelier Index (@ 20C)	1	N/A	2021/08/12		Auto Calc
Sat. pH and Langelier Index (@ 4C)	1	N/A	2021/08/12		Auto Calc
Sulphate by Automated Colourimetry	1	N/A	2021/08/09	CAM SOP-00464	EPA 375.4 m
Total Dissolved Solids (TDS calc)	1	N/A	2021/08/12		Auto Calc
Total Suspended Solids	1	2021/08/10	2021/08/11	CAM SOP-00428	SM 23 2540D m
Turbidity	1	N/A	2021/08/09	CAM SOP-00417	SM 23 2130 B m

Remarks:

Bureau Veritas is accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Bureau Veritas are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Bureau Veritas' profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Bureau Veritas in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.



Your Project #: 161413217.777
Site Location: WELLESLEY

Your C.O.C. #: 15552

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2021/08/12

Report #: R6762261 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BV LABS JOB #: C1M2547 Received: 2021/08/06, 14:25

Bureau Veritas liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Bureau Veritas has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Bureau Veritas, unless otherwise agreed in writing. Bureau Veritas is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by Bureau Veritas, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

- * RPDs calculated using raw data. The rounding of final results may result in the apparent difference.
- (1) Dissolved Organic Carbon (DOC) present in the sample should be considered as non-purgeable DOC.
- (2) Metals analysis was performed on the sample 'as received'.
- (3) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

Encryption Key



Bureau Veritas 12 Aug 2021 17:28:03

Please direct all questions regarding this Certificate of Analysis to your Project Manager.

Ronklin Gracian, Project Manager

Email: Ronklin.Gracian@bureauveritas.com

Phone# (905)817-5752

This report has been generated and distributed using a secure automated process.

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.



Client Project #: 161413217.777 Site Location: WELLESLEY

Sampler Initials: AV

RCAP - COMPREHENSIVE (DRINKING WATER)

BV Labs ID		QHU792			QHU792		
Sampling Date		2021/08/06			2021/08/06		
Sampling Date		10:40			10:40		
COC Number		15552			15552		
	UNITS	RW02	RDL	QC Batch	RW02 Lab-Dup	RDL	QC Batch
Calculated Parameters							
Anion Sum	me/L	13.0	N/A	7504994			
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	200	1.0	7504991			
Calculated TDS	mg/L	780	1.0	7504997			
Carb. Alkalinity (calc. as CaCO3)	mg/L	3.3	1.0	7504991			
Cation Sum	me/L	12.3	N/A	7504994			
Hardness (CaCO3)	mg/L	580	1.0	7506368			
Ion Balance (% Difference)	%	2.50	N/A	7504993			
Langelier Index (@ 20C)	N/A	1.21		7504995			
Langelier Index (@ 4C)	N/A	0.958		7504996			
Saturation pH (@ 20C)	N/A	7.03		7504995			
Saturation pH (@ 4C)	N/A	7.28		7504996			
Inorganics	•					•	
Total Ammonia-N	mg/L	0.065	0.050	7510353			
Conductivity	umho/cm	1200	1.0	7507152			
Dissolved Organic Carbon	mg/L	0.64	0.40	7510708			
Orthophosphate (P)	mg/L	<0.010	0.010	7507377			
рН	рН	8.23		7507154			
Dissolved Sulphate (SO4)	mg/L	420	2.0	7507376			
Alkalinity (Total as CaCO3)	mg/L	210	1.0	7507135			
Dissolved Chloride (Cl-)	mg/L	2.9	1.0	7507375			
Nitrite (N)	mg/L	<0.010	0.010	7507369	<0.010	0.010	7507369
Nitrate (N)	mg/L	<0.10	0.10	7507369	<0.10	0.10	7507369
Metals	•		•	•	-		
Aluminum (Al)	mg/L	<0.0049	0.0049	7508999			
Antimony (Sb)	mg/L	<0.00050	0.00050	7508999			
Arsenic (As)	mg/L	0.0010	0.0010	7508999			
Barium (Ba)	mg/L	0.024	0.0020	7508999			
Beryllium (Be)	mg/L	<0.00040	0.00040	7508999			
Boron (B)	mg/L	0.047	0.010	7508999			
RDL = Reportable Detection Limit				•			

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Client Project #: 161413217.777
Site Location: WELLESLEY

Sampler Initials: AV

RCAP - COMPREHENSIVE (DRINKING WATER)

BV Labs ID		QHU792			QHU792		
Sampling Date		2021/08/06			2021/08/06		
Jamping Date		10:40			10:40		
COC Number		15552			15552		
	UNITS	RW02	RDL	QC Batch	RW02 Lab-Dup	RDL	QC Batch
Cadmium (Cd)	mg/L	<0.000090	0.000090	7508999			
Calcium (Ca)	mg/L	150	1.0	7508999			
Chromium (Cr)	mg/L	<0.0050	0.0050	7508999			
Cobalt (Co)	mg/L	<0.00050	0.00050	7508999			
Copper (Cu)	mg/L	<0.00090	0.00090	7508999			
Iron (Fe)	mg/L	5.9	0.10	7508999			
Lead (Pb)	mg/L	<0.00050	0.00050	7508999			
Lithium (Li)	mg/L	0.0087	0.0050	7508999			
Magnesium (Mg)	mg/L	50	0.050	7508999			
Manganese (Mn)	mg/L	0.080	0.0020	7508999			
Molybdenum (Mo)	mg/L	0.0016	0.00050	7508999			
Nickel (Ni)	mg/L	<0.0010	0.0010	7508999			
Phosphorus (P)	mg/L	<0.10	0.10	7508999			
Potassium (K)	mg/L	1.4	0.20	7508999			
Selenium (Se)	mg/L	<0.0020	0.0020	7508999			
Silicon (Si)	mg/L	4.7	0.050	7508999			
Silver (Ag)	mg/L	<0.000090	0.000090	7508999			
Sodium (Na)	mg/L	11	0.10	7508999			
Strontium (Sr)	mg/L	38	0.0010	7508999			
Thallium (Tl)	mg/L	<0.000050	0.000050	7508999			
Titanium (Ti)	mg/L	<0.0050	0.0050	7508999			
Uranium (U)	mg/L	0.00016	0.00010	7508999			
Vanadium (V)	mg/L	<0.00050	0.00050	7508999			
Zinc (Zn)	mg/L	<0.0050	0.0050	7508999			

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate



Client Project #: 161413217.777
Site Location: WELLESLEY

Sampler Initials: AV

RESULTS OF ANALYSES OF WATER

BV Labs ID		QHU792			QHU792		
Sampling Date		2021/08/06 10:40			2021/08/06 10:40		
COC Number		15552			15552		
	UNITS	RW02	RDL	QC Batch	RW02 Lab-Dup	RDL	QC Batch
Inorganics							
Total Cuspanded Calids	ma/I	15	10	7509445			
Total Suspended Solids	mg/L	13	10	7303113			

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate



Client Project #: 161413217.777
Site Location: WELLESLEY

Sampler Initials: AV

MICROBIOLOGY (WATER)

BV Labs ID		QHU792				
Sampling Date		2021/08/06				
Sampling Date		10:40				
COC Number		15552				
	UNITS	RW02	QC Batch			
Microbiological						
Microbiological						
Microbiological Total Coliforms	CFU/100mL	0	7506507			
	CFU/100mL CFU/100mL	0	7506507 7506507			



Client Project #: 161413217.777 Site Location: WELLESLEY

Sampler Initials: AV

TEST SUMMARY

BV Labs ID: QHU792 Sample ID: RW02 Matrix: Water **Collected:** 2021/08/06

Shipped:

Received: 2021/08/06

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	7507135	N/A	2021/08/10	Surinder Rai
Carbonate, Bicarbonate and Hydroxide	CALC	7504991	N/A	2021/08/10	Automated Statchk
Chloride by Automated Colourimetry	KONE	7507375	N/A	2021/08/10	Alina Dobreanu
Conductivity	AT	7507152	N/A	2021/08/10	Surinder Rai
Dissolved Organic Carbon (DOC)	TOCV/NDIR	7510708	N/A	2021/08/10	Julianna Castiglione
Hardness (calculated as CaCO3)		7506368	N/A	2021/08/12	Automated Statchk
Metals Analysis by ICPMS (as received)	ICP/MS	7508999	N/A	2021/08/11	Nan Raykha
Ion Balance (% Difference)	CALC	7504993	N/A	2021/08/12	Automated Statchk
Anion and Cation Sum	CALC	7504994	N/A	2021/08/12	Automated Statchk
Total Coliforms/ E. coli, CFU/100mL	PL	7506507	N/A	2021/08/06	Soham Patel
Total Ammonia-N	LACH/NH4	7510353	N/A	2021/08/10	Amanpreet Sappal
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	7507369	N/A	2021/08/09	Chandra Nandlal
рН	AT	7507154	2021/08/07	2021/08/10	Surinder Rai
Orthophosphate	KONE	7507377	N/A	2021/08/09	Avneet Kour Sudan
Sat. pH and Langelier Index (@ 20C)	CALC	7504995	N/A	2021/08/12	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	7504996	N/A	2021/08/12	Automated Statchk
Sulphate by Automated Colourimetry	KONE	7507376	N/A	2021/08/09	Avneet Kour Sudan
Total Dissolved Solids (TDS calc)	CALC	7504997	N/A	2021/08/12	Automated Statchk
Total Suspended Solids	BAL	7509445	2021/08/10	2021/08/11	Shaneil Hall
Turbidity	AT	7507047	N/A	2021/08/09	Neil Dassanayake

BV Labs ID: QHU792 Dup Sample ID: RW02 Matrix: Water **Collected:** 2021/08/06

Shipped:

Received: 2021/08/06

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Nitrate (NO3) and Nitrite (NO2) in Water	LACH	7507369	N/A	2021/08/09	Chandra Nandlal
Turbidity	AT	7507047	N/A	2021/08/09	Neil Dassanayake



Client Project #: 161413217.777 Site Location: WELLESLEY

Sampler Initials: AV

GENERAL COMMENTS

Each te	emperature is the	average of up to t	three cooler temperatures taken at receipt
	Package 1	5.0°C	
Result	s relate only to the	e items tested.	



QUALITY ASSURANCE REPORT

Stantec Consulting Ltd

Client Project #: 161413217.777

Site Location: WELLESLEY

Sampler Initials: AV

			Matrix	Spike	SPIKED	BLANK	Method I	Blank	RP	D	QC Sta	QC Standard	
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits	
7507047	Turbidity	2021/08/09			94	85 - 115	<0.1	NTU	2.7	20			
7507135	Alkalinity (Total as CaCO3)	2021/08/10			96	85 - 115	<1.0	mg/L	0.82	20			
7507152	Conductivity	2021/08/10			103	85 - 115	<1.0	umho/c m	0.68	25			
7507154	рН	2021/08/10			102	98 - 103			0.47	N/A			
7507369	Nitrate (N)	2021/08/09	98	80 - 120	100	80 - 120	<0.10	mg/L	NC	20			
7507369	Nitrite (N)	2021/08/09	107	80 - 120	109	80 - 120	<0.010	mg/L	NC	20			
7507375	Dissolved Chloride (Cl-)	2021/08/10	NC	80 - 120	105	80 - 120	<1.0	mg/L	2.2	20		,	
7507376	Dissolved Sulphate (SO4)	2021/08/09	NC	75 - 125	102	80 - 120	<1.0	mg/L	1.5	20		,	
7507377	Orthophosphate (P)	2021/08/09	124	75 - 125	101	80 - 120	<0.010	mg/L	2.3	25		,	
7508999	Aluminum (AI)	2021/08/11	92	80 - 120	93	80 - 120	<0.0049	mg/L				,	
7508999	Antimony (Sb)	2021/08/11	105	80 - 120	106	80 - 120	<0.00050	mg/L				,	
7508999	Arsenic (As)	2021/08/11	104	80 - 120	104	80 - 120	<0.0010	mg/L					
7508999	Barium (Ba)	2021/08/11	99	80 - 120	101	80 - 120	<0.0020	mg/L					
7508999	Beryllium (Be)	2021/08/11	98	80 - 120	99	80 - 120	<0.00040	mg/L				,	
7508999	Boron (B)	2021/08/11	96	80 - 120	94	80 - 120	<0.010	mg/L					
7508999	Cadmium (Cd)	2021/08/11	101	80 - 120	102	80 - 120	<0.000090	mg/L					
7508999	Calcium (Ca)	2021/08/11	NC	80 - 120	92	80 - 120	<0.20	mg/L	5.2	20		,	
7508999	Chromium (Cr)	2021/08/11	100	80 - 120	99	80 - 120	<0.0050	mg/L				,	
7508999	Cobalt (Co)	2021/08/11	98	80 - 120	99	80 - 120	<0.00050	mg/L					
7508999	Copper (Cu)	2021/08/11	97	80 - 120	98	80 - 120	<0.00090	mg/L				,	
7508999	Iron (Fe)	2021/08/11	99	80 - 120	100	80 - 120	<0.10	mg/L	NC	20		,	
7508999	Lead (Pb)	2021/08/11	100	80 - 120	102	80 - 120	<0.00050	mg/L				,	
7508999	Lithium (Li)	2021/08/11	106	80 - 120	104	80 - 120	<0.0050	mg/L				,	
7508999	Magnesium (Mg)	2021/08/11	NC	80 - 120	103	80 - 120	<0.050	mg/L	1.1	20		,	
7508999	Manganese (Mn)	2021/08/11	97	80 - 120	98	80 - 120	<0.0020	mg/L	2.4	20			
7508999	Molybdenum (Mo)	2021/08/11	106	80 - 120	103	80 - 120	<0.00050	mg/L					
7508999	Nickel (Ni)	2021/08/11	97	80 - 120	99	80 - 120	<0.0010	mg/L					
7508999	Phosphorus (P)	2021/08/11	93	80 - 120	107	80 - 120	<0.10	mg/L					
7508999	Potassium (K)	2021/08/11	95	80 - 120	96	80 - 120	<0.20	mg/L					
7508999	Selenium (Se)	2021/08/11	102	80 - 120	97	80 - 120	<0.0020	mg/L					



QUALITY ASSURANCE REPORT(CONT'D)

Stantec Consulting Ltd

Client Project #: 161413217.777

Site Location: WELLESLEY

Sampler Initials: AV

_			Matrix Spike		SPIKED	SPIKED BLANK		Blank	RPI	O	QC Standard	
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits	% Recovery	QC Limits
7508999	Silicon (Si)	2021/08/11	92	80 - 120	90	80 - 120	<0.050	mg/L				
7508999	Silver (Ag)	2021/08/11	101	80 - 120	101	80 - 120	<0.000090	mg/L				
7508999	Sodium (Na)	2021/08/11	97	80 - 120	102	80 - 120	<0.10	mg/L				
7508999	Strontium (Sr)	2021/08/11	NC	80 - 120	100	80 - 120	<0.0010	mg/L				
7508999	Thallium (TI)	2021/08/11	103	80 - 120	102	80 - 120	<0.000050	mg/L				
7508999	Titanium (Ti)	2021/08/11	91	80 - 120	92	80 - 120	<0.0050	mg/L				
7508999	Uranium (U)	2021/08/11	105	80 - 120	103	80 - 120	<0.00010	mg/L				
7508999	Vanadium (V)	2021/08/11	101	80 - 120	100	80 - 120	<0.00050	mg/L				
7508999	Zinc (Zn)	2021/08/11	98	80 - 120	101	80 - 120	<0.0050	mg/L				
7509445	Total Suspended Solids	2021/08/11					<10	mg/L	NC	25	96	85 - 115
7510353	Total Ammonia-N	2021/08/10	106	75 - 125	101	80 - 120	<0.050	mg/L	2.8	20		
7510708	Dissolved Organic Carbon	2021/08/10	95	80 - 120	99	80 - 120	<0.40	mg/L	0.42	20		

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

QC Standard: A sample of known concentration prepared by an external agency under stringent conditions. Used as an independent check of method accuracy.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).



Client Project #: 161413217.777
Site Location: WELLESLEY

Sampler Initials: AV

VALIDATION SIGNATURE PAGE

The analytical data a	and all QC coi	ntained in thi	s report were r	reviewed and v	validated by:
	/				

Brad Newman, B.Sc., C.Chem., Scientific Service Specialist

Sohem N Patet

Soham Patel, Analyst 2

BV Labs has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation please refer to the Validation Signature Page.

Invoice Information		Report Info	rmation (if d	liffers fro	m invo	ice)						tion (whe				155552 Page of Turnaround Time (TAT) Required
HAME #9197 STANTER CON	USULTIMO-LT Sompany	Name:			17	1			Quotation	ı#: (01	624	A	MILES.		Regular TAT (5-7 days) Most analyses
			RANT	WH	ITE	HEAT	7	W IV	P.O. #/ Al	E#:	North	l on	10.			PLEASE PROVIDE ADVANCE NOTICE FOR RUSH PROJECT
ACOUNTS PAMABLE SUTTE SUTTE	€ VOO Address:				T, Ib		9	N. Fair	Project #:	161	4130	217.	77	1		Rush TAT (Surcharges will be applied)
WATERLOO ON NIL	- OA4		1/1000	e	dd 6	teu	ante	26-60	nte Local	ion: 🔽						1 Day 2 Days 3-4 Days
19-579-4410 Fax: 519-579	-6733 Phone:	519-585-7	400	Fáx:	,		INIL /s		Site #:				1	199	- Hall	
APINVOICES @ STANTEC :	CON Email: 9	grant. whi	tehea	105	tam	tec.	·co	m	Site Local	ion Provin	ce:C	W		7 - Q	17 5 1/11	Date Required:
ATED DRINKING WATER OR WATER INTENDED FOR HUMAN CO	ONSUMPTION MUST BE SUBMITTED	ON THE BUREAU VERITA	LABORATORI	ES' DRINKI	NG WATE	R CHAIN	OF CUS	TODY	Sampled 8	W. A.V	AND	ENT	LOF	F		Rush Confirmation #:
Regulation 153	Other Rep				_	17				s Requeste						LABORATORY USE ONLY
Res/Park Med/ Fine Ind/Comm Coarse		ry Sewer Bylaw Sewer Bylaw								1	7	3				CUSTORY CEAL
B Agri/Other	PWQO Region	n		Crvi			Y			5	0	A				Present Intact COOLER TEMPERATURE
	Other (Specify)	ODMS		1/Hg	Н	Т	١,		â		10	-8			277	Elule
SC (PLEASE CIRCLE) Y / N	REG 558 (MIN. 3 DAY	(A) REQUIRED)	9	Metal			SANIC		HWS-	200		Das				1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
eria on Certificate of Analysis: Y / N				(CLE)			INOR	TALS	etals,	文	1	3	15		3ZAT	NN 0/2/4
PLES MUST BE KEPT COOL (< 10 °C) FROM TIME O	F SAMPLING UNTIL DELIVER	TO BUREAU VERITA	s	ED (CI			ALS &	AS ME	REG 153 METALS Hg, Cr VI, ICPMS Metals, HW5 - B)	-Comprehensive	10	3	3		T ANA	
	DATE SAMPLED	TIME SAMPLED	AATRIX .	ELD FILTERED	PHCFI	2 - F4	EG 153 METALS	EG 153 ICPMS	3 MET	1-0	7	3 1	ā		ON OO	CODLING MEDIA PRESENT: N
SAMPLE IDENTIFICATION	(YYYY/MM/DD)	(HH:MM)	AATRIX 6	PIELD	BTEX/	PHCs F	VOC5	EG 15	REG 15 Hg, Cr	3	古	日本	3		-010	COMMENTS
J02	2021/08/06	1040	GW 6	NA	=	1/	-		Mr. mar	1	V	VV			-	thetals as rec'd
	2000	100				TO T	\top			Ť		-	+		0313	Metals as rec'd
							+					-	+	-		
		-					+	-				_	+			
21 1		7	100		1	Ļ	1	1					\perp			
			06-A	10-2	1 14	.25										
				-		.20								1	Tal.	REC'D IN WATERLOO
		Ron	klin G	acia		ı			-				1		100	WATERLOO
			1M2						-				+			
									_		+	+	+	-		
		ATM	L	NV	14	+	+	+		\vdash	\perp		\perp			
DELINGUISCUIS DU 161																On Ice
RELINQUISHED BY: (Signature/Print)	DATE: (YYYY/MM/DD)	TIME: (HHMM)	-	REC	EIVED 8	Y: (Sign	ature/	Print)	V	DATE	(YYYY/N	IM/DD)		TIME: (HE	(:MM:	BV JOB #
1 AAREN CLANSENHORF !	2021/08/06	H=24	MA	Dire	+	Co	rus	18		20	2/2	dos	1	14:2	et .	1 7 7
	TO VICTORIA		1/	1	-	10	1 1	1	111	22		17	1 6	7.11	11	1 0 3 1
BUT THE THE PARTY OF THE PARTY	STATE OF THE REAL PROPERTY.	The second second	1/12	X		IVI	VA	15/	1)44	102	1108	3/06	A = I	1.0	4	



Your Project #: 161413217.778 Your C.O.C. #: 927351-01-01

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2023/04/20

Report #: R7595176 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BUREAU VERITAS JOB #: C3A5628 Received: 2023/04/14, 12:50

Sample Matrix: Water # Samples Received: 6

		Date	Date		
Analyses	Quantity	Extracted	Analyzed	Laboratory Method	Analytical Method
Alkalinity	6	N/A	2023/04/18	CAM SOP-00448	SM 23 2320 B m
Carbonate, Bicarbonate and Hydroxide	6	N/A	2023/04/18	CAM SOP-00102	APHA 4500-CO2 D
Chloride by Automated Colourimetry	6	N/A	2023/04/18	CAM SOP-00463	SM 23 4500-Cl E m
Conductivity	6	N/A	2023/04/18	CAM SOP-00414	SM 23 2510 m
Dissolved Organic Carbon (DOC) (1)	6	N/A	2023/04/17	CAM SOP-00446	SM 23 5310 B m
Hardness (calculated as CaCO3)	6	N/A	2023/04/18	CAM SOP 00102/00408/00447	EPA 6010D m
Dissolved Metals by ICPMS	6	N/A	2023/04/17	CAM SOP-00447	EPA 6020B m
Ion Balance (% Difference)	5	N/A	2023/04/18		
on Balance (% Difference)	1	N/A	2023/04/19		
Anion and Cation Sum	6	N/A	2023/04/18		
Total Ammonia-N	6	N/A	2023/04/19	CAM SOP-00441	USGS I-2522-90 m
Nitrate & Nitrite as Nitrogen in Water (2)	6	N/A	2023/04/18	CAM SOP-00440	SM 23 4500-NO3I/NO2B
рН	6	2023/04/17	2023/04/18	CAM SOP-00413	SM 4500H+ B m
Orthophosphate	6	N/A	2023/04/18	CAM SOP-00461	SM 23 4500-P E m
Sat. pH and Langelier Index (@ 20C)	5	N/A	2023/04/18		Auto Calc
Sat. pH and Langelier Index (@ 20C)	1	N/A	2023/04/19		Auto Calc
Sat. pH and Langelier Index (@ 4C)	5	N/A	2023/04/18		Auto Calc
Sat. pH and Langelier Index (@ 4C)	1	N/A	2023/04/19		Auto Calc
Sulphate by Automated Turbidimetry	6	N/A	2023/04/18	CAM SOP-00464	SM 23 4500-SO42- E m
Total Dissolved Solids (TDS calc)	5	N/A	2023/04/18		Auto Calc
Total Dissolved Solids (TDS calc)	1	N/A	2023/04/19		Auto Calc

Remarks:

Bureau Veritas is accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Bureau Veritas are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCC, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Bureau Veritas' profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Bureau Veritas in writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement



Your Project #: 161413217.778 Your C.O.C. #: 927351-01-01

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2023/04/20

Report #: R7595176 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BUREAU VERITAS JOB #: C3A5628 Received: 2023/04/14, 12:50

Uncertainty has not been accounted for when stating conformity to the referenced standard.

Bureau Veritas liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Bureau Veritas has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Bureau Veritas, unless otherwise agreed in writing. Bureau Veritas is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by Bureau Veritas, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

- * RPDs calculated using raw data. The rounding of final results may result in the apparent difference.
- (1) Dissolved Organic Carbon (DOC) present in the sample should be considered as non-purgeable DOC.
- (2) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

Encryption Key

Please direct all questions regarding this Certificate of Analysis to: Julie Clement, Technical Account Manager Email: Julie.CLEMENT@bureauveritas.com Phone# (613)868-6079

This report has been generated and distributed using a secure automated process.

Bureau Veritas has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation, please refer to the Validation Signatures page if included, otherwise available by request. For Department specific Analyst/Supervisor validation names, please refer to the Test Summary section if included, otherwise available by request. This report is authorized by Rodney Major, General Manager responsible for Ontario Environmental laboratory operations.

Total Cover Pages : 2 Page 2 of 15



Sampler Initials: R

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		VOD656	VOD657	VOD658	VOD659		
Sampling Date		2023/04/13	2023/04/13	2023/04/13	2023/04/13		
		11:10	12:05	14:05	14:50		
COC Number		927351-01-01	927351-01-01	927351-01-01	927351-01-01		
	UNITS	BH04-21	BH06-21	BH05-21	BH02-21	RDL	QC Batch
Calculated Parameters							
Anion Sum	me/L	5.08	6.92	8.21	6.83	N/A	8610005
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	190	280	290	270	1.0	8610001
Calculated TDS	mg/L	290	370	450	370	1.0	8610000
Carb. Alkalinity (calc. as CaCO3)	mg/L	2.7	3.7	3.0	3.2	1.0	8610001
Cation Sum	me/L	5.42	7.08	8.57	6.95	N/A	8610005
Hardness (CaCO3)	mg/L	190	280	390	270	1.0	8610003
Ion Balance (% Difference)	%	3.22	1.20	2.13	0.860	N/A	8610004
Langelier Index (@ 20C)	N/A	0.695	0.871	0.987	0.833		8610006
Langelier Index (@ 4C)	N/A	0.446	0.622	0.739	0.585		8610007
Saturation pH (@ 20C)	N/A	7.49	7.28	7.05	7.27		8610006
Saturation pH (@ 4C)	N/A	7.74	7.53	7.29	7.52		8610007
Inorganics							
Total Ammonia-N	mg/L	0.082	<0.050	0.090	<0.050	0.050	8611996
Conductivity	umho/cm	500	640	740	650	1.0	8611440
Dissolved Organic Carbon	mg/L	1.3	0.83	0.97	0.76	0.40	8611466
Orthophosphate (P)	mg/L	<0.010	<0.010	<0.010	0.017	0.010	8611552
рН	рН	8.19	8.15	8.03	8.11		8611148
Dissolved Sulphate (SO4)	mg/L	44	60	93	59	1.0	8611561
Alkalinity (Total as CaCO3)	mg/L	190	280	300	270	1.0	8611439
Dissolved Chloride (Cl-)	mg/L	13	2.2	12	5.3	1.0	8611567
Nitrite (N)	mg/L	<0.010	<0.010	<0.010	<0.010	0.010	8611162
Nitrate (N)	mg/L	<0.10	<0.10	<0.10	0.60	0.10	8611162
Nitrate + Nitrite (N)	mg/L	<0.10	<0.10	<0.10	0.60	0.10	8611162
Metals							
Dissolved Aluminum (Al)	mg/L	<0.0049	0.0072	0.0049	0.015	0.0049	8611983
Dissolved Antimony (Sb)	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	0.00050	8611983
Dissolved Arsenic (As)	mg/L	<0.0010	<0.0010	0.0027	<0.0010	0.0010	8611983
Dissolved Barium (Ba)	mg/L	0.061	0.12	0.14	0.11	0.0020	8611983
Dissolved Beryllium (Be)	mg/L	<0.00040	<0.00040	<0.00040	<0.00040	0.00040	8611983
Dissolved Boron (B)	mg/L	0.14	0.13	0.024	0.12	0.010	8611983
Dissolved Cadmium (Cd)	mg/L	<0.000090	<0.000090	<0.000090	<0.000090	0.000090	8611983

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Sampler Initials: R

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		VOD656	VOD657	VOD658	VOD659		
Sampling Date		2023/04/13	2023/04/13	2023/04/13	2023/04/13		
Sampling Date		11:10	12:05	14:05	14:50		
COC Number		927351-01-01	927351-01-01	927351-01-01	927351-01-01		
	UNITS	BH04-21	BH06-21	BH05-21	BH02-21	RDL	QC Batch
Dissolved Calcium (Ca)	mg/L	44	52	87	54	0.20	8611983
Dissolved Chromium (Cr)	mg/L	<0.0050	<0.0050	<0.0050	<0.0050	0.0050	8611983
Dissolved Cobalt (Co)	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	0.00050	8611983
Dissolved Copper (Cu)	mg/L	0.0022	0.0018	0.0010	<0.00090	0.00090	8611983
Dissolved Iron (Fe)	mg/L	<0.10	<0.10	<0.10	<0.10	0.10	8611983
Dissolved Lead (Pb)	mg/L	<0.00050	<0.00050	<0.00050	<0.00050	0.00050	8611983
Dissolved Magnesium (Mg)	mg/L	19	37	41	33	0.050	8611983
Dissolved Manganese (Mn)	mg/L	0.053	0.0056	0.076	0.0042	0.0020	8611983
Dissolved Molybdenum (Mo)	mg/L	0.0085	0.0063	0.0024	0.0084	0.00050	8611983
Dissolved Nickel (Ni)	mg/L	<0.0010	<0.0010	0.0015	<0.0010	0.0010	8611983
Dissolved Phosphorus (P)	mg/L	<0.10	<0.10	<0.10	<0.10	0.10	8611983
Dissolved Potassium (K)	mg/L	1.3	2.0	1.8	2.1	0.20	8611983
Dissolved Selenium (Se)	mg/L	<0.0020	<0.0020	<0.0020	<0.0020	0.0020	8611983
Dissolved Silicon (Si)	mg/L	6.3	6.3	8.6	6.2	0.050	8611983
Dissolved Silver (Ag)	mg/L	<0.000090	<0.000090	<0.000090	<0.000090	0.000090	8611983
Dissolved Sodium (Na)	mg/L	37	33	18	34	0.10	8611983
Dissolved Strontium (Sr)	mg/L	0.59	1.8	0.46	1.3	0.0010	8611983
Dissolved Thallium (TI)	mg/L	<0.000050	<0.000050	<0.000050	<0.000050	0.000050	8611983
Dissolved Titanium (Ti)	mg/L	<0.0050	<0.0050	<0.0050	<0.0050	0.0050	8611983
Dissolved Uranium (U)	mg/L	0.0017	0.0032	0.0021	0.0028	0.00010	8611983
Dissolved Vanadium (V)	mg/L	<0.00050	0.00084	<0.00050	0.00076	0.00050	8611983
Dissolved Zinc (Zn)	mg/L	<0.0050	<0.0050	<0.0050	<0.0050	0.0050	8611983

RDL = Reportable Detection Limit QC Batch = Quality Control Batch



Sampler Initials: R

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		VOD659			VOD660	VOD661		
Sampling Date		2023/04/13 14:50			2023/04/13 15:06	2023/04/13 16:30		
COC Number		927351-01-01			927351-01-01	927351-01-01		
	UNITS	BH02-21 Lab-Dup	RDL	QC Batch	вн03-21	BH01-21	RDL	QC Batch
Calculated Parameters	<u>- </u>		•	<u> </u>			·	<u></u>
Anion Sum	me/L				8.68	11.5	N/A	8610005
Bicarb. Alkalinity (calc. as CaCO3)	mg/L				350	310	1.0	8610001
Calculated TDS	mg/L				460	660	1.0	8610000
Carb. Alkalinity (calc. as CaCO3)	mg/L				2.9	3.1	1.0	8610001
Cation Sum	me/L				8.98	13.0	N/A	8610005
Hardness (CaCO3)	mg/L				440	440	1.0	8610003
lon Balance (% Difference)	%				1.68	6.10	N/A	8610004
Langelier Index (@ 20C)	N/A				1.08	1.02		8610006
Langelier Index (@ 4C)	N/A				0.834	0.774		8610007
Saturation pH (@ 20C)	N/A				6.87	7.01		8610006
Saturation pH (@ 4C)	N/A				7.11	7.25		8610007
Inorganics								
Total Ammonia-N	mg/L				0.070	0.10	0.050	8611996
Conductivity	umho/cm				780	1200	1.0	8611440
Dissolved Organic Carbon	mg/L				0.98	1.4	0.40	8611466
Orthophosphate (P)	mg/L	<0.010	0.010	8611552	<0.010	<0.010	0.010	8611552
рН	рН				7.95	8.03		8611148
Dissolved Sulphate (SO4)	mg/L	60	1.0	8611561	69	68	1.0	8611561
Alkalinity (Total as CaCO3)	mg/L				350	310	1.0	8611439
Dissolved Chloride (Cl-)	mg/L	5.0	1.0	8611567	6.0	140	1.0	8611567
Nitrite (N)	mg/L				<0.010	<0.010	0.010	8611162
Nitrate (N)	mg/L				<0.10	<0.10	0.10	8611162
Nitrate + Nitrite (N)	mg/L				<0.10	<0.10	0.10	8611162
Metals	•	•	•	•			•	•
Dissolved Aluminum (AI)	mg/L				<0.0049	0.32	0.0049	8611983
Dissolved Antimony (Sb)	mg/L				<0.00050	<0.00050	0.00050	8611983
Dissolved Arsenic (As)	mg/L				0.0013	0.0017	0.0010	8611983
Dissolved Barium (Ba)	mg/L				0.12	0.16	0.0020	8611983
Dissolved Beryllium (Be)	mg/L	<u> </u>			<0.00040	<0.00040	0.00040	8611983
Dissolved Boron (B)	mg/L				0.015	0.048	0.010	8611983

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Sampler Initials: R

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		VOD659			VOD660	VOD661		
Sampling Date		2023/04/13			2023/04/13	2023/04/13		
Sampling Date		14:50			15:06	16:30		
COC Number		927351-01-01			927351-01-01	927351-01-01		
	UNITS	BH02-21 Lab-Dup	RDL	QC Batch	BH03-21	BH01-21	RDL	QC Batch
Dissolved Cadmium (Cd)	mg/L				<0.000090	<0.000090	0.000090	8611983
Dissolved Calcium (Ca)	mg/L				110	100	0.20	8611983
Dissolved Chromium (Cr)	mg/L				<0.0050	<0.0050	0.0050	8611983
Dissolved Cobalt (Co)	mg/L				<0.00050	<0.00050	0.00050	8611983
Dissolved Copper (Cu)	mg/L				<0.00090	0.0014	0.00090	8611983
Dissolved Iron (Fe)	mg/L				0.21	0.29	0.10	8611983
Dissolved Lead (Pb)	mg/L				<0.00050	<0.00050	0.00050	8611983
Dissolved Magnesium (Mg)	mg/L				38	47	0.050	8611983
Dissolved Manganese (Mn)	mg/L				0.044	0.054	0.0020	8611983
Dissolved Molybdenum (Mo)	mg/L				0.00087	0.0040	0.00050	8611983
Dissolved Nickel (Ni)	mg/L				<0.0010	<0.0010	0.0010	8611983
Dissolved Phosphorus (P)	mg/L				<0.10	<0.10	0.10	8611983
Dissolved Potassium (K)	mg/L				1.3	2.6	0.20	8611983
Dissolved Selenium (Se)	mg/L				<0.0020	<0.0020	0.0020	8611983
Dissolved Silicon (Si)	mg/L				7.9	9.2	0.050	8611983
Dissolved Silver (Ag)	mg/L				<0.000090	<0.000090	0.000090	8611983
Dissolved Sodium (Na)	mg/L				5.4	93	0.10	8611983
Dissolved Strontium (Sr)	mg/L				0.39	1.1	0.0010	8611983
Dissolved Thallium (TI)	mg/L				<0.000050	<0.000050	0.000050	8611983
Dissolved Titanium (Ti)	mg/L				<0.0050	0.014	0.0050	8611983
Dissolved Uranium (U)	mg/L				0.00062	0.0037	0.00010	8611983
Dissolved Vanadium (V)	mg/L				<0.00050	0.00079	0.00050	8611983
Dissolved Zinc (Zn)	mg/L				<0.0050	<0.0050	0.0050	8611983

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate



Matrix: Water

Stantec Consulting Ltd

Client Project #: 161413217.778

Sampler Initials: R

TEST SUMMARY

Bureau Veritas ID: VOD656 **Collected:** 2023/04/13 Sample ID: BH04-21

Shipped:

Received: 2023/04/14

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	8611439	N/A	2023/04/18	Kien Tran
Carbonate, Bicarbonate and Hydroxide	CALC	8610001	N/A	2023/04/18	Automated Statchk
Chloride by Automated Colourimetry	KONE	8611567	N/A	2023/04/18	Massarat Jan
Conductivity	AT	8611440	N/A	2023/04/18	Kien Tran
Dissolved Organic Carbon (DOC)	TOCV/NDIR	8611466	N/A	2023/04/17	Gyulshen Idriz
Hardness (calculated as CaCO3)		8610003	N/A	2023/04/18	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	8611983	N/A	2023/04/17	Arefa Dabhad
Ion Balance (% Difference)	CALC	8610004	N/A	2023/04/19	Automated Statchk
Anion and Cation Sum	CALC	8610005	N/A	2023/04/18	Automated Statchk
Total Ammonia-N	LACH/NH4	8611996	N/A	2023/04/19	Prabhjot Kaur
Nitrate & Nitrite as Nitrogen in Water	LACH	8611162	N/A	2023/04/18	Chandra Nandlal
рН	AT	8611148	2023/04/17	2023/04/18	Kien Tran
Orthophosphate	KONE	8611552	N/A	2023/04/18	Massarat Jan
Sat. pH and Langelier Index (@ 20C)	CALC	8610006	N/A	2023/04/19	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	8610007	N/A	2023/04/19	Automated Statchk
Sulphate by Automated Turbidimetry	KONE	8611561	N/A	2023/04/18	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	8610000	N/A	2023/04/19	Automated Statchk

Bureau Veritas ID: VOD657 Sample ID: BH06-21 Matrix: Water **Collected:** 2023/04/13

Shipped:

Received: 2023/04/14

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	8611439	N/A	2023/04/18	Kien Tran
Carbonate, Bicarbonate and Hydroxide	CALC	8610001	N/A	2023/04/18	Automated Statchk
Chloride by Automated Colourimetry	KONE	8611567	N/A	2023/04/18	Massarat Jan
Conductivity	AT	8611440	N/A	2023/04/18	Kien Tran
Dissolved Organic Carbon (DOC)	TOCV/NDIR	8611466	N/A	2023/04/17	Gyulshen Idriz
Hardness (calculated as CaCO3)		8610003	N/A	2023/04/18	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	8611983	N/A	2023/04/17	Arefa Dabhad
Ion Balance (% Difference)	CALC	8610004	N/A	2023/04/18	Automated Statchk
Anion and Cation Sum	CALC	8610005	N/A	2023/04/18	Automated Statchk
Total Ammonia-N	LACH/NH4	8611996	N/A	2023/04/19	Prabhjot Kaur
Nitrate & Nitrite as Nitrogen in Water	LACH	8611162	N/A	2023/04/18	Chandra Nandlal
рН	AT	8611148	2023/04/17	2023/04/18	Kien Tran
Orthophosphate	KONE	8611552	N/A	2023/04/18	Massarat Jan
Sat. pH and Langelier Index (@ 20C)	CALC	8610006	N/A	2023/04/18	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	8610007	N/A	2023/04/18	Automated Statchk
Sulphate by Automated Turbidimetry	KONE	8611561	N/A	2023/04/18	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	8610000	N/A	2023/04/18	Automated Statchk



Matrix: Water

Sulphate by Automated Turbidimetry

Matrix:

Water

Total Dissolved Solids (TDS calc)

Stantec Consulting Ltd

2023/04/18

2023/04/18

Client Project #: 161413217.778

Sampler Initials: R

TEST SUMMARY

Bureau Veritas ID: VOD658 Collected: 2023/04/13 Sample ID: BH05-21

Shipped: Received: 2023/04/14

Test Description Extracted Instrumentation Batch **Date Analyzed** Analyst Alkalinity ΑТ 8611439 N/A 2023/04/18 Kien Tran CALC Automated Statchk Carbonate, Bicarbonate and Hydroxide 8610001 N/A 2023/04/18 Chloride by Automated Colourimetry KONE 8611567 N/A 2023/04/18 Massarat Jan Conductivity ΑT 8611440 N/A 2023/04/18 Kien Tran Dissolved Organic Carbon (DOC) TOCV/NDIR 8611466 N/A 2023/04/17 Gyulshen Idriz Hardness (calculated as CaCO3) 8610003 N/A 2023/04/18 Automated Statchk ICP/MS Dissolved Metals by ICPMS 8611983 N/A 2023/04/17 Arefa Dabhad Ion Balance (% Difference) CALC 8610004 N/A 2023/04/18 Automated Statchk Anion and Cation Sum CALC N/A 2023/04/18 8610005 Automated Statchk Total Ammonia-N LACH/NH4 8611996 N/A 2023/04/19 Prabhjot Kaur Nitrate & Nitrite as Nitrogen in Water LACH 8611162 Chandra Nandlal N/A 2023/04/18 2023/04/17 рΗ ΑТ 8611148 2023/04/18 Kien Tran KONE 8611552 2023/04/18 Massarat Jan Orthophosphate N/A Sat. pH and Langelier Index (@ 20C) CALC 8610006 N/A 2023/04/18 Automated Statchk Sat. pH and Langelier Index (@ 4C) CALC 8610007 N/A 2023/04/18 Automated Statchk

Collected: Bureau Veritas ID: VOD659 2023/04/13 Sample ID: BH02-21

8611561

8610000

N/A

N/A

KONE

CALC

Shipped:

Received:

Massarat Jan

Automated Statchk

2023/04/14

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	8611439	N/A	2023/04/18	Kien Tran
Carbonate, Bicarbonate and Hydroxide	CALC	8610001	N/A	2023/04/18	Automated Statchk
Chloride by Automated Colourimetry	KONE	8611567	N/A	2023/04/18	Massarat Jan
Conductivity	AT	8611440	N/A	2023/04/18	Kien Tran
Dissolved Organic Carbon (DOC)	TOCV/NDIR	8611466	N/A	2023/04/17	Gyulshen Idriz
Hardness (calculated as CaCO3)		8610003	N/A	2023/04/18	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	8611983	N/A	2023/04/17	Arefa Dabhad
Ion Balance (% Difference)	CALC	8610004	N/A	2023/04/18	Automated Statchk
Anion and Cation Sum	CALC	8610005	N/A	2023/04/18	Automated Statchk
Total Ammonia-N	LACH/NH4	8611996	N/A	2023/04/19	Prabhjot Kaur
Nitrate & Nitrite as Nitrogen in Water	LACH	8611162	N/A	2023/04/18	Chandra Nandlal
рН	AT	8611148	2023/04/17	2023/04/18	Kien Tran
Orthophosphate	KONE	8611552	N/A	2023/04/18	Massarat Jan
Sat. pH and Langelier Index (@ 20C)	CALC	8610006	N/A	2023/04/18	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	8610007	N/A	2023/04/18	Automated Statchk
Sulphate by Automated Turbidimetry	KONE	8611561	N/A	2023/04/18	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	8610000	N/A	2023/04/18	Automated Statchk



Report Date: 2023/04/20

Stantec Consulting Ltd

Client Project #: 161413217.778

Sampler Initials: R

TEST SUMMARY

Bureau Veritas ID: VOD659 Dup

Sample ID: BH02-21

Matrix: Water

Collected: 2023/04/13

Shipped:

Received: 2023/04/14

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Chloride by Automated Colourimetry	KONE	8611567	N/A	2023/04/18	Massarat Jan
Orthophosphate	KONE	8611552	N/A	2023/04/18	Massarat Jan
Sulphate by Automated Turbidimetry	KONE	8611561	N/A	2023/04/18	Massarat Jan

Bureau Veritas ID: VOD660

Sample ID: BH03-21

Matrix: Water

Collected: 2023/04/13

Shipped:

Received: 2023/04/14

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	8611439	N/A	2023/04/18	Kien Tran
Carbonate, Bicarbonate and Hydroxide	CALC	8610001	N/A	2023/04/18	Automated Statchk
Chloride by Automated Colourimetry	KONE	8611567	N/A	2023/04/18	Massarat Jan
Conductivity	AT	8611440	N/A	2023/04/18	Kien Tran
Dissolved Organic Carbon (DOC)	TOCV/NDIR	8611466	N/A	2023/04/17	Gyulshen Idriz
Hardness (calculated as CaCO3)		8610003	N/A	2023/04/18	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	8611983	N/A	2023/04/17	Arefa Dabhad
Ion Balance (% Difference)	CALC	8610004	N/A	2023/04/18	Automated Statchk
Anion and Cation Sum	CALC	8610005	N/A	2023/04/18	Automated Statchk
Total Ammonia-N	LACH/NH4	8611996	N/A	2023/04/19	Prabhjot Kaur
Nitrate & Nitrite as Nitrogen in Water	LACH	8611162	N/A	2023/04/18	Chandra Nandlal
рН	AT	8611148	2023/04/17	2023/04/18	Kien Tran
Orthophosphate	KONE	8611552	N/A	2023/04/18	Massarat Jan
Sat. pH and Langelier Index (@ 20C)	CALC	8610006	N/A	2023/04/18	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	8610007	N/A	2023/04/18	Automated Statchk
Sulphate by Automated Turbidimetry	KONE	8611561	N/A	2023/04/18	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	8610000	N/A	2023/04/18	Automated Statchk

Bureau Veritas ID: VOD661

Sample ID: BH01-21

Matrix: Water

Shipped:

Collected: 2023/04/13

Received: 2023/04/14

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	8611439	N/A	2023/04/18	Kien Tran
Carbonate, Bicarbonate and Hydroxide	CALC	8610001	N/A	2023/04/18	Automated Statchk
Chloride by Automated Colourimetry	KONE	8611567	N/A	2023/04/18	Massarat Jan
Conductivity	AT	8611440	N/A	2023/04/18	Kien Tran
Dissolved Organic Carbon (DOC)	TOCV/NDIR	8611466	N/A	2023/04/17	Gyulshen Idriz
Hardness (calculated as CaCO3)		8610003	N/A	2023/04/18	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	8611983	N/A	2023/04/17	Arefa Dabhad
Ion Balance (% Difference)	CALC	8610004	N/A	2023/04/18	Automated Statchk
Anion and Cation Sum	CALC	8610005	N/A	2023/04/18	Automated Statchk
Total Ammonia-N	LACH/NH4	8611996	N/A	2023/04/19	Prabhjot Kaur
Nitrate & Nitrite as Nitrogen in Water	LACH	8611162	N/A	2023/04/18	Chandra Nandlal
рН	AT	8611148	2023/04/17	2023/04/18	Kien Tran
Orthophosphate	KONE	8611552	N/A	2023/04/18	Massarat Jan



Client Project #: 161413217.778

Sampler Initials: R

TEST SUMMARY

Bureau Veritas ID: VOD661 **Collected:** 2023/04/13

Shipped:

Sample ID: BH01-21 Matrix: Water **Received:** 2023/04/14

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sat. pH and Langelier Index (@ 20C)	CALC	8610006	N/A	2023/04/18	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	8610007	N/A	2023/04/18	Automated Statchk
Sulphate by Automated Turbidimetry	KONE	8611561	N/A	2023/04/18	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	8610000	N/A	2023/04/18	Automated Statchk



Sampler Initials: R

GENERAL COMMENTS

Each temperature is the average of up to three cooler temperatures taken at receipt

Package 1 2.0 C	Package 1	2.0°C
-----------------	-----------	-------

Sample VOD659 [BH02-21]: Total Phosphorus < ortho-Phosphate: Both values fall within the method uncertainty for duplicates and are likely equivalent.

Results relate only to the items tested.



QUALITY ASSURANCE REPORT

Stantec Consulting Ltd

Client Project #: 161413217.778

Sampler Initials: R

			Matrix	Spike	SPIKED	BLANK	Method I	Blank	RP	D
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
8611148	рН	2023/04/18			102	98 - 103			0.18	N/A
8611162	Nitrate (N)	2023/04/18	103	80 - 120	108	80 - 120	<0.10	mg/L	2.1	20
8611162	Nitrite (N)	2023/04/18	101	80 - 120	105	80 - 120	<0.010	mg/L	NC	20
8611439	Alkalinity (Total as CaCO3)	2023/04/18			95	85 - 115	<1.0	mg/L	1.0	20
8611440	Conductivity	2023/04/18			102	85 - 115	<1.0	umho/cm	0.41	25
8611466	Dissolved Organic Carbon	2023/04/17	96	80 - 120	99	80 - 120	<0.40	mg/L	9.2	20
8611552	Orthophosphate (P)	2023/04/18	92	75 - 125	99	80 - 120	<0.010	mg/L	NC	20
8611561	Dissolved Sulphate (SO4)	2023/04/18	NC	75 - 125	102	80 - 120	<1.0	mg/L	0.85	20
8611567	Dissolved Chloride (Cl-)	2023/04/18	97	80 - 120	100	80 - 120	<1.0	mg/L	5.1	20
8611983	Dissolved Aluminum (AI)	2023/04/17	101	80 - 120	102	80 - 120	<0.0049	mg/L	NC	20
8611983	Dissolved Antimony (Sb)	2023/04/17	104	80 - 120	101	80 - 120	<0.00050	mg/L	11	20
8611983	Dissolved Arsenic (As)	2023/04/17	100	80 - 120	101	80 - 120	<0.0010	mg/L	2.0	20
8611983	Dissolved Barium (Ba)	2023/04/17	101	80 - 120	101	80 - 120	<0.0020	mg/L	1.0	20
8611983	Dissolved Beryllium (Be)	2023/04/17	99	80 - 120	99	80 - 120	<0.00040	mg/L	NC	20
8611983	Dissolved Boron (B)	2023/04/17	100	80 - 120	99	80 - 120	<0.010	mg/L	3.2	20
8611983	Dissolved Cadmium (Cd)	2023/04/17	101	80 - 120	99	80 - 120	<0.000090	mg/L	NC	20
8611983	Dissolved Calcium (Ca)	2023/04/17	NC	80 - 120	100	80 - 120	<0.20	mg/L	6.2	20
8611983	Dissolved Chromium (Cr)	2023/04/17	94	80 - 120	95	80 - 120	<0.0050	mg/L	NC	20
8611983	Dissolved Cobalt (Co)	2023/04/17	102	80 - 120	101	80 - 120	<0.00050	mg/L	NC	20
8611983	Dissolved Copper (Cu)	2023/04/17	97	80 - 120	96	80 - 120	<0.00090	mg/L	5.9	20
8611983	Dissolved Iron (Fe)	2023/04/17	103	80 - 120	101	80 - 120	<0.10	mg/L	NC	20
8611983	Dissolved Lead (Pb)	2023/04/17	96	80 - 120	95	80 - 120	<0.00050	mg/L	NC	20
8611983	Dissolved Magnesium (Mg)	2023/04/17	NC	80 - 120	102	80 - 120	<0.050	mg/L	3.7	20
8611983	Dissolved Manganese (Mn)	2023/04/17	101	80 - 120	101	80 - 120	<0.0020	mg/L	1.4	20
8611983	Dissolved Molybdenum (Mo)	2023/04/17	98	80 - 120	97	80 - 120	<0.00050	mg/L	2.6	20
8611983	Dissolved Nickel (Ni)	2023/04/17	97	80 - 120	100	80 - 120	<0.0010	mg/L	NC	20
8611983	Dissolved Phosphorus (P)	2023/04/17	104	80 - 120	114	80 - 120	<0.10	mg/L	NC	20
8611983	Dissolved Potassium (K)	2023/04/17	107	80 - 120	108	80 - 120	<0.20	mg/L	1.9	20
8611983	Dissolved Selenium (Se)	2023/04/17	99	80 - 120	99	80 - 120	<0.0020	mg/L	NC	20
8611983	Dissolved Silicon (Si)	2023/04/17	103	80 - 120	104	80 - 120	<0.050	mg/L	1.1	20
8611983	Dissolved Silver (Ag)	2023/04/17	97	80 - 120	96	80 - 120	<0.000090	mg/L	NC	20



Report Date: 2023/04/20

QUALITY ASSURANCE REPORT(CONT'D)

Stantec Consulting Ltd

Client Project #: 161413217.778

Sampler Initials: R

			Matrix	Matrix Spike		SPIKED BLANK		lank	RPD	
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
8611983	Dissolved Sodium (Na)	2023/04/17	102	80 - 120	107	80 - 120	<0.10	mg/L	5.4	20
8611983	Dissolved Strontium (Sr)	2023/04/17	NC	80 - 120	100	80 - 120	<0.0010	mg/L	3.0	20
8611983	Dissolved Thallium (TI)	2023/04/17	97	80 - 120	93	80 - 120	<0.000050	mg/L	NC	20
8611983	Dissolved Titanium (Ti)	2023/04/17	103	80 - 120	104	80 - 120	<0.0050	mg/L	NC	20
8611983	Dissolved Uranium (U)	2023/04/17	99	80 - 120	98	80 - 120	<0.00010	mg/L	NC	20
8611983	Dissolved Vanadium (V)	2023/04/17	98	80 - 120	98	80 - 120	<0.00050	mg/L	NC	20
8611983	Dissolved Zinc (Zn)	2023/04/17	NC	80 - 120	101	80 - 120	<0.0050	mg/L	0.95	20
8611996	Total Ammonia-N	2023/04/19	99	75 - 125	98	80 - 120	<0.050	mg/L	NC	20

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).



Sampler Initials: R

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by:

Anastassia Hamanov, Scientific Specialist

Bureau Veritas has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation, please refer to the Validation Signatures page if included, otherwise available by request. For Department specific Analyst/Supervisor validation names, please refer to the Test Summary section if included, otherwise available by request. This report is authorized by {0}, {1} responsible for {2} {3} laboratory operations.

BUREAU VERITAS		Bureau Veritas 6740 Campobello Road	d, Mississauga, Ontai	rio Canada L5N 21	L8 Tel:(905) 817-5	700 Toll-free 800	-563-6266 Fax:(905) 817-5777	www.bvna.com					CHAIN	OF CU	14-/	Apr-23 12:50	Page	of
		VVOICE TO:				REPO	RT TO:				PRO	ECT INFORMA	ATION:			Julie Clem	ipi-23 12:50		
Company Name:		Section 1 and 1 an		Company						uotation#	C1:	5856		1,1100	ı		ent Historia		
Attention:	Accounts Payab			Attention	Grant V	Vhitehead			F	.0,#		TELL IFM				C3A56	28		
Address:	300 Hagey Blvd Waterloo ON N2	STREET, STREET		Address:	-					roject:					- p	I tre			-
Tel:	(519) 579-4410		519) 579-6733	Tel:	(519) 5	85-7400	Fax	(519) 579	0.4220	roject Nam ite #.	9:				111111	UK EN	IV-965		
Email:	SAPinvoices@S			Email:		hitehead@st				ampled By					11111111	C#927351-01-01	101/0001100		
		G WATER OR WATE				MUST BE			ANAL	YSIS REQI	JESTED (PLEAS	E BE SPECIFI	0)				d Time (TAT) Required		
	SUBMITTED ON T	HE BUREAU VERIT	AS DRINKING W	ATER CHAIN	OF CUSTODY		÷								Regular (Standard) TAT:	dvance notice for rush p	projects	
111111111111111111111111111111111111111	ion 153 (2011)		Other Regulations		Special In	structions	circle):									ed if Rush TAT is not sp	ecified):		
The state of the s	Res/Park Mediu		Sanitary Sewer I											1	- A-4-COLONIA - COLONIA -	T = 5-7 Working days fo			
Table 3	Ind/Comm Coars Agri/Other For R		Storm Sewer By Municipality	aw			(plea	evisi							Please note: days - conta	Standard TAT for certai of your Project Manager	n tests such as BOD and for details.	Dioxins/Furans	are > 5
Table 3		PWQO	Reg 406 Table	LA HILL			Field Filtered (please c	reher				1 1					s to entire submission		
		Other	ODWS	10-1-17			Filt	diwo							Date Require	mation Number:	Time Requ	ired:	$-\Box$
	Include Criter	a on Certificate of An	nalysis (Y/N)?	_			le C	RCAp - C							# of Bottles	nadori Number.	(call lab fo	r#)	
Sample	le Barcode Label	Sample (Location)	Identification	Date Sampled	Time Sampled	Matrix		RC.				+			# or Bottles	11 1 0	comments potab	10 0	W
1		BH04-	21	Apr13	11.10	GW	MOKE	X	1 1							Not fro	m pords	ه ه	W
2		BH06-	Z١	Apr 13	12:05	GN	HV	X					į.				//		
3		BHC5-	21	Apr13	14 05	GW	1	X									10		
4		BHOZ		Apr 13	14:50	GW	~	X				-					11		
5		BH 03.	A	pr13	15:06	GW	1	X									10		
6		RHOI -		Apr 13	16:30	GW		X									17		
7	-	51.01	<u> </u>	17.5	.0 32														
8												-	7						
9											-				-	REC'D IN	WATERLOC)	
10				4															
10							posite sola				1								
• 1	RELINQUISHED BY: (S	signature/Print)	Date: (YY/MI		1.00	1	BY: (Signature/	-	Date: (YY/M		Time		sed and bmitted			atory Use Only		Lvas	l No
6.	Ken!	M/C	23/0	1/14 12	50	KINDA	TRAS A		2013 04	114	12-50		File	Time Sensitive	Tempera	ture (°C) on Recei	Present	Yes	No
ACKNOWLEDGME	ENT AND ACCEPTANCE	RITING, WORK SUBMITTE OF OUR TERMS WHICH A LINQUISHER TO ENSURE	ARE AVAILABLE FOR	VIEWING AT WWW	V.BVNA.COM/EN √ II	RONMENTAL-LAB	ORATORIES/RE	ND CONDITION	C-TERMS-AND-CON	DITIONS.		CUMENT IS	SAMPLES	MUST BE KEPT CO UNTIL DELIVE	OL (< 10° C)	FROM TIME OF SAME	White: Bureau	Veritas Yell	low: Client
SAMPLE CONT	AINER, PRESERVATION	I, HOLD TIME AND PACKA	AGE INFORMATION C	AN BE VIEWED A	T WWW.BVNA.COM	/ENVIRONMENTA	L-LABORATOR		ES/CHAIN-CUSTODY		ogs.	- (1	-		- 1	1010	1-	7/73	



Your Project #: 161413217.778 Your C.O.C. #: 965717-01-01

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2023/12/11

Report #: R7950239 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BUREAU VERITAS JOB #: C3AV735 Received: 2023/12/05, 15:09

Sample Matrix: Water # Samples Received: 6

		Date	Date		
Analyses	Quantity	Extracted	Analyzed	Laboratory Method	Analytical Method
Alkalinity	6	N/A	2023/12/07	CAM SOP-00448	SM 24 2320 B m
Carbonate, Bicarbonate and Hydroxide	2	N/A	2023/12/07	CAM SOP-00102	APHA 4500-CO2 D
Carbonate, Bicarbonate and Hydroxide	4	N/A	2023/12/08	CAM SOP-00102	APHA 4500-CO2 D
Chloride by Automated Colourimetry	6	N/A	2023/12/07	CAM SOP-00463	SM 24 4500-Cl E m
Conductivity	6	N/A	2023/12/07	CAM SOP-00414	SM 24 2510 m
Dissolved Organic Carbon (DOC) (1)	6	N/A	2023/12/07	CAM SOP-00446	SM 24 5310 B m
Hardness (calculated as CaCO3)	6	N/A	2023/12/07	CAM SOP 00102/00408/00447	SM 2340 B
Dissolved Metals by ICPMS	6	N/A	2023/12/07	CAM SOP-00447	EPA 6020B m
Ion Balance (% Difference)	2	N/A	2023/12/07		
Ion Balance (% Difference)	4	N/A	2023/12/08		
Anion and Cation Sum	2	N/A	2023/12/07		
Anion and Cation Sum	4	N/A	2023/12/08		
Total Ammonia-N	6	N/A	2023/12/07	CAM SOP-00441	USGS I-2522-90 m
Nitrate & Nitrite as Nitrogen in Water (2)	6	N/A	2023/12/08	CAM SOP-00440	SM 24 4500-NO3I/NO2B
рН	6	2023/12/06	2023/12/07	CAM SOP-00413	SM 24th - 4500H+ B
Orthophosphate	6	N/A	2023/12/07	CAM SOP-00461	SM 24 4500-P E
Sat. pH and Langelier Index (@ 20C)	2	N/A	2023/12/07		Auto Calc
Sat. pH and Langelier Index (@ 20C)	4	N/A	2023/12/08		Auto Calc
Sat. pH and Langelier Index (@ 4C)	2	N/A	2023/12/07		Auto Calc
Sat. pH and Langelier Index (@ 4C)	4	N/A	2023/12/08		Auto Calc
Sulphate by Automated Turbidimetry	6	N/A	2023/12/07	CAM SOP-00464	SM 24 4500-SO42- E m
Total Dissolved Solids (TDS calc)	2	N/A	2023/12/07		Auto Calc
Total Dissolved Solids (TDS calc)	4	N/A	2023/12/08		Auto Calc

Remarks:

Bureau Veritas is accredited to ISO/IEC 17025 for specific parameters on scopes of accreditation. Unless otherwise noted, procedures used by Bureau Veritas are based upon recognized Provincial, Federal or US method compendia such as CCME, MELCCFP, EPA, APHA.

All work recorded herein has been done in accordance with procedures and practices ordinarily exercised by professionals in Bureau Veritas' profession using accepted testing methodologies, quality assurance and quality control procedures (except where otherwise agreed by the client and Bureau Veritas in



Your Project #: 161413217.778 Your C.O.C. #: 965717-01-01

Attention: Grant Whitehead

Stantec Consulting Ltd 300 Hagey Blvd Suite 100 Waterloo, ON CANADA N2L 0A4

Report Date: 2023/12/11

Report #: R7950239 Version: 1 - Final

CERTIFICATE OF ANALYSIS

BUREAU VERITAS JOB #: C3AV735

Received: 2023/12/05, 15:09

writing). All data is in statistical control and has met quality control and method performance criteria unless otherwise noted. All method blanks are reported; unless indicated otherwise, associated sample data are not blank corrected. Where applicable, unless otherwise noted, Measurement Uncertainty has not been accounted for when stating conformity to the referenced standard.

Bureau Veritas liability is limited to the actual cost of the requested analyses, unless otherwise agreed in writing. There is no other warranty expressed or implied. Bureau Veritas has been retained to provide analysis of samples provided by the Client using the testing methodology referenced in this report. Interpretation and use of test results are the sole responsibility of the Client and are not within the scope of services provided by Bureau Veritas, unless otherwise agreed in writing. Bureau Veritas is not responsible for the accuracy or any data impacts, that result from the information provided by the customer or their agent.

Solid sample results, except biota, are based on dry weight unless otherwise indicated. Organic analyses are not recovery corrected except for isotope dilution methods.

Results relate to samples tested. When sampling is not conducted by Bureau Veritas, results relate to the supplied samples tested.

This Certificate shall not be reproduced except in full, without the written approval of the laboratory.

Reference Method suffix "m" indicates test methods incorporate validated modifications from specific reference methods to improve performance.

- * RPDs calculated using raw data. The rounding of final results may result in the apparent difference.
- (1) Dissolved Organic Carbon (DOC) present in the sample should be considered as non-purgeable DOC.
- (2) Values for calculated parameters may not appear to add up due to rounding of raw data and significant figures.

Encryption Key

Please direct all questions regarding this Certificate of Analysis to: Julie Clement, Technical Account Manager Email: Julie.CLEMENT@bureauveritas.com Phone# (613)868-6079

This report has been generated and distributed using a secure automated process.

Bureau Veritas has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation, please refer to the Validation Signatures page if included, otherwise available by request. For Department specific Analyst/Supervisor validation names, please refer to the Test Summary section if included, otherwise available by request. This report is authorized by Rodney Major, General Manager responsible for Ontario Environmental laboratory operations.

Total Cover Pages : 2 Page 2 of 17



Client Project #: 161413217.778

Sampler Initials: AV

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		XUM766		XUM767	XUM768		
Sampling Date		2023/12/05		2023/12/05	2023/12/05		
Jamping Date		10:15		10:54	12:01		
COC Number		965717-01-01		965717-01-01	965717-01-01		
	UNITS	BH06-21	QC Batch	BH03-21	BH02-21	RDL	QC Batch
Calculated Parameters							
Anion Sum	me/L	7.08	9094273	8.83	7.08	N/A	9094273
Bicarb. Alkalinity (calc. as CaCO3)	mg/L	290	9094253	350	280	1.0	9094253
Calculated TDS	mg/L	370	9091491	470	380	1.0	9091491
Carb. Alkalinity (calc. as CaCO3)	mg/L	2.7	9094253	2.5	2.6	1.0	9094253
Cation Sum	me/L	7.19	9094273	9.07	7.19	N/A	9094273
Hardness (CaCO3)	mg/L	290	9091675	440	280	1.0	9091675
Ion Balance (% Difference)	%	0.780	9092884	1.36	0.730	N/A	9092884
Langelier Index (@ 20C)	N/A	0.758	9094252	1.04	0.769		9094252
Langelier Index (@ 4C)	N/A	0.509	9094254	0.794	0.521		9094254
Saturation pH (@ 20C)	N/A	7.23	9094252	6.84	7.21		9094252
Saturation pH (@ 4C)	N/A	7.48	9094254	7.09	7.46		9094254
Inorganics							
Total Ammonia-N	mg/L	<0.050	9097395	0.068	<0.050	0.050	9097395
Conductivity	umho/cm	660	9095908	800	660	1.0	9095934
Dissolved Organic Carbon	mg/L	0.95	9095162	1.2	0.58	0.40	9095162
Orthophosphate (P)	mg/L	<0.010	9095971	<0.010	<0.010	0.010	9095971
рН	рН	7.99	9095909	7.88	7.98		9095936
Dissolved Sulphate (SO4)	mg/L	55	9095976	73	59	1.0	9095976
Alkalinity (Total as CaCO3)	mg/L	290	9095906	360	290	1.0	9095914
Dissolved Chloride (Cl-)	mg/L	2.4	9095969	5.6	3.9	1.0	9095969
Nitrite (N)	mg/L	<0.010	9095978	<0.010	<0.010	0.010	9095978
Nitrate (N)	mg/L	<0.10	9095978	<0.10	0.39	0.10	9095978
Nitrate + Nitrite (N)	mg/L	<0.10	9095978	<0.10	0.39	0.10	9095978
Metals			•		•	•	•
Dissolved Aluminum (AI)	mg/L	0.0054	9096389	<0.0049	<0.0049	0.0049	9096389
Dissolved Antimony (Sb)	mg/L	<0.00050	9096389	<0.00050	<0.00050	0.00050	9096389
Dissolved Arsenic (As)	mg/L	<0.0010	9096389	0.0015	<0.0010	0.0010	9096389
Dissolved Barium (Ba)	mg/L	0.11	9096389	0.098	0.11	0.0020	9096389
Dissolved Beryllium (Be)	mg/L	<0.00040	9096389	<0.00040	<0.00040	0.00040	9096389
Dissolved Boron (B)	mg/L	0.12	9096389	0.012	0.10	0.010	9096389
Dissolved Cadmium (Cd)	mg/L	<0.000090	9096389	<0.000090	<0.000090	0.000090	9096389
RDL = Reportable Detection Limit					<u> </u>		

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

N/A = Not Applicable



Sampler Initials: AV

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		XUM766		XUM767	XUM768		
Sampling Date		2023/12/05		2023/12/05	2023/12/05		
Sampling Date		10:15		10:54	12:01		
COC Number		965717-01-01		965717-01-01	965717-01-01		
	UNITS	BH06-21	QC Batch	BH03-21	BH02-21	RDL	QC Batch
Dissolved Calcium (Ca)	mg/L	55	9096389	120	59	0.20	9096389
Dissolved Chromium (Cr)	mg/L	<0.0050	9096389	<0.0050	<0.0050	0.0050	9096389
Dissolved Cobalt (Co)	mg/L	<0.00050	9096389	<0.00050	<0.00050	0.00050	9096389
Dissolved Copper (Cu)	mg/L	<0.00090	9096389	<0.00090	<0.00090	0.00090	9096389
Dissolved Iron (Fe)	mg/L	<0.10	9096389	0.45	<0.10	0.10	9096389
Dissolved Lead (Pb)	mg/L	<0.00050	9096389	<0.00050	<0.00050	0.00050	9096389
Dissolved Magnesium (Mg)	mg/L	37	9096389	35	33	0.050	9096389
Dissolved Manganese (Mn)	mg/L	0.018	9096389	0.040	0.0053	0.0020	9096389
Dissolved Molybdenum (Mo)	mg/L	0.0059	9096389	0.00092	0.0076	0.00050	9096389
Dissolved Nickel (Ni)	mg/L	<0.0010	9096389	<0.0010	<0.0010	0.0010	9096389
Dissolved Phosphorus (P)	mg/L	<0.10	9096389	<0.10	<0.10	0.10	9096389
Dissolved Potassium (K)	mg/L	2.1	9096389	1.2	2.1	0.20	9096389
Dissolved Selenium (Se)	mg/L	<0.0020	9096389	<0.0020	<0.0020	0.0020	9096389
Dissolved Silicon (Si)	mg/L	6.5	9096389	8.3	6.4	0.050	9096389
Dissolved Silver (Ag)	mg/L	<0.000090	9096389	<0.000090	<0.000090	0.000090	9096389
Dissolved Sodium (Na)	mg/L	31	9096389	5.0	34	0.10	9096389
Dissolved Strontium (Sr)	mg/L	1.5	9096389	0.34	1.1	0.0010	9096389
Dissolved Thallium (TI)	mg/L	<0.000050	9096389	<0.000050	<0.000050	0.000050	9096389
Dissolved Titanium (Ti)	mg/L	<0.0050	9096389	<0.0050	<0.0050	0.0050	9096389
Dissolved Uranium (U)	mg/L	0.0031	9096389	0.00053	0.0029	0.00010	9096389
Dissolved Vanadium (V)	mg/L	0.00098	9096389	<0.00050	0.00083	0.00050	9096389
Dissolved Zinc (Zn)	mg/L	<0.0050	9096389	<0.0050	<0.0050	0.0050	9096389
RDL = Reportable Detection Limit						•	

RDL = Reportable Detection Limit QC Batch = Quality Control Batch



Client Project #: 161413217.778

Sampler Initials: AV

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		XUM768			XUM769	XUM770		
Sampling Date		2023/12/05 12:01			2023/12/05 12:46	2023/12/05 13:25		
COC Number		965717-01-01			965717-01-01	965717-01-01		
	UNITS	BH02-21 Lab-Dup	RDL	QC Batch	BH05-21	BH04-21	RDL	QC Batch
Calculated Parameters								
Anion Sum	me/L				8.11	5.03	N/A	9094273
Bicarb. Alkalinity (calc. as CaCO3)	mg/L				300	200	1.0	9094253
Calculated TDS	mg/L				440	300	1.0	9091491
Carb. Alkalinity (calc. as CaCO3)	mg/L				2.4	1.7	1.0	9094253
Cation Sum	me/L				8.19	6.10	N/A	9094273
Hardness (CaCO3)	mg/L				380	220	1.0	9091675
Ion Balance (% Difference)	%				0.500	9.59	N/A	9092884
Langelier Index (@ 20C)	N/A				0.886	0.580		9094252
Langelier Index (@ 4C)	N/A				0.637	0.331		9094254
Saturation pH (@ 20C)	N/A				7.03	7.39		9094252
Saturation pH (@ 4C)	N/A				7.28	7.64		9094254
Inorganics								
Total Ammonia-N	mg/L	0.081	0.050	9097395	0.10	0.15	0.050	9097395
Conductivity	umho/cm				750	500	1.0	9095934
Dissolved Organic Carbon	mg/L				1.3	1.5	0.40	9095162
Orthophosphate (P)	mg/L				<0.010	<0.010	0.010	9095971
рН	рН				7.91	7.97		9095936
Dissolved Sulphate (SO4)	mg/L				80	38	1.0	9095976
Alkalinity (Total as CaCO3)	mg/L				310	200	1.0	9095914
Dissolved Chloride (Cl-)	mg/L				12	11	1.0	9095969
Nitrite (N)	mg/L				<0.010	<0.010	0.010	9095978
Nitrate (N)	mg/L				<0.10	<0.10	0.10	9095978
Nitrate + Nitrite (N)	mg/L				<0.10	<0.10	0.10	9095978
Metals	•	•	•	•			•	•
Dissolved Aluminum (AI)	mg/L				<0.0049	0.44	0.0049	9096389
Dissolved Antimony (Sb)	mg/L				<0.00050	<0.00050	0.00050	9096389
Dissolved Arsenic (As)	mg/L				0.0014	0.0011	0.0010	9096389
Dissolved Barium (Ba)	mg/L				0.11	0.064	0.0020	9096389
Dissolved Beryllium (Be)	mg/L				<0.00040	<0.00040	0.00040	9096389
Dissolved Boron (B)	mg/L				0.016	0.14	0.010	9096389

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Client Project #: 161413217.778

Sampler Initials: AV

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		XUM768			XUM769	XUM770		
Sampling Date		2023/12/05			2023/12/05	2023/12/05		
Sampling Date		12:01			12:46	13:25		
COC Number		965717-01-01			965717-01-01	965717-01-01		
	UNITS	BH02-21 Lab-Dup	RDL	QC Batch	BH05-21	BH04-21	RDL	QC Batch
Dissolved Cadmium (Cd)	mg/L				<0.000090	<0.000090	0.000090	9096389
Dissolved Calcium (Ca)	mg/L				87	54	0.20	9096389
Dissolved Chromium (Cr)	mg/L				<0.0050	<0.0050	0.0050	9096389
Dissolved Cobalt (Co)	mg/L				<0.00050	<0.00050	0.00050	9096389
Dissolved Copper (Cu)	mg/L				<0.00090	0.0022	0.00090	9096389
Dissolved Iron (Fe)	mg/L				<0.10	0.49	0.10	9096389
Dissolved Lead (Pb)	mg/L				<0.00050	0.00065	0.00050	9096389
Dissolved Magnesium (Mg)	mg/L				39	21	0.050	9096389
Dissolved Manganese (Mn)	mg/L				0.050	0.085	0.0020	9096389
Dissolved Molybdenum (Mo)	mg/L				0.0021	0.0074	0.00050	9096389
Dissolved Nickel (Ni)	mg/L				<0.0010	0.0014	0.0010	9096389
Dissolved Phosphorus (P)	mg/L				<0.10	<0.10	0.10	9096389
Dissolved Potassium (K)	mg/L				1.5	1.4	0.20	9096389
Dissolved Selenium (Se)	mg/L				<0.0020	<0.0020	0.0020	9096389
Dissolved Silicon (Si)	mg/L				8.4	6.8	0.050	9096389
Dissolved Silver (Ag)	mg/L				<0.000090	<0.000090	0.000090	9096389
Dissolved Sodium (Na)	mg/L				14	36	0.10	9096389
Dissolved Strontium (Sr)	mg/L				0.30	0.66	0.0010	9096389
Dissolved Thallium (TI)	mg/L				<0.000050	<0.000050	0.000050	9096389
Dissolved Titanium (Ti)	mg/L				<0.0050	0.018	0.0050	9096389
Dissolved Uranium (U)	mg/L				0.0021	0.0016	0.00010	9096389
Dissolved Vanadium (V)	mg/L				<0.00050	0.0016	0.00050	9096389
Dissolved Zinc (Zn)	mg/L				<0.0050	<0.0050	0.0050	9096389

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate



Client Project #: 161413217.778

Sampler Initials: AV

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		XUM770			XUM771		
Sampling Date		2023/12/05 13:25			2023/12/05 14:01		
COC Number		965717-01-01			965717-01-01		
	UNITS	BH04-21 Lab-Dup	RDL	QC Batch	BH01-21	RDL	QC Batch
Calculated Parameters			•	<u> </u>		·	·
Anion Sum	me/L				9.57	N/A	9094273
Bicarb. Alkalinity (calc. as CaCO3)	mg/L				300	1.0	9094253
Calculated TDS	mg/L				520	1.0	9091491
Carb. Alkalinity (calc. as CaCO3)	mg/L				2.1	1.0	9094253
Cation Sum	me/L				9.90	N/A	9094273
Hardness (CaCO3)	mg/L				370	1.0	9094285
Ion Balance (% Difference)	%				1.71	N/A	9092884
Langelier Index (@ 20C)	N/A				0.784		9094252
Langelier Index (@ 4C)	N/A				0.536		9094254
Saturation pH (@ 20C)	N/A				7.09		9094252
Saturation pH (@ 4C)	N/A				7.34		9094254
Inorganics						•	•
Total Ammonia-N	mg/L				0.11	0.050	9097395
Conductivity	umho/cm	500	1.0	9095934	970	1.0	9095908
Dissolved Organic Carbon	mg/L				1.2	0.40	9095162
Orthophosphate (P)	mg/L				<0.010	0.010	9095971
рН	рН	8.04		9095936	7.88		9095909
Dissolved Sulphate (SO4)	mg/L				43	1.0	9095976
Alkalinity (Total as CaCO3)	mg/L	200	1.0	9095914	300	1.0	9095906
Dissolved Chloride (Cl-)	mg/L				92	1.0	9095969
Nitrite (N)	mg/L	<0.010	0.010	9095978	<0.010	0.010	9095978
Nitrate (N)	mg/L	<0.10	0.10	9095978	<0.10	0.10	9095978
Nitrate + Nitrite (N)	mg/L	<0.10	0.10	9095978	<0.10	0.10	9095978
Metals	•		•	•		•	•
Dissolved Aluminum (Al)	mg/L				<0.0049	0.0049	9096389
Dissolved Antimony (Sb)	mg/L				<0.00050	0.00050	9096389
Dissolved Arsenic (As)	mg/L				0.0020	0.0010	9096389
Dissolved Barium (Ba)	mg/L				0.13	0.0020	9096389
Dissolved Beryllium (Be)	mg/L				<0.00040	0.00040	9096389
Dissolved Boron (B)	mg/L				0.060	0.010	9096389
PDI - Papartable Detection Limit	•		•				

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate

N/A = Not Applicable



Client Project #: 161413217.778

Sampler Initials: AV

RCAP - COMPREHENSIVE (WATER)

Bureau Veritas ID		XUM770			XUM771		
Sampling Date		2023/12/05 13:25			2023/12/05 14:01		
COC Number		965717-01-01			965717-01-01		
	UNITS	BH04-21 Lab-Dup	RDL	QC Batch	BH01-21	RDL	QC Batch
Dissolved Cadmium (Cd)	mg/L				<0.000090	0.000090	9096389
Dissolved Calcium (Ca)	mg/L				78	0.20	9096389
Dissolved Chromium (Cr)	mg/L				<0.0050	0.0050	9096389
Dissolved Cobalt (Co)	mg/L				<0.00050	0.00050	9096389
Dissolved Copper (Cu)	mg/L				<0.00090	0.00090	9096389
Dissolved Iron (Fe)	mg/L				<0.10	0.10	9096389
Dissolved Lead (Pb)	mg/L				<0.00050	0.00050	9096389
Dissolved Magnesium (Mg)	mg/L				41	0.050	9096389
Dissolved Manganese (Mn)	mg/L				0.044	0.0020	9096389
Dissolved Molybdenum (Mo)	mg/L				0.0046	0.00050	9096389
Dissolved Nickel (Ni)	mg/L				<0.0010	0.0010	9096389
Dissolved Phosphorus (P)	mg/L				<0.10	0.10	9096389
Dissolved Potassium (K)	mg/L				2.4	0.20	9096389
Dissolved Selenium (Se)	mg/L				<0.0020	0.0020	9096389
Dissolved Silicon (Si)	mg/L				8.0	0.050	9096389
Dissolved Silver (Ag)	mg/L				<0.000090	0.000090	9096389
Dissolved Sodium (Na)	mg/L				58	0.10	9096389
Dissolved Strontium (Sr)	mg/L				1.1	0.0010	9096389
Dissolved Thallium (TI)	mg/L				<0.000050	0.000050	9096389
Dissolved Titanium (Ti)	mg/L				<0.0050	0.0050	9096389
Dissolved Uranium (U)	mg/L				0.0028	0.00010	9096389
Dissolved Vanadium (V)	mg/L				<0.00050	0.00050	9096389
Dissolved Zinc (Zn)	mg/L				<0.0050	0.0050	9096389

RDL = Reportable Detection Limit

QC Batch = Quality Control Batch

Lab-Dup = Laboratory Initiated Duplicate



Report Date: 2023/12/11

Stantec Consulting Ltd

Client Project #: 161413217.778

Sampler Initials: AV

TEST SUMMARY

Bureau Veritas ID: XUM766 **Collected:** 2023/12/05 Sample ID: BH06-21

Shipped:

Matrix: Water **Received:** 2023/12/05

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	9095906	N/A	2023/12/07	Nachiketa Gohil
Carbonate, Bicarbonate and Hydroxide	CALC	9094253	N/A	2023/12/07	Automated Statchk
Chloride by Automated Colourimetry	SKAL	9095969	N/A	2023/12/07	Massarat Jan
Conductivity	AT	9095908	N/A	2023/12/07	Nachiketa Gohil
Dissolved Organic Carbon (DOC)	TOCV/NDIR	9095162	N/A	2023/12/07	Gyulshen Idriz
Hardness (calculated as CaCO3)		9091675	N/A	2023/12/07	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	9096389	N/A	2023/12/07	Arefa Dabhad
Ion Balance (% Difference)	CALC	9092884	N/A	2023/12/07	Automated Statchk
Anion and Cation Sum	CALC	9094273	N/A	2023/12/07	Automated Statchk
Total Ammonia-N	LACH/NH4	9097395	N/A	2023/12/07	Shivani Shivani
Nitrate & Nitrite as Nitrogen in Water	LACH	9095978	N/A	2023/12/08	Chandra Nandlal
рН	AT	9095909	2023/12/06	2023/12/07	Nachiketa Gohil
Orthophosphate	KONE	9095971	N/A	2023/12/07	Massarat Jan
Sat. pH and Langelier Index (@ 20C)	CALC	9094252	N/A	2023/12/07	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	9094254	N/A	2023/12/07	Automated Statchk
Sulphate by Automated Turbidimetry	SKAL	9095976	N/A	2023/12/07	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	9091491	N/A	2023/12/07	Automated Statchk

Bureau Veritas ID: XUM767 Sample ID: BH03-21 Matrix: Water **Collected:** 2023/12/05

Shipped:

Received: 2023/12/05

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	9095914	N/A	2023/12/07	Nachiketa Gohil
Carbonate, Bicarbonate and Hydroxide	CALC	9094253	N/A	2023/12/08	Automated Statchk
Chloride by Automated Colourimetry	SKAL	9095969	N/A	2023/12/07	Massarat Jan
Conductivity	AT	9095934	N/A	2023/12/07	Nachiketa Gohil
Dissolved Organic Carbon (DOC)	TOCV/NDIR	9095162	N/A	2023/12/07	Gyulshen Idriz
Hardness (calculated as CaCO3)		9091675	N/A	2023/12/07	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	9096389	N/A	2023/12/07	Arefa Dabhad
Ion Balance (% Difference)	CALC	9092884	N/A	2023/12/08	Automated Statchk
Anion and Cation Sum	CALC	9094273	N/A	2023/12/08	Automated Statchk
Total Ammonia-N	LACH/NH4	9097395	N/A	2023/12/07	Shivani Shivani
Nitrate & Nitrite as Nitrogen in Water	LACH	9095978	N/A	2023/12/08	Chandra Nandlal
рН	AT	9095936	2023/12/06	2023/12/07	Nachiketa Gohil
Orthophosphate	KONE	9095971	N/A	2023/12/07	Massarat Jan
Sat. pH and Langelier Index (@ 20C)	CALC	9094252	N/A	2023/12/08	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	9094254	N/A	2023/12/08	Automated Statchk
Sulphate by Automated Turbidimetry	SKAL	9095976	N/A	2023/12/07	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	9091491	N/A	2023/12/08	Automated Statchk



Client Project #: 161413217.778

Sampler Initials: AV

TEST SUMMARY

Bureau Veritas ID: XUM768

Collected: 2023/12/05 Shipped:

Sample ID: BH02-21 Matrix: Water

Received: 2023/12/05

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	9095914	N/A	2023/12/07	Nachiketa Gohil
Carbonate, Bicarbonate and Hydroxide	CALC	9094253	N/A	2023/12/08	Automated Statchk
Chloride by Automated Colourimetry	SKAL	9095969	N/A	2023/12/07	Massarat Jan
Conductivity	AT	9095934	N/A	2023/12/07	Nachiketa Gohil
Dissolved Organic Carbon (DOC)	TOCV/NDIR	9095162	N/A	2023/12/07	Gyulshen Idriz
Hardness (calculated as CaCO3)		9091675	N/A	2023/12/07	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	9096389	N/A	2023/12/07	Arefa Dabhad
Ion Balance (% Difference)	CALC	9092884	N/A	2023/12/08	Automated Statchk
Anion and Cation Sum	CALC	9094273	N/A	2023/12/08	Automated Statchk
Total Ammonia-N	LACH/NH4	9097395	N/A	2023/12/07	Shivani Shivani
Nitrate & Nitrite as Nitrogen in Water	LACH	9095978	N/A	2023/12/08	Chandra Nandlal
рН	AT	9095936	2023/12/06	2023/12/07	Nachiketa Gohil
Orthophosphate	KONE	9095971	N/A	2023/12/07	Massarat Jan
Sat. pH and Langelier Index (@ 20C)	CALC	9094252	N/A	2023/12/08	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	9094254	N/A	2023/12/08	Automated Statchk
Sulphate by Automated Turbidimetry	SKAL	9095976	N/A	2023/12/07	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	9091491	N/A	2023/12/08	Automated Statchk

Bureau Veritas ID: XUM768 Dup Sample ID: BH02-21 Matrix: Water

Collected: 2023/12/05

Shipped:

Received: 2023/12/05

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Total Ammonia-N	LACH/NH4	9097395	N/A	2023/12/07	Shivani Shivani

Bureau Veritas ID: XUM769

Shipped:

Collected: 2023/12/05

Sample ID: BH05-21 Matrix: Water

Received: 2023/12/05

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	9095914	N/A	2023/12/07	Nachiketa Gohil
Carbonate, Bicarbonate and Hydroxide	CALC	9094253	N/A	2023/12/08	Automated Statchk
Chloride by Automated Colourimetry	SKAL	9095969	N/A	2023/12/07	Massarat Jan
Conductivity	AT	9095934	N/A	2023/12/07	Nachiketa Gohil
Dissolved Organic Carbon (DOC)	TOCV/NDIR	9095162	N/A	2023/12/07	Gyulshen Idriz
Hardness (calculated as CaCO3)		9091675	N/A	2023/12/07	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	9096389	N/A	2023/12/07	Arefa Dabhad
Ion Balance (% Difference)	CALC	9092884	N/A	2023/12/08	Automated Statchk
Anion and Cation Sum	CALC	9094273	N/A	2023/12/08	Automated Statchk
Total Ammonia-N	LACH/NH4	9097395	N/A	2023/12/07	Shivani Shivani
Nitrate & Nitrite as Nitrogen in Water	LACH	9095978	N/A	2023/12/08	Chandra Nandlal
рН	AT	9095936	2023/12/06	2023/12/07	Nachiketa Gohil
Orthophosphate	KONE	9095971	N/A	2023/12/07	Massarat Jan
Sat. pH and Langelier Index (@ 20C)	CALC	9094252	N/A	2023/12/08	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	9094254	N/A	2023/12/08	Automated Statchk



Report Date: 2023/12/11

Stantec Consulting Ltd

Client Project #: 161413217.778

Sampler Initials: AV

TEST SUMMARY

Bureau Veritas ID: XUM769 Sample ID: BH05-21

Collected: 2023/12/05 Shipped:

Matrix: Water

Received: 2023/12/05

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Sulphate by Automated Turbidimetry	SKAL	9095976	N/A	2023/12/07	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	9091491	N/A	2023/12/08	Automated Statchk

Bureau Veritas ID: XUM770

Collected: 2023/12/05

Sample ID: BH04-21 Matrix: Water

Shipped:

Received: 2023/12/05

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	9095914	N/A	2023/12/07	Nachiketa Gohil
Carbonate, Bicarbonate and Hydroxide	CALC	9094253	N/A	2023/12/08	Automated Statchk
Chloride by Automated Colourimetry	SKAL	9095969	N/A	2023/12/07	Massarat Jan
Conductivity	AT	9095934	N/A	2023/12/07	Nachiketa Gohil
Dissolved Organic Carbon (DOC)	TOCV/NDIR	9095162	N/A	2023/12/07	Gyulshen Idriz
Hardness (calculated as CaCO3)		9091675	N/A	2023/12/07	Automated Statchk
Dissolved Metals by ICPMS	ICP/MS	9096389	N/A	2023/12/07	Arefa Dabhad
Ion Balance (% Difference)	CALC	9092884	N/A	2023/12/08	Automated Statchk
Anion and Cation Sum	CALC	9094273	N/A	2023/12/08	Automated Statchk
Total Ammonia-N	LACH/NH4	9097395	N/A	2023/12/07	Shivani Shivani
Nitrate & Nitrite as Nitrogen in Water	LACH	9095978	N/A	2023/12/08	Chandra Nandlal
рН	AT	9095936	2023/12/06	2023/12/07	Nachiketa Gohil
Orthophosphate	KONE	9095971	N/A	2023/12/07	Massarat Jan
Sat. pH and Langelier Index (@ 20C)	CALC	9094252	N/A	2023/12/08	Automated Statchk
Sat. pH and Langelier Index (@ 4C)	CALC	9094254	N/A	2023/12/08	Automated Statchk
Sulphate by Automated Turbidimetry	SKAL	9095976	N/A	2023/12/07	Massarat Jan
Total Dissolved Solids (TDS calc)	CALC	9091491	N/A	2023/12/08	Automated Statchk

Bureau Veritas ID: XUM770 Dup

Sample ID: BH04-21

Matrix: Water Collected: 2023/12/05

Shipped:

Received: 2023/12/05

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	9095914	N/A	2023/12/07	Nachiketa Gohil
Conductivity	AT	9095934	N/A	2023/12/07	Nachiketa Gohil
Nitrate & Nitrite as Nitrogen in Water	LACH	9095978	N/A	2023/12/08	Chandra Nandlal
nH	AT	9095936	2023/12/06	2023/12/07	Nachiketa Gohil

Bureau Veritas ID: XUM771

Collected: 2023/12/05 Shipped:

Sample ID: BH01-21 Matrix: Water

Received: 2023/12/05

Test Description	Instrumentation	Batch	Extracted	Date Analyzed	Analyst
Alkalinity	AT	9095906	N/A	2023/12/07	Nachiketa Gohil
Carbonate, Bicarbonate and Hydroxide	CALC	9094253	N/A	2023/12/07	Automated Statchk
Chloride by Automated Colourimetry	SKAL	9095969	N/A	2023/12/07	Massarat Jan
Conductivity	AT	9095908	N/A	2023/12/07	Nachiketa Gohil



Matrix: Water

Stantec Consulting Ltd Report Date: 2023/12/11 Client Project #: 161413217.778

Sampler Initials: AV

TEST SUMMARY

Bureau Veritas ID: XUM771 Collected: 2023/12/05 Sample ID: BH01-21

Shipped:

Received: 2023/12/05

Test Description Instrumentation **Extracted Date Analyzed** Batch Analyst Dissolved Organic Carbon (DOC) TOCV/NDIR 9095162 N/A 2023/12/07 Gyulshen Idriz Hardness (calculated as CaCO3) 2023/12/07 9094285 N/A **Automated Statchk** Dissolved Metals by ICPMS ICP/MS 9096389 N/A 2023/12/07 Arefa Dabhad 2023/12/07 Ion Balance (% Difference) CALC 9092884 N/A **Automated Statchk** Anion and Cation Sum CALC 9094273 N/A 2023/12/07 **Automated Statchk** Total Ammonia-N LACH/NH4 9097395 N/A 2023/12/07 Shivani Shivani Nitrate & Nitrite as Nitrogen in Water LACH 9095978 N/A 2023/12/08 Chandra Nandlal рΗ ΑТ 9095909 2023/12/06 2023/12/07 Nachiketa Gohil KONE N/A Orthophosphate 9095971 2023/12/07 Massarat Jan Sat. pH and Langelier Index (@ 20C) CALC 9094252 N/A 2023/12/07 Automated Statchk Sat. pH and Langelier Index (@ 4C) CALC 9094254 N/A **Automated Statchk** 2023/12/07 N/A Sulphate by Automated Turbidimetry SKAL 9095976 2023/12/07 Massarat Jan Total Dissolved Solids (TDS calc) CALC 9091491 N/A 2023/12/07 **Automated Statchk**



Client Project #: 161413217.778

Sampler Initials: AV

GENERAL COMMENTS

Each te	emperature is the	average of up to	three cooler temperatures taken at receipt
	Package 1	6.7°C	
		•	
Result	s relate only to th	e items tested.	



QUALITY ASSURANCE REPORT

Stantec Consulting Ltd

Client Project #: 161413217.778

Sampler Initials: AV

			Matrix	Spike	SPIKED	BLANK	Method Blank		RPD	
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
9095162	Dissolved Organic Carbon	2023/12/06	92	80 - 120	96	80 - 120	<0.40	mg/L	1.0	20
9095906	Alkalinity (Total as CaCO3)	2023/12/07			98	85 - 115	<1.0	mg/L	1.0	20
9095908	Conductivity	2023/12/07			103	85 - 115	<1.0	umho/cm	0.40	10
9095909	рН	2023/12/07			101	98 - 103			0.16	N/A
9095914	Alkalinity (Total as CaCO3)	2023/12/07			99	85 - 115	<1.0	mg/L	2.1	20
9095934	Conductivity	2023/12/07			103	85 - 115	<1.0	umho/cm	0.60	10
9095936	рН	2023/12/07			101	98 - 103			0.87	N/A
9095969	Dissolved Chloride (Cl-)	2023/12/07	NC	80 - 120	102	80 - 120	<1.0	mg/L	0.42	20
9095971	Orthophosphate (P)	2023/12/07	96	75 - 125	94	80 - 120	<0.010	mg/L	NC	20
9095976	Dissolved Sulphate (SO4)	2023/12/07	NC	75 - 125	94	80 - 120	<1.0	mg/L	2.1	20
9095978	Nitrate (N)	2023/12/08	98	80 - 120	102	80 - 120	<0.10	mg/L	NC	20
9095978	Nitrite (N)	2023/12/08	105	80 - 120	107	80 - 120	<0.010	mg/L	NC	20
9096389	Dissolved Aluminum (AI)	2023/12/07	101	80 - 120	99	80 - 120	<0.0049	mg/L		
9096389	Dissolved Antimony (Sb)	2023/12/07	105	80 - 120	104	80 - 120	<0.00050	mg/L	NC	20
9096389	Dissolved Arsenic (As)	2023/12/07	99	80 - 120	99	80 - 120	<0.0010	mg/L	NC	20
9096389	Dissolved Barium (Ba)	2023/12/07	96	80 - 120	96	80 - 120	<0.0020	mg/L	1.3	20
9096389	Dissolved Beryllium (Be)	2023/12/07	100	80 - 120	97	80 - 120	<0.00040	mg/L	NC	20
9096389	Dissolved Boron (B)	2023/12/07	100	80 - 120	97	80 - 120	<0.010	mg/L	5.8	20
9096389	Dissolved Cadmium (Cd)	2023/12/07	104	80 - 120	99	80 - 120	<0.000090	mg/L	NC	20
9096389	Dissolved Calcium (Ca)	2023/12/07	NC	80 - 120	100	80 - 120	<0.20	mg/L		
9096389	Dissolved Chromium (Cr)	2023/12/07	91	80 - 120	95	80 - 120	<0.0050	mg/L	NC	20
9096389	Dissolved Cobalt (Co)	2023/12/07	94	80 - 120	99	80 - 120	<0.00050	mg/L	NC	20
9096389	Dissolved Copper (Cu)	2023/12/07	98	80 - 120	95	80 - 120	<0.00090	mg/L	NC	20
9096389	Dissolved Iron (Fe)	2023/12/07	NC	80 - 120	99	80 - 120	<0.10	mg/L		
9096389	Dissolved Lead (Pb)	2023/12/07	95	80 - 120	96	80 - 120	<0.00050	mg/L	NC	20
9096389	Dissolved Magnesium (Mg)	2023/12/07	93	80 - 120	98	80 - 120	<0.050	mg/L		
9096389	Dissolved Manganese (Mn)	2023/12/07	NC	80 - 120	97	80 - 120	<0.0020	mg/L		
9096389	Dissolved Molybdenum (Mo)	2023/12/07	99	80 - 120	93	80 - 120	<0.00050	mg/L	NC	20
9096389	Dissolved Nickel (Ni)	2023/12/07	95	80 - 120	96	80 - 120	<0.0010	mg/L	NC	20
9096389	Dissolved Phosphorus (P)	2023/12/07	106	80 - 120	102	80 - 120	<0.10	mg/L		
9096389	Dissolved Potassium (K)	2023/12/07	102	80 - 120	101	80 - 120	<0.20	mg/L		



QUALITY ASSURANCE REPORT(CONT'D)

Stantec Consulting Ltd

Client Project #: 161413217.778

Sampler Initials: AV

			Matrix	Spike	SPIKED	BLANK	Method B	lank	RP	D
QC Batch	Parameter	Date	% Recovery	QC Limits	% Recovery	QC Limits	Value	UNITS	Value (%)	QC Limits
9096389	Dissolved Selenium (Se)	2023/12/07	99	80 - 120	98	80 - 120	<0.0020	mg/L	NC	20
9096389	Dissolved Silicon (Si)	2023/12/07	100	80 - 120	99	80 - 120	<0.050	mg/L		
9096389	Dissolved Silver (Ag)	2023/12/07	85	80 - 120	95	80 - 120	<0.000090	mg/L	NC	20
9096389	Dissolved Sodium (Na)	2023/12/07	96	80 - 120	97	80 - 120	<0.10	mg/L	3.2	20
9096389	Dissolved Strontium (Sr)	2023/12/07	NC	80 - 120	98	80 - 120	<0.0010	mg/L		
9096389	Dissolved Thallium (TI)	2023/12/07	101	80 - 120	102	80 - 120	<0.000050	mg/L	NC	20
9096389	Dissolved Titanium (Ti)	2023/12/07	103	80 - 120	97	80 - 120	<0.0050	mg/L		
9096389	Dissolved Uranium (U)	2023/12/07	101	80 - 120	100	80 - 120	<0.00010	mg/L	NC	20
9096389	Dissolved Vanadium (V)	2023/12/07	94	80 - 120	97	80 - 120	<0.00050	mg/L	NC	20
9096389	Dissolved Zinc (Zn)	2023/12/07	98	80 - 120	98	80 - 120	<0.0050	mg/L	NC	20
9097395	Total Ammonia-N	2023/12/07	101	75 - 125	98	80 - 120	<0.050	mg/L	NC	20

N/A = Not Applicable

Duplicate: Paired analysis of a separate portion of the same sample. Used to evaluate the variance in the measurement.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate sample matrix interference.

Spiked Blank: A blank matrix sample to which a known amount of the analyte, usually from a second source, has been added. Used to evaluate method accuracy.

Method Blank: A blank matrix containing all reagents used in the analytical procedure. Used to identify laboratory contamination.

NC (Matrix Spike): The recovery in the matrix spike was not calculated. The relative difference between the concentration in the parent sample and the spike amount was too small to permit a reliable recovery calculation (matrix spike concentration was less than the native sample concentration)

NC (Duplicate RPD): The duplicate RPD was not calculated. The concentration in the sample and/or duplicate was too low to permit a reliable RPD calculation (absolute difference <= 2x RDL).



Client Project #: 161413217.778

Sampler Initials: AV

VALIDATION SIGNATURE PAGE

The analytical data and all QC contained in this report were reviewed and validated by:

Anastassia Hamanov, Scientific Specialist

Bureau Veritas has procedures in place to guard against improper use of the electronic signature and have the required "signatories", as per ISO/IEC 17025, signing the reports. For Service Group specific validation, please refer to the Validation Signatures page if included, otherwise available by request. For Department specific Analyst/Supervisor validation names, please refer to the Test Summary section if included, otherwise available by request. This report is authorized by Rodney Major, General Manager responsible for Ontario Environmental laboratory operations.

#9197 Stantec Consulting Ltd Company Name	BUREAU VERITAS	INVOICE TO:			REPO	ORT TO:	-			PROJEC	CT INFORMATION:	Ē		<u> </u>	
Accounts Payable	pany Name: #9197 Stante		Co	ompany Name				0	Quotation #	C310	67				Bottle Order
Waterion ON NZL DAA (519) 579-4610 SAPInvoices@Stantec.com Super Supe	Accounts Paya		-	-	nt Whitehead							110	NT-2023-12	-155	
(519) 579-433 Tel. (519) 579-6733 Tel. (Ac	ddress:				P	Project:	1614	13217.778				965717 Project Mana
SAPINVICES (Stantec.com Email: grant.whitehead@stantec.com ED) @ \$40x4ec.\$\text{Composition} by \text{AVAIDENHORE} \text{Composition} by Composition	The state of the s		9-6733	(519) 585-7400	Fav	(519) 57	70 4220		-			THE		
Submitted on the Bureau veritas delivery of the Regulations Regulation 152 (2011) Other Regulations Special Instructions				mail: gran	t.whitehead@s	tantec.com	EDDE	stanteccos	Sampled By:	A-V	ANDENH	OFF			Julie Clemi
Regulation 153 (2011)	MOE REGULATED DRINK	ING WATER OR WATER INTE	NDED FOR HUM	AN CONSUMPTION	ON MUST BE			ANAL*	YSIS REQUEST	TED (PLEASE	BE SPECIFIC)				
RestPark MediumFine COME Standard Tax For Noting days from the tests.		The second secon				 (<u>e</u>)		1.15				J 1 6		Standard) TAT:	
Sample Barcode Label Sample (Location) Identification Date Sampled Time Sampled Matrix Sample Barcode Label Sample (Location) Identification Date Sampled Time Sampled Matrix Sample Matri				эресі	ii instructions	Z Se cin							100		
Sample Barcode Label Sample (Location) Identification Date Sampled Time Sampled Matrix Sampled (Location) Identification Date Sampled Time Sampled Matrix Sampled (Location) Identification Date Sampled Time Sampled Time Sampled Date Sampled (Location) Identification Date Sampled Time Sampled Date Sampled (Location) Identification Date Sampled Date Sampled Date Sampled Date Sampled (Location) Identification Date Sampled						pleas g / C	sive					116	Please note	Standard TAT for certain tests such as B	OD and Dioxins/Furant
Sample Barcode Label Sample (Location) Identification Date Sampled Time Sampled Matrix Sampled (Location) Identification Date Sampled Time Sampled Matrix Sampled (Location) Identification Date Sampled Time Sampled Time Sampled Date Sampled (Location) Identification Date Sampled Time Sampled Date Sampled (Location) Identification Date Sampled Date Sampled Date Sampled Date Sampled (Location) Identification Date Sampled		PWQ0 Reg	406 Table			bared (rehen								nission)
Sample Barcode Label Sample (Location) Identification Date Sampled Time Sampled Matrix Sampled (Location) Identification Date Sampled Time Sampled Matrix Sampled (Location) Identification Date Sampled Time Sampled Time Sampled Date Sampled (Location) Identification Date Sampled Time Sampled Date Sampled (Location) Identification Date Sampled Date Sampled Date Sampled Date Sampled (Location) Identification Date Sampled		Other ODWS -	-Not pota	He		Meta Meta	Сошр					1919	STATE OF THE PARTY		ne Required:
BH06-21 5-Dac 3 10-15 GW				T 0		Jan Co	CAp-						10000	(0	
BH03-21 10:54 1 1 14 14 14 15 16 16 17 17 18 16 17 18 16 17 18 16 17 18 16 17 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 16 18 18 16 18 18 18 18 18 18 18 18 18 18 18 18 18	Sample Barcode Label			~	- 1		2						11	Somm	01110
BHOS-21		BH06-21	5-LE	(2) 10:15	GW		V						14	- (1) . Free (Fr)	
BH0S-21		BH03-21		10:54			V						4		
BH01-21 13:25 / 4 BH01-21 V H:01 V / 4	. " .	BH 02-21		12-01			1						4		
BH01-21 13:25 / 4 BH01-21 V H:01 V / H:01 P Received In		BH05-21		12=46		1	V						4		
BH01-21 V H:01 V V Received In		BH04-21				T A	1			V		-	4		
Received In		BH01-21	6	/	A		1			1			4		1. 30
WATERLOO				1100										Received In	
														WATERLO	0
	107	P. C.													
RELINQUISHED BY: (Signature/Print) Date: (YY/MM/DD) Time RECEIVED BY: (Signature/Print) Date: (YY/MM/DD) Time # jars used and Laboratory Use Only	PELINOUISHED BY	(Signature/Print) Da	te: (YY/MM/DD)	Time	. A RECEIVED	BY: (Signature)	Print)	Date: (YY/MM	(DD)	Time	# jars used and		Labor	atory Use Only	
Man Baras / JANDEN/HOFF 23/17/05 6:0 33 KINDAN PAPE 2023 IP 05 IS 13 9 not submitted Time Sensitive Temperature (°C) on Recei Custody Seal	// NEEMIGOURIED DI.						ATI	- CONTROL MAINTENANCE					Tempera	ture (°C) on Recei	al Yes
Present	Van Aspail WA	The state of the s	W		in of Kard	RUBINA	SE VAN	c 2022/12/		:05			(L	H6°C. Present	

HYDROGEOLOGICAL ASSESSMENT, STROHVEST SUBDIVISION, TOWNSHIP OF WELLESLEY, ONTARIO

APPENDIX J: Test Pit Photographs



Photo 1: TP01-24 (May 2, 2024). Looking southeast towards Gerber Road.



Photo 3: TP01-24 (May 3, 2024). Western face of test pit.



Photo 2: TP01-24 (May 3, 2024, after 24 hours of being excavated) Looking southeast towards Gerber Road.



Photo 4: TP01-24 (May 3, 2024). Western face of test pit. From top of dashed white line to test pit bottom the wall is "sweating", an indication that groundwater is very slowly seeping from the wall.








Photo 5: TP02-24 (May 2, 2024). Looking to the northwest.



Photo 7: TP02-24 (May 3, 2024). Looking at north face of test pit.



Photo 6: TP02-24 (May 3, 2024, after 24 hours of being excavated).

Looking to the northwest. Note that soil sloughing of the test pit walls has occurred



Photo 8: TP02-24 (May 3, 2024). Note that from an approximate depth of 1.0 m BGS to base of pit (4.0 m BGS) the wall is "sweating", an indication that groundwater is very slowly seeping from the wall.








Photo 9: TP03-24 (May 2, 2024). Looking to the northwest.



Photo 11: TP03-24 (May 2, 2024). Looking at east face of test pit. Seeping sand seam present in southeast corner of the test pit (marked by 'X').




Photo 10: TP03-24 (May 2, 2024). Beginnings of seeping / flowing sand seam in southeast corner of the test pit.



Photo 12: TP03-24 (May 3, 2024, after 24 hours of being excavated).

Note that soil sloughing of the test pit walls have occurred.

Standing water is a byproduct of sand seam drainage.

Client/Project	Month Year
Client	Project Number
Project Name	
Appendix	Page
J	3 of 5
Title	





Photo 13: TP04-24 (May 2, 2024). Looking at east face of test pit. Observed draining of gravelly sand seam into test pit at time of excavation.



Photo 15: TP04-24 (May 3, 2024). Looking south towards Gerber Road. Standing water is a byproduct of gravelly sand seam drainage.



Photo 14: TP04-24 (May 3, 2024, after 24 hours of being excavated). Standing water is a byproduct of gravelly sand seam drainage.



Photo 16: TP04-24 (May 3, 2024). Looking east towards existing residential subdivision.

Client/Project	Month Year
Client	Project Number
Project Name	
Appendix	Page
J	4 of 5
Title	
PHOTOGRAPHIC RECORD	





Photo 17: TP05-24 (May 2, 2024). Looking to the northwest.



Photo 19: TP05-24 (May 3, 2024). Looking to the northeast. Note that soil sloughing of the test pit walls have occurred. Standing water is a byproduct of sand seam drainage.




Photo 18: TP05-24 (May 3, 2024, after 16 hours of being excavated).

Looking to the northwest. Below dashed white line the test pit wall is "sweating". Seepage (flow) from sand seam marked by 'X'.



Photo 20: TP05-24 (May 3, 2024, after 24 hours of being excavated).

Looking to the northwest. Note that seepage from sand seam had stopped (i.e., drained out).

Project Number
Page
5 of 5

